

DOCUMENT RESUME

ED 069 254

HE 003 581

TITLE A Comparison of the Costs of Building Elements
 Related to Design Requirements for Selected
 University and Non-University Buildings in Ontario.
 Volume 4.

INSTITUTION Council of Ontario Universities, Toronto.

PUB DATE Jul 72

NOTE 254p.; Report of the Task Force on Building Costs,
 Report 72-12

EDRS PRICE MF-\$0.65 HC-\$9.87

DESCRIPTORS *Buildings; *College Buildings; *Cost Effectiveness;
 *Educational Economics; *Higher Education;
 International Education

ABSTRACT

The Committee on Capital Financing of the Council of Ontario Universities set up the Task Force on Building Costs in June 1971 to analyze in detail comparative building cost data. The first phase of the study involved describing and comparing in detail the initial costs and design requirements of a group of university and non-university buildings. The second phase is to investigate long-term cost and performance factors, including costs of maintenance and operation, and the effectiveness of the buildings in use. This report covers only the first phase of the study, the specific objectives of which were: (1) to develop an understanding of the components of cost in university and non-university buildings; (2) to develop and utilize a methodology that will enable the ready comparison of components of cost; and (3) to provide the necessary descriptive information so that a cost/design comparison might be undertaken. Also included is an extensive supplement that contains the elemental cost analysis and performance and statistical data on which the report is based. (Author/HS)

Council of Ontario Universities
Conseil des Universités de l'Ontario



Building Blocks

Background Studies on the Development
of a Capital Formula for Ontario

VOLUME 4


Report of the Task Force BUILDING COSTS

17
16
15
14
13
12
11
10
9
8
7
6
5
4
3
2
1



**U.S. DEPARTMENT OF HEALTH
EDUCATION & WELFARE
OFFICE OF EDUCATION**

THIS DOCUMENT HAS BEEN REPRODUCED EXACTLY AS RECEIVED FROM THE PERSON OR ORGANIZATION ORIGINATING IT. POINTS OF VIEW OR OPINIONS STATED DO NOT NECESSARILY REPRESENT OFFICIAL OFFICE OF EDUCATION POSITION OR POLICY.



HE 0035587

ED 069254

REPORT OF
THE TASK FORCE - BUILDING COSTS

A COMPARISON OF THE COSTS OF BUILDING ELEMENTS RELATED
TO DESIGN REQUIREMENTS FOR SELECTED UNIVERSITY
AND NON-UNIVERSITY BUILDINGS IN ONTARIO

The Council of Ontario Universities
Conseil des Universités de l'Ontario
102 Bloor Street West
Toronto 181, Ontario

72-12
July 1972

TASK FORCE - BUILDING COSTS

Commissioner/Director,
Mr. C. Arnold,
Vice President, Building Systems Development,
San Francisco, California.

Mr. H. Graupner,
Head, Planning Department,
University of Guelph.

Mr. W. Morgan,
Director, Physical Plant and Planning,
University of Windsor.

Mr. A.R. Dawson,
Director, Campus Planning,
York University.

Mr. D.M. Hedden,
Vice President, Administration,
McMaster University.

Dr. G.R. Love,
Chairman, Committee on Capital Financing,
Carleton University.

Mr. J. Whenham,
Secretary, Committee on Capital Financing,
Carleton University.

Mr. I.W. Thompson,
Secretary 1971,
Council of Ontario Universities.

Mr. T. Da Silva,
Secretary 1972,
Council of Ontario Universities.

Hanscomb-Roy Associates,
Consultant,
Mr. B. Bowen, Partner-in-Charge,
Mr. S. Donnell, Project Leader.

The Task Force on Building Costs wishes to acknowledge the help of all those who provided information for this study. Special thanks are due to the architectural services branch of the Ministry of Colleges and Universities, the physical planning staffs of the universities, and the architects of all the buildings studied. The cooperation of the owners of the non-university buildings is particularly appreciated.

PREFACE

The Report of the Task Force - Building Costs has been received by the Committee on Capital Financing and its parent body, the Council of Ontario Universities. On the basis of recommendations from the Committee on Capital Financing, the Council at its meeting on June 2, 1972, agreed:

- a. to accept the Report as a basis for negotiation with the Committee on University Affairs in reviewing the cost component of the capital formula;
- b. to approve recommendations 6 and 7 of the Report (page 4);
- c. to commend to member institutions recommendations 3 and 4 of the Report (page 4);
- d. to refer to the Committee on Capital Financing and the Ontario Association of Physical Plant and Planning Administrators, for further consideration and advice, recommendations 1, 2 and 5 of the Report (pages 3 and 4). In particular the Committee on Capital Financing was requested to develop and submit to COU a specific proposal for Phase II of the study.

COUNCIL OF ONTARIO UNIVERSITIES | 102 BLOOR STREET WEST
CONSEIL DES UNIVERSITÉS DE L'ONTARIO | TORONTO 1S1, ONTARIO
| (416) 920-6365

ERRATA

1. p. 20. Floor plan title should read:
Mathematics and Computer Building,
University of Waterloo
2. p. 21. Photograph title should read:
Mathematics and Computer Building,
University of Waterloo

CONTENTS

	PAGE
SUMMARY	1
1. INTRODUCTION	5
a. Origins of the Building Cost Study	
b. Objectives and Scope	
2. GENERAL DESCRIPTION OF THE METHODOLOGY EMPLOYED	7
a. Methods of Analysis	
b. Selection of Samples	
c. The Buildings Studied	
Table 1. Building Areas, Volumes and Total Costs	
Table 2. Building Unit Costs	
Table 3. Costs by Building Element	
3. FINDINGS	39
4. DETAILED SAMPLE STUDIES	49
a. Comparison of the Petrie Science Building and the Food and Drug Laboratory	
b. Comparison of the Law Building, the General Purpose Office Building and the Varette Office Building	
c. Comparison of the Mathematics and Computer Building, the Systems Dimension Limited Building and the Northern Electric Laboratory	
d. Comments on other buildings	
5. ADDITIONAL TABLES	61
Table 4. Configuration Ratios	
Table 5. Percentage Distribution of Net Assignable Area by Function	
Table 6. Shell, Services and Other Elemental Costs	
Table 7. HVAC and Plumbing Costs	

	PAGE
6. COST ANALYSIS-ISSUES	66
a. The Interim Capital Formula	
b. Cost Escalation	
c. Measurement of Assignable Area	
d. University Design Requirements	
e. University Identity	
7. RECOMMENDATIONS	73
8. METHODOLOGY	76
a. Gross Building Samples	
b. Rules for Measurement of Areas	
c. Element Descriptions	
9. GLOSSARY	86

BUILDING COST AND DESIGN REQUIREMENTS

SUMMARY

The Committee on Capital Financing of the Council of Ontario Universities set up the Task Force on Building Costs in June 1971 in order to analyse in more detail comparative building cost data such as that contained in the report "Cost Study: Interim report to the Committee on University Affairs", prepared by the Department of Colleges and Universities in December 1970. Such an analysis, would also provide data to universities, and be of great use in decision making associated with new building design and construction. A two-phase study was envisioned. The first phase would describe and compare in detail the initial costs and design requirements of a group of university and non-university buildings. The second phase would investigate long-term cost and performance factors, including costs of maintenance and operation, and the effectiveness of the buildings in use. This report covers only the first phase, the specific objectives of which were as follows:

- (1) To develop an understanding of the components of cost in university and non-university buildings.
- (2) To develop and utilize a methodology that will enable the ready comparison of components of cost.
- (3) To provide the necessary descriptive information so that a cost/design comparison might be undertaken.

The study was concerned with the following major types of assignable space:

- (1) Offices
- (2) Classrooms
- (3) Teaching laboratories
- (4) Research laboratories

The method of analysis used was to arrive at building costs by re-estimating the cost of each building component, using actual cost for general validation and reconciliation. Costs were estimated as at one place and at one time viz, Toronto, last quarter 1971.

From a gross sample of about 80 buildings, the selection process produced a sample of six university and six non-university buildings. The selected sample, and the costs of the buildings, were as follows:

Summary...

- 2 -

Highest costs underlined, lowest costs underlined.

<u>University Buildings</u>	<u>Rank</u>	<u>Cost/GSF*</u>	<u>Cost/NASF*</u>
Child Study Center (Ottawa)	4	\$33.61	\$54.28
Law Building (Windsor)	6	<u>27.85</u>	<u>45.33</u>
Crop Science Building (Guelph)	1	<u>42.39</u>	<u>71.27</u>
Petrie Science Building (York)	3	<u>34.74</u>	<u>60.92</u>
Maths & Computer Building (Waterloo)	7	24.26	38.38
Engineering IV (Waterloo)	2	<u>36.80</u>	<u>62.33</u>

<u>Non-University Buildings</u>			
Northern Electric Laboratory (Toronto)	8	24.14	32.56
Systems Dimension Limited Building (Ottawa)	10	22.58	<u>29.17</u>
Varette Office Building (Ottawa)	12	<u>14.73</u>	<u>**</u>
General Purpose Office Building (Ottawa)	11	17.17	<u>**</u>
Food & Drug Laboratory (Toronto)	5	32.04	62.86
Georgian CAAT (IIIA) (Barrie)	9	23.93	34.17

The analysis of elemental costs and design requirements resulted in the following findings:

- a. Based on this sample, where university and non-university buildings have approximately like functions, mixes of space, and are similar in size, their costs were found to be comparable.
- b. The cheapest buildings within the range studied were ones that were very large, very repetitive, very simple in plan form, and responded to a single generalized function, such as the provision of undifferentiated office space.
- c. The combination of shell and services costs effectively decides the cost magnitude of the building. A high cost in these two groups of elements cannot be offset by low costs elsewhere.
- d. The cost of services varies more than the cost of the shell, and is also a high cost element, hence it may exert more influence on the overall cost of the building than the shell: shell costs range from \$13.30 to \$4.82/GSF, or 3:1, and service costs range from \$20.81 to \$5.16/GSF, or 4:1.
- e. The cost of interior finishes, including walls, floor and ceiling, has minimal effect on the overall cost of the building.
- f. There is a great variation in fixtures and fittings cost. This variation is a direct result of the programmatic functions of the building.

* See Glossary for definitions of G.S.F. and N.A.S.F.

** NASF figures not applicable: see Section 6c for explanation

NOTE: Federal Tax rebate not deducted from University Projects costs.

- g. Indirect costs of university buildings in this sample average \$1.19/GSF greater than non-university buildings.
- h. The overall cost of buildings is not consistent with the costs of their individual elements. A low-cost building may have some elements that are high in cost and, conversely, a high-cost building may have some low-cost elements within it.
- i. There is a wider range of element costs than building costs. This finding confirms the need to look closely at element costs in order to gain understanding of the cost characteristics of a building.
- j. Higher performance requirements cost more, and the study shows the magnitude of some of these costs, and also shows the complexity of the variables that influence the cost design relationship.
- k. University buildings generally cost more because of a conscious attempt to provide good exterior quality and a university identity: this extra cost for the sample of buildings is approximately in the range of \$1.10 to \$1.73/GSF.

The Task Force also reviewed the development of a capital formula dollar allowance that would vary, depending on the type of building under consideration. However, it was agreed that the formula dollar allowance should remain a single, average figure, primarily because the single figure allows for more flexibility and is simpler to administer.

The study suggests that escalation of building costs of the studied sample was about 50% less than would be indicated by the Southam Index.

The Task Force study concluded with the following recommendations: *

- 1. The systematic cost/design analysis developed in this study should be applied to the continuing university construction program. In this way, a body of coherent building information will be developed which will be of immense value for future planning and cost control.
- 2. The cost/design information developed in this study provides essential data which could form the basis for the development of an appropriate systems building program for the Ontario University system. A study should be instituted to determine the objectives for future university buildings, to establish the cost/benefit parameters for such a program, to outline feasible alternative kinds of system programs, and to estimate potential benefits and constraints of such programs.

*For an elaboration of these recommendations, see page 47

3. The data in this report provides a basis for establishing design and cost guidelines, for all building elements, to assist university architects and engineers. These guidelines should be developed by each university.
4. Each university should initially concentrate on setting guidelines for the cost characteristics of the shell of future projects.
5. The second phase of the study should be immediately implemented to include the study of life costs, including costs of maintenance, operations and change, and to analyse the validity of programmatic needs that result in higher design requirements and higher cost elements for buildings.
6. The capital formula dollar allowance should be formally reviewed annually by a joint DCU/COU staff committee not only to take escalation into account, but also new information arising from on-going studies and further experience.
7. Because even the most conservative estimates of a capital formula dollar allowance exceeds \$55/NASF an upward adjustment should be made in the present unit cost allowance.

In addition to this report, a second publication is envisaged. It will consist exclusively of the detailed building cost data derived and used in the study. Readers wishing to delve further into the data base of the study should obtain copies of this publication which is expected to be available by August 30, 1972.

1. INTRODUCTION

a. Origins of the Building Cost Study

The Committee on Capital Financing (CCF) of the Council of Ontario Universities (COU) set up the Task Force on Building Costs in June 1971 in order to analyse in more detail comparative building cost data such as that contained in the report "Cost Study: Interim report to the Committee on University Affairs", prepared by the Department of Colleges and Universities (DCU) in December 1970. Such an analysis would also provide data to universities and be of great use in decision making associated with new building design and construction. The DCU study was the first to demonstrate the difference between costs of Ontario University buildings, as a group and costs of a number of non-university buildings. However, it did not attempt to show in detail what makes up the cost of a building or to systematically explain the cause of the demonstrated difference. It did not analyse the design requirements of the buildings for which costs were being compared.

The intention of the COU Task Force was to carry out these analyses as an amplification of and a complement to the DCU study. The CCF envisaged a two-phase effort for this study. First, an examination and analysis of the average unit costs of university and comparable non-university buildings would be undertaken. Second, explanations of any differences brought to light and recommendations as to the standards to which universities in Ontario should build in the immediate future would be made. This latter phase, a much more complex and difficult one, was thought to require a critical examination of costs over the lifetimes of the buildings, not just initial costs. The CCF went on to recommend that the Ontario Association of Physical Plant and Planning Administrators (OAPPPA) be asked to propose the membership of a group to undertake the first phase and a methodology for carrying out the first step, with the aid of outside consultants engaged and paid for by the Council of Ontario Universities (COU).

The CCF report was presented at the May 14 meeting of COU by Dr. Ross Love. In the ensuing discussion of the proposal, the Committee agreed that the building cost study should proceed under COU auspices, that the Committee on University Affairs (CUA) and DCU should be kept informed about its progress, and that CUA should be invited to express its views concerning the building and cost comparisons employed in the study.

Subsequently, the Executive Director of COU wrote to Dr. Wright, the Chairman of CUA, informing him of the proposed building cost study and soliciting his views on the subject. Dr. Wright in reply stated that any competent work in the area of building costs analysis would be of value.

At the following meeting of COU on June 11, 1971, Dr. Love presented the views of the CCF regarding the conduct of the study. It was the opinion of the CCF that the Task Force on Building Costs should be composed of a commissioner-director, a five-man steering committee and a firm of cost consultants and the responsibilities of each member group were stated. Three of the five members on the steering committee were to be appointed by the OAPPPA and two by the CCF. It was intended that the commissioner-director would be appointed by the CCF and, following this, the cost consultant

appointed jointly by the commissioner-director and the steering committee. The three members of the steering committee appointed by the OAPPPA were Mr. Ross Dawson of York University, Mr. Henry Graupner of the University of Guelph, and Mr. William Morgan of the University of Windsor, while the CCF appointed Mr. Michael Hedden of McMaster University and Dr. Ross Love of Carleton University, the latter being expected to serve as chairman and coordinator in the absence of the commissioner-director.

On June 30, 1971, Mr. Christopher Arnold of Building Systems Development, San Francisco, was offered and accepted the position of commissioner-director, and on August 24, 1971, the firm of Hanscomb-Roy Associates was retained as consultant for the project.

b. Objectives and Scope

On July 27, 1971, the members of the task force convened to make explicit the terms of reference, the objectives, the scope and depth of the study, and the responsibilities of those involved. The terms of reference agreed upon were as follows:

- (1) To document the costs of university buildings.
- (2) To audit the university buildings to be included in the study.
- (3) To document and analyze the costs of the various components of university buildings.
- (4) To select, document and analyze the costs of non-university buildings to be included in the study.

The specific objectives of the first phase of the study were defined to be:

- (1) To develop an understanding of the components of cost in university and non-university buildings.
- (2) To develop and utilize a methodology that will enable the ready comparison of components of cost of university and non-university buildings.
- (3) To provide the necessary descriptive information so that a cost/design comparison may be undertaken.

Two of the major aspects of the study to be considered were the type and the number of buildings to be included. After some deliberation buildings containing the following major types of space were accepted for inclusion:

- (1) Office space
- (2) Classrooms
- (3) Teaching laboratories
- (4) Research laboratories.

Special-purpose buildings such as gymnasiums were excluded, and it was recognized that the final selection of building types might be dependent on the non-university buildings available for study.

Subsequently, a sub-sample of six non-university buildings was chosen for detailed study.

The use of a sample of twelve buildings was primarily the result of limited time and resources. It was recognized that such a small sample would not provide results of any precise statistical validity and the results have not been interpreted in detail on a statistical basis, nor have general conclusions been arrived at on this basis. However, the use of a small sample enables each building to be analyzed and compared with others in depth on an individual basis.

In addition, since the DCU list was limited both in total number of buildings (approximately 40) and in the types of buildings, the list was expanded by the addition of several other buildings before the sample of six buildings was selected. The university buildings considered for inclusion are shown in Section 8a.

- The method of selecting a sub-sample of six university buildings for further study was as follows: The DCU Project Cost Space Record for each project was used to review and subjectively classify the projects into two categories, viz: light and heavy service.* Next, the cost per net assignable square foot of each building in the two categories was adjusted by the Composite Southam Construction Index, Ontario Series, to August 1971, and separately ranked for each category in descending order of adjusted unit cost. The Southam index was used only for this preliminary selection process. Finally, from each of the two lists the 25th, 50th and 75th percentile buildings were selected.

The consultants were then provided with the following information for each of the buildings selected:

- (1) Tender set of working drawings
- (2) Tender building specifications and all relevant addenda.
- (3) Tender form submitted by the successful contractor.
- (4) Contractors' progress payment schedule.
- (5) All other relevant documents pertaining to cost.
- (6) Bid record sheet indicating spread of bids.

In addition to the above, basic performance information about each building was collected on a form prepared by the commissioner-director and the consultant.

The procedure for selecting a sub-sample of six non-university buildings differed from that employed for university buildings in that cost per gross square foot was used as the ranking basis instead of cost per net assignable square foot. This was necessary because only data on gross square footage were available for all of the non-university buildings. In addition, detailed information on non-university buildings, particularly in the heavy-service category, was relatively scarce. It was not possible, within the time and resources available for the study, to develop a gross sample, as for the university buildings, and select buildings on a percentile basis. Hence, buildings were selected by inspection on the basis that they conformed to the following criteria:

* For preliminary selection, light and heavy service were defined by the title of the building, with science and engineering buildings assumed to be heavy service buildings.

2. GENERAL DESCRIPTION OF THE METHODOLOGY EMPLOYED

a. Methods of Analysis

Two alternate cost analysis methodologies were considered and discussed. The first method was to arrive at the building cost by re-estimating the cost of each building component, using actual cost for general validation and reconciliation. This method has the advantages of uniformity of estimating and of assumptions, and can be used where actual costs are not reliable or are suspect. In addition, cost differentials between projects due to time and location variables are eliminated. Disadvantages may be a lack of credibility, since the basic comparisons of elements are based on estimates rather than a contractor's breakdown.

The second method is to work back from the actual cost and the contractor's breakdown. This method has the advantage of using known costs as a base and gains in credibility. Disadvantages include questions of the reliability of contractor's breakdown and the validity of cost information of some private work, the difficulties of interpretation and translation of trade breakdowns into elemental costs, and the extreme difficulty of isolating time and location cost variables for comparison purposes. The question of differences in cost arising out of geographical location was not considered, not because the differences are not real or important but because of limitations on the time and resources available to the Task Force. Thus the method of estimating building costs used in this report deliberately excludes any attempt to compensate for differences in geographical location.

After much discussion, the first approach was chosen. Thus the method of cost analysis was to:

- (1) Estimate projects from scratch, on an elemental cost basis.
- (2) Use known cost as validation and control.
- (3) Estimate as at one place and at one time viz, Toronto last quarter 1971.

b. Selection of Samples

The next step was to select a sub-sample from a gross sample of 39 university buildings included in the DCU study. The sub-sample consisted of six university buildings to be analysed in detail while the gross sample conformed to the following criteria:

- (1) Only buildings costing over \$1,000,000 were included.
- (2) Only buildings included in the DCU categories of Administration, Science, Engineering, Arts, Law and Education were regarded as candidates for inclusion.
- (3) Only buildings tendered from 1966 to the present were included in the first selection; buildings in the sub-sample must have been occupied by April 1, 1971.
- (4) Buildings were not additions or extensions to existing buildings.*
- (5) Buildings did not have unusual features of design, site condition, or other characteristics that might make comparison unrepresentative.

* This criterion was waived in the case of the Engineering IV Building (Wa35). This is a large extension to an existing building and was judged discrete and large enough to be included. **14**

- (1) The detailed information noted above was available for each building.
- (2) Only buildings costing over \$1,000,000 were included.
- (3) Buildings selected fitted one of the following categories:
 - (a) Owner-occupied commercial office.
 - (b) Speculative commercial office.
 - (c) Research laboratory - Commercial
 - (d) Research laboratory - Government/Institutional.
 - (e) Office building - Government
 - (f) High school/College of Applied Arts & Technology (CAAT)/Vocational school
- (4) Buildings were tendered during the period 1966 to the present and occupied by April 1, 1971. *
- (5) Buildings were not additions or extensions to existing buildings.
- (6) Buildings did not have unusual features of design, site condition, or other characteristics that might make comparison unrepresentative.

The gross sample of non-university buildings was gathered from a variety of sources, including the Federal Public Works Department, the Provincial Government, Atomic Energy of Canada Ltd., the Ontario Department of Education, the Toronto Board of Education and from projects known or worked on by the consultants. Section 8a shows the non-university buildings considered for inclusion in the detailed sample.

c. The Buildings Studied

The twelve buildings studied in detail are as follows:

University buildings:

Ottawa 34 - Child Study Center Building
Windsor 24 - Law Building
Guelph 04 - Crop Science Building
York 26 - Petrie Science Building
Waterloo 17 - Mathematics and Computer Building
Waterloo 35 - Engineering IV Building

Non-university buildings:

Northern Electric Laboratory - Toronto
Systems Dimensions Limited Building - Ottawa
Varette Office Building - Ottawa
General Purpose Office Building - Ottawa
Food and Drug Building - Toronto
Georgian CAAT (IIIA) - Barrie


The university buildings were specially visited by a majority of the Task Force and all of the buildings were visited by at least one member of the Task Force.

* Because of the difficulties in procuring adequate information in the time available, this criterion was waived in the case of the Food and Drug Building, which was tendered on November 1971.

For identification purposes a general exterior photograph and a plan of a typical floor are shown. In two cases, the General Purpose Office Building and Varette, a drawing is shown instead of a photograph. No plans or photographs of the Food and Drug Laboratory were available. The names of the architect and general contractor for each building are also provided.

- 11 -

PLANS AND PHOTOGRAPHS OF ELEVEN
OF THE TWELVE BUILDINGS STUDIED




3

Child Study Centre, University of Ottawa

Architects: Schoeler, Heaton, Harvor, Menendez, Ottawa


General Contractor: Admiral Engineering and Construction Ltd., Ottawa

GROUND FLOOR PLAN



Faculty of Law Building, University of Windsor


Architects: Gordon S. Adamson and Associates, Toronto
General Contractor: W.A. McDougall Ltd., London



Child Study Centre, University of Ottawa


Architects: Schoeler, Heaton, Harvor, Menendez, Ottawa

General Contractor: Admiral Engineering and Construction Ltd., Ottawa



Faculty of Law Building, University of Windsor

Architects: Gordon S. Adamson and Associates, Toronto
General Contractor: W.A. McDougall Ltd., London



Crop Science Building, University of Guelph

Architects: Herbert Agnew Associates, Toronto


General Contractor: E.G.M. Cape & Company (1956) Ltd., Toronto



Crop Science Building, University of Guelph

Architects: Herbert Agnew Associates, Toronto


General Contractor: E.G.M. Cape & Company (1956) Ltd., Toronto



Petrie Science Building, York University


Architects: U.P.A.C.E., Toronto


General Contractor: Eastern Construction Company Limited, Toronto



Petrie Science Building, York University


Architects: U.P.A.C.E., Toronto
General Contractor: Eastern Construction Company Limited, Toronto





Mathematics and Computer Building, University of Toronto

Architects: Webb, Zerafa, Menkes & Matthews, Toronto
General Contractor: Ellis-Don Limited, London




Engineering IV Building, University of Waterloo

Consulting Engineers: Giffels Associates Limited, Toronto
General Contractor: Ellis-Don Limited, London



Engineering IV Building, University of Waterloo


Consulting Engineers: Giffels Associates Limited, Toronto
General Contractor: Ellis-Don Limited, London



Northern Electric Branch Laboratory, Toronto

Architects: Gordon S. Adamson & Associates, Toronto


General Contractor: The Mitchell Construction Company (Canada)



Northern Electric Branch Laboratory, Toronto

Architects: Gordon S. Adamson & Associates, Toronto

General Contractor: The Mitchell Construction Company (Canada)



Systems Dimensions Limited Building, Ottawa

Architects: Murray & Murray, Ottawa


General Contractor: L'Abbe Construction Ltd., Ottawa



Systems Dimensions Limited Building, Ottawa


Architects: Murray & Murray, Ottawa

General Contractor: L'Abbe Construction Ltd., Ottawa



Varette Office Building, Ottawa


Architects: Craig & Kohler, Ottawa
General Contractor: Owner Built



Varette Office Building, Ottawa

ALBERT STREET ELEVATION


Architects: Craig & Kohler, Ottawa
General Contractor: Owner Built



General Purpose Office Building, Ottawa

Architects: Ronald Ogilvie, Ottawa

General Contractor: Argo Construction Ltd., Montreal



GENERAL PURPOSE OFFICE BUILDING
TUNNEYS PASTURE OTTAWA

RONALD OGILVIE architect

General Purpose Office Building, Ottawa

Architect: Ronald Ogilvie, Ottawa

General Contractor: Argo Construction Ltd., Montreal

Food & Drug Laboratory, Toronto


Architects: Department of Public Works, Ottawa
Robbie, Vaughan & Williams, Toronto

General Contractor: West York Construction Ltd., Toronto

Food & Drug Laboratory, Toronto

Architects: Department of Public Works, Ottawa
Robbie, Vaughan & Williams, Toronto

General Contractor: West York Construction Ltd., Toronto



Georgian College of Applied Arts and Technology, Phase IIIA, Barrie

Architects: Page & Steele, Toronto
Salter & Allison, Barrie

General Contractor: M & D Kennedy Contractors Limited, Barrie



Georgian College of Applied Arts and Technology, Phase IIIA, Barrie

Architects: Page & Steele, Toronto
Salter & Allison, Barrie

General Contractor: M & D Kennedy Contractors Limited, Barrie

BUILDING AREAS, VOLUMES AND TOTAL COSTS

TABLE 1

<u>University Buildings</u>	<u>Area/GSF</u>	<u>Volume (CF.)</u>	<u>1971 Cost (incl. Federal Sales Tax)</u>
Child Study Center	58,150	670,000	1,954,360
Law Building	85,140	1,214,843	2,371,080
Crop Science Building	106,069	1,415,760	4,496,050
Petrie Science Building	131,000	1,639,620	4,551,370
Math & Computer Building	299,736	3,825,000	7,258,520
Engineering IV	170,900	2,505,000	6,289,300
<u>Non-University Buildings</u>			
Northern Electric Laboratory	90,147	1,329,125	2,175,800
Systems Dimensions Limited Building	102,930	1,407,220	2,314,030
Varette Office Building	317,400	3,293,753	4,675,990
General Purpose Office Building	433,410	4,848,413	7,440,480
Food & Drug Laboratory	105,675	1,327,832	3,385,900
Georgian CAAT (IIIA)	43,140	621,440	1,032,260
	1,943,697	24,098,006	\$47,945,140

NOTE: All costs normalized to Toronto, last quarter, 1971

TABLE 2

BUILDING UNIT COSTS

(Highest costs underlined. Lowest costs underlined.)

<u>University Buildings</u>	<u>Cost/ GSF</u>	<u>Rank</u>	<u>Cost/ NASF</u>	<u>Rank</u>	<u>Cost/ CF</u>
Child Study Center	\$33.61	4	\$54.28	2	\$2.92
Law Building	27.85	6	45.33	6	1.95
Crop Science Building	<u>42.39</u>	1	<u>71.27</u>	1	<u>3.18</u>
Petrie Science Building	34.74	3	60.92	3	2.78
Maths & Computer Building	24.26	7	38.38	7	1.90
Engineering IV	36.80	2	62.33	5	2.52
<u>Non-University Buildings</u>					
Northern Electric Laboratory	24.14	8	32.56	9	1.64
Systems Dimensions Limited Building	22.58	10	29.17	10	1.64
Varette Office Building	<u>14.73</u>	12	*	12	<u>1.42</u>
General Purpose Office Building	<u>17.17</u>	11	*	11	<u>1.53</u>
Food & Drug Laboratory	32.04	5	62.86	4	2.55
Georgian CAAT (IIIA)	23.93	9	34.17	8	1.66

NOTE: Federal Tax rebate not deducted from University Projects costs.

All costs normalized to Toronto, last quarter 1971

* NASF figures not applicable: see Section 6c for explanation

COSTS BY BUILDING ELEMENT. (Dollars/GSF and Percentages of Total Cost.)

(Highest costs underlined. Lowest costs underlined)

	Overall Cost	1. Indirect & General %	2. Sub-structure %	3. Horizontal Structure %	4. Exterior Cladding %	5. Interior Vertical %	6. Multi-story Elements %
<u>University Buildings</u>							
Child Study Center	4	3.04	9.0	1.02	3.0	3.84	11.5
Law Building	6	2.53	9.1	1.20	4.3	6.03	21.6
Crop Science Building	<u>1</u>	<u>3.61</u>	8.5	1.47	3.5	<u>5.88</u>	13.9
Petrie Science Building	<u>3</u>	<u>2.95</u>	8.5	0.43	1.2	4.75	13.7
Maths & Computer Building	8	2.20	9.1	0.79	3.3	4.25	17.5
Engineering IV	2	2.75	7.5	1.49	4.0	6.01	16.3
<u>Non-University Buildings</u>							
Northern Electric Laboratory	9	1.77	7.3	0.52	2.1	4.43	18.4
Systems Dimensions Ltd. Building	10	1.76	7.8	0.24	1.1	3.94	17.5
Varette Office Building	12	<u>1.06</u>	7.2	0.32	2.2	<u>2.03</u>	13.8
General Purpose Office Building	11	<u>1.13</u>	6.6	<u>0.12</u>	0.7	<u>2.38</u>	14.0
Food & Drug Laboratory	5	1.83	5.7	0.79	2.4	3.50	11.0
Georgian CAAT (IIIA)	7	1.76	7.4	0.54	2.2	3.96	16.6
7. Interior Finishes							
8. Fittings & Fixtures							
9. Cash Allow.							
10. Plumbing & Drains							
11. HVAC							
12. Electrical							
<u>University Buildings</u>							
Child Study Center	<u>3.13</u>	9.3	0.99	3.0	<u>0.89</u>	2.6	1.92
Law Building	<u>2.72</u>	9.8	0.77	2.8	<u>0.44</u>	1.6	<u>0.72</u>
Crop Science Building	2.06	4.9	3.31	7.8	0.39	0.9	<u>2.64</u>
Petrie Science Building	1.47	4.2	<u>4.28</u>	12.3	0.57	1.6	2.11
Maths & Computer Building	1.78	7.3	0.78	3.2	0.60	2.5	0.91
Engineering IV	1.96	7.3	3.01	8.2	0.65	1.8	1.84
<u>Non-University Buildings</u>							
Northern Electric Laboratory	2.48	10.3	0.30	1.2	0.15	0.6	1.20
Systems Dimensions Ltd. Building	1.93	8.5	1.02	4.5	0.26	1.1	0.83
Varette Office Building	1.83	12.4	0.10	0.7	0.05	0.3	0.76
General Purpose Office Bldg.	1.67	9.7	<u>0.07</u>	0.4	<u>0.03</u>	0.2	0.81
Food & Drug Laboratory	<u>1.24</u>	3.8	<u>3.68</u>	11.5	<u>0.39</u>	1.2	<u>3.36</u>
Georgian CAAT (IIIA)	<u>2.08</u>	8.7	1.01	4.2	0.48	1.9	<u>1.68</u>

TABLE 3

- 38 -

Note: Federal tax rebate not deducted from University Projects Costs
All costs normalized to Toronto, last quarter 1971

TABLE 3

3. FINDINGS

Introduction

This study provides some clear and expressive information as to where the costs of building lie. In addition to elemental building costs information is provided on the nature of the design, construction, and composition of each element, and on the performance both of the building as a whole and of some of its elements. In order to budget and control costs for any building program, it is necessary to investigate the probable costs associated with the defined purpose of the building. Such investigation is in fact done, to some extent, during the budgeting, programming and design of any new building. The information presented here may make such single building studies more effective and more pointed and may also be used to enable campuses to set up guidelines or even cost targets related to certain building elements to which the architect and the engineer can respond.

Such information enables cost estimates to be put on factors which, although well known in general, can typically only be discussed across a conference table in terms of general assertions. The more information of the kind shown in this report is gathered, the more effective will become the questions that may be asked, and the trade-off studies that can be done.

Cost control is dependent upon an information base of consistent comparative information. This information must be available in sufficient detail to provide a basis for measuring the effectiveness of design alternatives. This study provides the methodology for such a data base, and also utilizes a sample large enough to reveal the effectiveness of such coherent comparative data.

- a. Based on this sample, where university and non-university buildings have approximately like functions, mixes of space, and are similar in size, their costs were found to be comparable.

Compare, for example, the Mathematics and Computer Building, the Systems Dimensions Limited Building, and the Northern Electric Laboratory Building:

	<u>GSF</u>	<u>Cost/GSF</u>	<u>Cost/NASF</u>	<u>Lab, Support and Data Process Space</u>
Mathematics and Computer Building	299,736	24.26	38.38	22.7%
Systems Dimensions Limited Building	90,147	24.14	29.17*	33.6%
Northern Electric Lab Building	102,930	22.58	32.56*	17.8%

*Both the Systems Dimensions Limited and Northern Electric Laboratory buildings have NASF/GSF ratios which, as discussed in section 6c, are not comparable to university buildings.

Compare also the Petrie Science Building and the Food and Drug Laboratory:

	<u>GSF</u>	<u>Cost/GSF</u>	<u>Cost/NASF</u>	<u>Lab., Support and Data Process Space</u>
Petrie Science Building	131,000	34.74	60.92	70.2%
Food and Drug Laboratory	105,675	32.04	62.86	51.0%

A detailed comparison of these groups of buildings is presented in section 4.

- b. The cheapest buildings within the range studied were ones that were very large, very repetitive, very simple in plan form, and responded to a single generalized function, such as the provision of undifferentiated office space.

This is a kind of building which, typically, the university does not build. It does not build very large buildings because of the growth pattern on campuses and related funding. It does not build single-function buildings, offices, and laboratories. Very often for programmatic reasons these spaces adjoin on the same floor, or are contained within the same building. For example:

	<u>GSF</u>	<u>Cost/GSF</u>	<u>Floors above grade</u>	<u>Office space</u>
General Purpose Office Building	433,410	17.17	22	92%*
Varette Office Building	317,400	14.73	19	78%*

Compare these two buildings with a lightly serviced university building, the Law Building:

	<u>GSF</u>	<u>Cost/GSF</u>	<u>Floors above grade</u>	
Law Building	85,140	27.85	2	
Law Building	11.8%	16.7%	16.5%	50.1%

A detailed comparison of these buildings is presented in section 4.

* These figures do not allow for circulation space within the office areas: the net assignable figure is not available.

- c. The combination of shell and service costs effectively decides the cost magnitude of the building. High costs in these two groups of elements cannot be offset by low costs elsewhere.

In the sample, the shell accounted for between 22.4% and 37.9% of the total cost of the building. The services accounted for between 21.8% and 34.5%. In combination, these two groups of elements account for between 44.2% and 72.4% of the total building cost.

	<u>Shell & Services Cost/GSF</u>	<u>Rank</u>	<u>Building Cost/GSF</u>	<u>Rank</u>
<u>University Buildings</u>				
Child Study Center	23.84	3	33.61	4
Law Building	20.33	6	27.85	6
Crop Science Building	31.64	1	42.39	1
Petrie Science Building	23.40	4	34.74	3
Mathematics and Computer Building	17.51	9	24.26	7
Engineering IV	27.10	2	36.80	2
<u>Non-University Buildings</u>				
Northern Electric Laboratory	19.44	7	24.14	8
Systems Dimensions Limited Building	16.89	10	22.58	10
Varette Office Building	9.98	12	14.73	12
General Purpose Office Building	12.47	11	17.17	11
Food and Drug Laboratory	23.27	5	32.04	5
Georgian CAAT (IIIA)	17.92	8	23.93	9

In this sample, a comparison of rank between the cost of Shell and Services/GSF and Building Cost/GSF showed only one instance of a two-point difference, and three instances of a one-point difference. The remaining ranks are identical.

The costs of the shell for university buildings ranged from \$8.89/GSF to \$13.30/GSF. For non-university buildings, the range was from \$4.82/GSF to \$8.31/GSF.

Services are predominantly the result of functional and programmatic requirements within the building. If certain kinds of research are to be performed in the building, certain kinds of services will be essential, and there is no escaping their cost. Shell costs, on the other hand, are relatively independent of program, which suggests that an effective way to attack costs, and at the same time have minimal effect on program functions, is to tackle the shell cost of the building. This point is developed further in the recommendations section. The costs of the exterior skin are also affected by the External Wall/GSF ratio; a simple plan form such as the General Purpose Office Building, with an Exterior Wall/GSF ratio of 0.31, can be compared to Engineering IV at 0.79. Thus Engineering IV has more than twice the perimeter wall/GSF.

Shell costs are the summation of costs for elements 2, 3 and 4, plus a percentage of element 1. Services costs are the summation of costs for elements 10, 11 and 12, plus a percentage of element 1.

- d. The cost of services varies more than the cost of the shell, and it is also a high cost element; hence it may exert more influence on the overall cost of the building than the shell; shell costs vary over a range of 3:1, while services costs vary over a range of 4:1.

One university building, the Crop Science Building, had service costs of \$20.81/GSF, or 140% of the entire cost of the Varette Building (\$14.73/GSF). These high service costs relate directly to the function of the building, i.e. advanced research, requiring special environmental conditions. For example, the Crop Science Building has large areas with 1500 foot-candle intensity lighting for plant growth experiments. In addition, the service costs include items that in another type of building might be costed as movable equipment, and hence not appear in this analysis.

However, in one sample building, the Food and Drug Laboratory, a very high service cost was counterbalanced by a very low shell cost and, in conjunction with average costs for other elements, resulted in an average cost for the building.

Comparison HVAC Element:

	<u>Tons Cooling/1000 GSF</u>	<u>%AC</u>	<u>CFM/GSF</u>	<u>BTU/HR/GSF</u>
Crop Science Building	5.7	100	2.43	102.4
Varette Office Building	1.58	67	0.41	26.4

- e. The cost of interior finishes of walls, floor and ceiling, has minimal effect on the overall cost of the building.

The building with the lowest-cost interior finishes in the study, the Food and Drug Laboratory, ranked fifth in overall placing. The building with the highest-cost interior finishes ranked fourth in overall cost. The highest-cost building ranked fifth in interior finishes cost, and the lowest-cost building ranked seventh.

This finding is of particular interest because it contradicts a popular impression of cost influence. The lay observer, seeing expensive wall or ceiling finishes, doors, paneling and the like, will often equate this with an expensive building. The study shows conclusively that this is not so.

The interior finishes element becomes complex to study when the variables of floor, ceiling, walls and special finishes are considered and related to intensity of use. This is particularly true as far as interior wall finishes are concerned, since the relative quantity of interior walls in the study varies from building to building, over a range of about 3:1. This

suggests that careful trade-off studies relating long-term maintenance costs to relative quantities of various materials are desirable; nevertheless, the general conclusion holds that the overall cost of finishes will have little effect on the overall cost of the building. This conclusion has a very important corollary, namely, that money spent in this element to reduce maintenance costs is money very well spent indeed, because relatively expensive low-maintenance materials will still have little inflationary effect on the overall cost of the building.

This is particularly important as a high proportion of the maintenance dollar is spent on cleaning, repairing and replacing interior finish materials.

f. This is a great variation in fixtures and fittings cost. This variation is a direct result of the functions of the building. It is also related to the method by which these items are procured, i.e., whether this figure shows in the building contract (and the drawings and specifications) or not.

The variation in fixtures and fittings cost was from \$0.07/GSF for the General Purpose Office Building to \$4.28/GSF for the Petrie Science Building.

Typically, university buildings have high figures, especially in labs. Note, however, that the Food and Drug Laboratory has a high figure (\$3.68/GSF) where Northern Electric Laboratory has a low one (\$0.30/GSF). Obviously, Northern Electric Laboratory fixtures and fittings cost does not show in this analysis, and so it is not comparable to the other buildings in this respect.

g. Indirect costs of university buildings in this sample average \$1.19/GSF greater than non-university buildings.

This element includes the general contractor's indirect and general expenses for items such as access to site, site accommodation, site protection, temporary services, clean-up, supervision, insurance and bonds, equipment and winter conditions, together with the contractor's fee, which represents a proportion of his head office overheads and his profit. Estimating these indirect costs is largely judgmental being directly related for the most part to the following factors:

- (a) The estimated time necessary (or available) for construction.
- (b) The estimated cost of the project.
- (c) The nature, complexity and quality of the work.
- (d) The anticipated level of supervision and administration to be exercised by the client and his consultants.

Findings...

- 44 -

- (e) Other intangible factors, such as the level of the market, anticipated competition, time of year, quality of tendering documentation, time allowed for tendering, payment procedures, change order approval procedures, etc.

However, the estimates in this report assume a consistent level of market, competition and time of year, being normalized to Toronto, last quarter, 1971.

It should be further noted in relation to this element that bids are not attempts at accurate estimating, they are attempts to obtain the contract at the highest possible price, resulting (naturally) in the highest possible profit.

The following table lists the comparative elemental costs and percentages of total cost for this element:

University Buildings	Indirect & General Expenses		Percentage of Total Cost	
	Cost/GSF	Rank	%	Rank
Child Study Center	3.04	2	9.0	3
Law Building	2.53	4	9.1	1
Crop Science Building	3.61	1	8.5	4
Petrie Science Building	2.95	3	8.5	4
Mathematics and Computer Building	2.20	5	9.1	1
Engineering IV	2.15	6	7.5	7

Non-University Buildings	Cost/GSF	Rank	%	Rank
Northern Electric Laboratory	1.77	8	7.3	9
Systems Dimensions Limited Building	1.76	9	7.8	6
Varette Office Building	1.06	12	7.2	10
General Purpose Office Building	1.13	11	6.6	11
Food & Drug Laboratory	1.83	7	5.7	12
Georgian CAAT (IIIA)	1.76	9	7.4	8

As the cost of all other elements influences its level of cost, the cost per GSF is not the most meaningful basis of comparison for this element. An analysis of indirect costs expressed as a percentage of the whole reveals the average percentage for university buildings at 8.6% and for the non-university buildings at 7.0%.

Whilst further study in this area appears warranted, it would seem that the reasons for this higher proportion can be attributed to the factors listed above, i.e. university buildings generally take longer to build; the buildings in the sample group are of a higher unit cost; they tend to be more complex and contain more items of work of a higher quality; they are intended to have a considerably longer life; hence universities as owner-occupiers as well as their design consultants tend to insist on specifications being met and institute rigorous inspection routines to ensure this. The effect of this latter consideration on contractors' prices should not be underestimated.

It would be interesting and profitable to study the effect of the increasing use of construction management techniques by the universities since it seems likely that such techniques may well result in a reduction of indirect expenses.

- h. The overall cost of buildings is not consistent with the cost of their individual elements. A low-cost building may contain some elements that are high in cost and conversely, a high-cost building may have some low-cost elements within it.

For example, the Food and Drug Laboratory ranked 5 overall, but 10 in shell cost, 2 in services, and 2 in fixtures and fittings. Note that the Varette Office Building ranked 12 overall, but 2 in multi-storey elements. The Crop Science Building ranked 1 overall, but 7 in interior vertical elements.

However, interpretation of the relative costs of elements may be complex. An example of this complexity of interpretation shows in the General Purpose Office Building, ranking 11 at a figure of \$17.17/GSF. This building had a cost for exterior cladding of \$3.06/GSF which is 8 in rank. However, the unit cost of its exterior pre-cast wall was \$10.61/square foot: approximately double the unit cost of any other exterior walls in the study. The Exterior Wall/GSF ratio in this building was .31, the lowest figure of any in the study. This ratio shows the amount of the perimeter wall per gross square foot of building, and since this building is nearly square in plan, with no projections or recesses, its relatively small amount of exterior wall can counterbalance the high unit costs of the wall itself.

It should also be noted that elements are related to one another through the design of a building. It is not, for example, possible to combine all the low-cost elements in a single building (resulting, for this study, in a hypothetical building costing \$12.46/GSF). Such a building would be a high-rise building with no elevators!

- i. There is a wider range of element costs than building costs. This finding confirms the need to look closely at element costs in order to gain understanding of cost characteristics of the building.

For the buildings studied, overall costs range from \$42.39/GSF to \$14.73/GSF, or 3:1, while building elements range from 7:1 (Multi-storey elements) to 6:1 (Fittings and Fixtures).

- j. Higher performance requirements cost more, and the study shows the magnitude of some of these costs, as well as the complexity of the variables that influence the cost/design relationship.

For example, the study demonstrates that high-cost HVAC systems are the result of requirements for high-capacity HVAC systems. A clear measure of this shows in the Crop Science Building, with its special environmental requirements for plant growth research, which provides 5.7 tons of cooling per thousand gross square feet, 102.4 BTU per hour heating per gross square foot, and 2.43 CFM of ventilation per square foot at a cost of \$9.86/GSF. This compares with another university science building, the Petrie Science Building, which provides 4.2 tons of cooling per thousand gross square feet, 61 BTU per hour heating per gross square foot, and 1.00 CFM ventilation per square foot, at a cost of \$6.33/GSF.

Clearly, the functions and programs in these buildings make many more demands on the HVAC system than in that of a single-function office building such as Varette. This building provides 1.58 tons of cooling per thousand square feet, 26.4 BTU per hour heating per gross square foot, and .41 CFM of ventilation per square foot, for a cost of \$2.69/GSF, the lowest-cost HVAC system in the sample. In addition, in this building only 67% of the space is air-conditioned, while the other two buildings are fully air-conditioned.

This comparison shows the consistency between the cost of an HVAC system and its capacity, i.e., the quantity of air-conditioned and heated space that it provides relative to a standard measure, such as a gross square foot.

Capacity required is also affected by the volume of space heated. Buildings in the study ranged in average floor-to-floor height from 10.33 feet (Varette Office Building) to 14.66 feet (Engineering IV). Thus, the effect of volume on the buildings in this study is much less than the effect of program-related requirements. However, a study of operational costs of HVAC systems would be necessary to validate this statement.

This example also shows clearly that the comparison, even of a single building element, let alone a whole building, is not a simple procedure, and comparing the costs of air-conditioning on only a gross square footage basis is not going to provide a valid comparison unless functional demands are also considered. Finally, it must be emphasized that this study cannot validate the need for these differences in capacity; it can only point out that they exist.

Findings...

- 47 -

- k. University buildings generally cost more because of a conscious attempt to provide good exterior quality and a university identity; this extra cost for the sample of buildings lies in the range of \$1.10 to \$1.73/SF.

An attempt to isolate the costs of exterior quality for a university building was made as follows. One can assume that the extra cost is in that part of the shell that is above ground. This is contained in Element 4, Exterior Cladding; comprising 4b, Walls Above Grade; 4c, Windows; 4d, Exterior Doors; 4e, Projections, Balconies, etc. Adding to these element subcosts a figure representing that portion of the indirect costs (Element 1) attributable to Exterior Cladding (obtained by multiplying the indirect cost element by the percentage of exterior cost element of the whole), provides the basis for the figures shown below.

If unit prices for Exterior Cladding/SF are compared, so that the perimeter/GSF ratio is considered, the differences between university and non-university buildings are as follows:

<u>University Buildings</u>	<u>Exterior Cladding Unit Cost/SF</u>
Child Study Center	5.84
Law Building	3.35
Crop Science Building	3.21
Petrie Science Building	3.10
Maths & Computer Building	3.34
Engineering IV	4.89

Non-University Buildings

Northern Electric Laboratory	2.31
Systems Dimensions Limited	1.71
Varette Office Building	2.05
General Purpose Office Building	2.96
Food & Drug Laboratory	2.48
Georgian CAAT (IIIA)	3.24

Eliminating the three largest buildings (viz the Mathematics & Computer Building, the Varette Office Building, and the General Purpose Office Building) in order to lessen the cost reduction effects of scale, then average costs for above-ground exterior cladding are:

University Buildings	\$4.13/SF
Non-University Buildings	\$2.40/SF
Difference	\$1.73/SF

This figure gives a measure of the maximum unit cost difference which, in this sample of buildings, could be attributed to visible exterior cladding of higher quality.

If unit prices are compared (so that the effect of perimeter/GSF ratio does not apply), the differences between university and non-university buildings are as follows:

	Exterior Cladding Unit Cost/ Wall Area Above Grade	\$/SF of Window	% Window	Weighted Average
<u>University Buildings</u>				
Child Study Center	5.04	12.29	12.0	5.91
Law Building	4.55	12.84	25.0	6.62
Crop Science Building	4.95	10.50	15.0	5.78
Petrie Science Building	4.62	14.11	10.0	5.57
Maths & Computer Building	4.72	7.82	11.0	5.06
Engineering IV	5.14	11.00	16.5	6.11
<u>Non-University Buildings</u>				
Northern Electric Laboratory	4.23	12.00	10.7	5.06
Systems Dimensions Limited	2.14	10.44	14.0	3.30
Varette Office Building	6.52	4.75	16.0	6.24
General Purpose Office Building	10.61	7.80	38.0	9.54
Food and Drug Laboratory	4.78	9.53	29.0	6.16
Georgian CAAT (IIIA)	4.83	13.44	6.4	5.38

Omitting the three largest buildings (viz the Mathematics & Computer Building, the Varette Office Building, and the General Purpose Office Building) in order to lessen the cost reduction effects of scale, then average costs for above ground Exterior Cladding are:

University Buildings	\$6.06/ SF
Non-University Buildings	\$4.96/ SF
Difference	\$1.10/ SF

This figure gives a measure of the minimum unit cost difference which, in this sample of buildings, could be attributed to visible exterior cladding of higher quality.

It should also be noted that this quality is not only a matter of appearance, but may have great impact on operating and long-term maintenance costs, particularly in the case of the quality of window types and glazing. The proposed Phase II study would provide information on the magnitude of such savings.

4. DETAILED SAMPLE STUDIES

A full understanding of building cost and performance can only be gained by detailed study of consistent and comparable information.

The section which follows compares a number of buildings in detail and, where significant, points out parameters of cost and performance. This kind of comparison is individual rather than statistical. The comparisons that follow are between not more than three buildings chosen because of their general similarities, either in cost, function, performance, a combination thereof. Therefore, great care should be exercised in interpreting and extrapolating these results. To obtain statistically valid results would have necessitated an analysis of many more buildings than are contained in our sample. It goes without saying that neither the time nor the resources available to the Task Force permitted this. Therefore we have attempted to compensate for this deficiency by ranking a larger sample of buildings and choosing the 25th, 50th, and 75th percentile buildings from each group for more detailed analysis. The comparisons show that

1. Buildings can be similar in overall cost, but vary considerably in elemental costs - see the Petrie Science Building and the Food and Drug Laboratory comparison.
2. Buildings can be superficially similar in function but vary considerably in space and service allocation - see the Maths and Computer Building, the Systems Dimensions Limited Building, and the Northern Electric Laboratory Building comparison.
3. Buildings can be similar in overall performance, but vary considerably in detailed performance of certain elements - see the Law Building, the General Purpose Office Building and the Varette Office Building comparison.

a. Comparison of the Petrie Science Building and the Food and Drug Laboratory

These two buildings have similar mixes of space and are very close in size and cost. Both are heavily serviced buildings.

Petrie Science Building cost \$34.74/GSF as against Food and Drug Laboratory's cost of \$32.04/GSF. A more favourable NASF/GSF ratio for Petrie (0.57 vs 0.51) results in a reversal of ranking for NASF unit cost (\$60.32/NASF for Petrie, and \$62.86/NASF for Food and Drug).

The shell cost of the Petrie Science Building is \$2.57/GSF more than that for the Food and Drug Laboratory, but this is offset by a service cost which is \$2.44/GSF less, divided about equally between plumbing and HVAC. Petrie, however, provides about 25% more cooling capacity and 4% more ventilation capacity while the Food and Drug Laboratory provides approximately 85% more heating capacity.

COMPARISON OF THE PETRIE SCIENCE BUILDING AND THE FOOD AND DRUG LABORATORY

	Cost/ GSF	Cost/ NASF	GSF	NASF/GSF Ratio	Volume/ GSF	Exterior Cladding/ GSF	Roof Area/ GSF	Floors above grade	Floors below grade
Petrie Science Building	34.74	60.92	131,000	0.57	12.51	0.51	0.24	3	1
Food & Drug Laboratory	32.04	62.86	105,675	0.51	12.57	0.54	0.23	3	1

PERCENTAGE DISTRIBUTION OF NASF BY FUNCTION

	Classroom	Special Purpose	Office	Library	Special Use	General Use	Support
Petrie Science Building	2.2	51.1	21.9	1.4	2.0	2.3	19.1
Food & Drug Laboratory	---	31.6	39.5	3.0	1.9	3.8	20.2


ELEMENT COSTS PER GSF

	Cost/ GSF	1	2	3	4	5	6	7	8	9	10	11	12
Petrie Science Building	34.74	2.95	0.43	4.75	3.75	2.73	0.80	1.47	4.28	0.57	2.11	6.33	4.57
Food & Drug Laboratory	32.04	1.83	0.79	3.50	2.88	1.59	0.54	1.24	3.68	0.39	3.36	7.76	4.48

1: Indirect & General Expenses; 2: Substructure; 3: Horizontal Structure; 4: Exterior Cladding; 5: Interior Vertical;
 6: Multi-storey; 7: Interior Finishes; 8: Fittings & Fixtures; 9: Cash Allowances; 10: Plumbing; 11: HVAC;
 12: Electrical.

	HVAC											
	Tons/ 1000 GSF	CFM/ GSF	BTU/ HR/ GSF	Ser- vices Cost	Unit Cost of Exterior Walls	Cost/GSF of Ext. Wall	Ratio Ext./ GSF	Unit Cost of Int. Vert. Partitions	Cost/ GSF of Interior Vert.	Cost/ GSF of Vertical/ GSF	Ratio of Int. Vertical/ GSF	
Petrie Science Building	4.42	1.00	61.0	9.35	14.05	4.62	1.52	0.57	2.23	2.15	1:10.8	
Food & Drug Laboratory	3.50	.96	110.0	6.78	16.49	4.78	1.48	0.54	1.57	1.02	1:14.5	

ELEMENT COSTS PROFILE



The extra cost of the Petrie Science Building of \$2.70/GSF is predominantly made up of Indirect Costs (\$1.12/GSF), Fittings and Fixtures (\$0.60/GSF), and Interior Vertical elements (\$1.14/GSF). In addition, the Petrie Science Building has an extra cost of \$0.44 for roof finish, occasioned by requirements for a high quality roof which is used functionally for experimental purposes.

The extra cost for the Petrie Science Building in interior vertical elements is a combination of material (Petrie - 29% structural concrete, 68% concrete block; Food and Drug Laboratory - 69% concrete block, 11% drywall and studs, 4% brick), and a partition ratio which provides approximately 50% more partitions/GSF.

The extra cost for the Petrie Science Building in fittings and fixtures is probably accounted for by additional instructional material not provided in the Food and Drug Laboratory (chalk and tackboards, floating floor, etc.).

b. Comparison of the Law Building, the General Purpose Office Building, and the Varette Building

This summary compares a lightly serviced university building (the Law Building) with a speculative high-rise office building (the Varette Office Building) and a high-rise government office building that was specifically designed as a prototype low-cost building (the General Purpose Office Building).

The Law Building cost \$27.85/GSF as against the General Purpose Office cost of \$17.17/GSF, and the Varette cost of \$14.73/GSF. Since both office buildings provide no partition layout for analysis, it is not possible to obtain a realistic assignable square-foot figure for them, so that the NASF comparison is not presented.

The shell cost for the Law Building of \$11.54/GSF compares with shell costs of \$5.93 (General Purpose Office Building) and \$4.82 (Varette Office Building). This large discrepancy is primarily the result of large areas, and a simple repetitive plan that optimizes all structural and skin construction costs in the office buildings. The exterior skin is minimal in area relative to the plan (the relevant Exterior Cladding/GSF ratios are General Purpose Office 0.31, Varette 0.37, and Law 0.50) and very simple, with uniform height per floor, no re-entrant corners, and minimal special detailing. Floor loadings for the office buildings are low (General Purpose 75 lb/SF, Varette 50 lb/SF) as against the Law Building's average of 125 lb/SF.

The complex plan form and high loadings of the Law Building result in the highest horizontal structural cost for the entire sample of twelve buildings studies.

Service costs for the Law Building are not noticeably higher, but not to the same extent as the shell. Performance in HVAC is noticeably higher for the Law Building also.

COMPARISON OF THE LAW BUILDING, THE GENERAL PURPOSE OFFICE BUILDING, AND THE VARETTE OFFICE BUILDING

	Cost/ GSF	Cost/ NASF	NASF/ GSF Ratio	Volume/ GSF	Exterior Cladding/ GSF	Roof Area/ GSF	Floors above grade	Floors below grade
Law Building	27.85	45.53	85,140	0.59	14.27	0.50	2	1
General Purpose Office Bldg.	17.17	19.96	433,410	0.86	11.19	0.31	22	1
Varette Office Bldg.	14.73	16.66	317,400	0.89	10.38	0.37	19	4

PERCENTAGE DISTRIBUTION OF NASF BY FUNCTION

	Classroom	Special Purpose	Office	Library	Special Use	General Use	Support	Parking
Law Building	16.5	11.8	16.7	50.1	--	4.9	--	--
General Purpose Office Bldg.	--	--	78.0	--	--	--	22.0	--
Varette	--	--	92.5	--	--	7.5	--	--

ELEMENT COSTS PER GSF


	Cost/ GSF	Cost/ NASF	1	2	3	4	5	6	7	8	9	10	11	12
Law Building	27.85	45.53	2.53	1.20	6.03	3.35	1.94	0.81	2.72	0.77	0.44	0.72	4.50	2.84
General Purpose Office Bldg.	17.17	19.96	1.13	0.12	2.38	3.06	0.80	1.77	1.67	0.07	0.03	0.81	2.88	2.45
Varette Office Bldg.	14.73	16.66	1.06	0.32	2.03	2.19	0.70	1.63	1.83	0.10	0.05	0.76	2.70	1.36

1: Indirect & General Expenses; 2: Substructure; 3: Horizontal Structure; 4: Exterior Cladding; 5: Interior Vertical
 6: Multi-storey; 7: Interior Finishes; 8: Fittings & Fixtures; 9: Cash Allowance; 10: Plumbing; 11: HVAC;
 12: Electrical.

HVAC

	Tons/ 1000 GSF	CFM/ GSF	BTU/ HR/ GSF	Shell Cost	Ser- vices Cost	Unit Cost of Exterior Walls	Cost/GSF Ratio	Ext./ Wall	Cost of Int. Vert. Partitions	Unit Cost of GSF of Interior Vertical	Cost/ GSF of Interior Vertical	Ratio of Vertical/ GSF
Law Building	3.2	1.03	43.5	11.54	8.79	4.55	1.48	0.50	1.85	1.34	1:16.1	
General Purpose Office Bldg	2.7	0.62	62.3	5.93	6.54	10.61	2.22	0.31	2.19	0.70	1:33.3	
Varette Office Building	1.6	0.41	26.4	4.82	5.16	6.52	1.55	0.37	1.85	0.56	1:33.3	

ELEMENT COSTS PROFILE



	Cooling tons/1000 GSF	Heating BTU/HR/GSF	%AC	Ventilation CFM/GSF
Law Building	3.2	43.5	100	1.03
General Purpose Office Building	2.7	62.3	90	0.62
Varette Office Building	1.61	26.4	67	0.41

Plumbing costs are similar (Law Building \$0.72/GSF, General Purpose Office Building \$0.81/GSF, Varette Office Building \$0.76/GSF), though the office buildings provide a better fixture ratio viz. 1.10 fixtures/1000 GSF for the General Purpose Office Building, 0.95 fixtures/1000 GSF for Varette, and 0.64 fixtures/1000 GSF for the Law Building. The repetitive toilet layout in the office buildings is very economical.

Both office buildings have higher unit costs for exterior wall than the Law Building (General Purpose Office Building \$10.61/GSF, Varette \$6.52/GSF, as against \$4.55/GSF for Law, but the excellent perimeter/GSF ratio for the office buildings offsets the higher unit costs. In addition, the two office buildings have lower floor-to-floor heights than the Law Building with its two-storey moot court space (average floor-to-floor height: General Purpose Office Building 11.21 feet; Varette Office Building 10.4 feet; Law Building 14.3 feet).

The office buildings also gain in substructure costs (a function of the multi-storey characteristics of small foundation and excavation area) and can easily offset the extra multi-storey costs (highest of the entire sample).

c. Comparison of the Maths & Computer Building, the Systems Dimensions Limited Building, and the Northern Electric Laboratory Building

This summary compares three buildings with a mix of space approximately similar, and approximately equal in cost. All three buildings make extensive provision for computer facilities, or provide for special electrical requirements.

The Maths & Computer Building cost \$24.26/GSF, the Systems Dimensions Limited Building \$22.58/GSF, and the Northern Electric Laboratory \$24.14/GSF. The Systems Dimensions Limited Building includes 21.6% of space as covered parking, with a low structural and service cost. For the Maths & Computer Building, the cost is \$38.38/NASF, with a NASF/GSF ratio of 0.63. Systems Dimensions Limited shows a cost of \$29.17/NASF and a ratio of 0.77, while the Northern Electric Laboratory has a cost of \$32.56/NASF and a ratio of 0.74. Both these buildings have large open areas for office and computer use, so that their NASF areas are not comparable to the Maths & Computer Building which also has a large computer room, but this space is much smaller in area (3.6%) relative to the total NASF for the other two buildings.

PARISON OF THE MATHS & COMPUTER BUILDING, THE SYSTEMS DIMENSIONS LTD. BLDG., AND THE NORTHERN ELECTRIC LABORATORY BLDG.

	Cost/ GSF	Cost/ GSF	NASF/GSF Ratio	Volume/ GSF	Exterior Cladding/ GSF	Roof Area/ GSF	Floors above grade	Floors below grade
Maths & Computer Bldg.	24.26	38.38	299,736	0.63	12.76	0.57	0.18	6
Northern Electric Lab.	24.14	32.56	90,147	0.74	14.74	0.42	0.59	2
Systems Dimensions Ltd.	22.58	29.17	102,930	0.77	13.67	0.48	0.37	2

PERCENTAGE DISTRIBUTION OF NASF BY FUNCTION

	Classroom	Special Purpose	Office	Library	Special Use	General Use	Support	Parking
Maths & Computer Bldg.	23.9	3.6	40.5	1.2	--	10.6	19.6	--
Northern Electric Lab.	--	17.8	73.0	--	2.2	7.0	--	--
Systems Dimensions Ltd.	5.0	--	21.6	1.7	1.5	8.2	40.4*	21.6

*included 33.6% data processing.

61

ELEMENT COSTS PER GSF

	Cost/ GSF	Cost/ NASF	1	2	3	4	5	6	7	8	9	10	11	12
Maths & Computer Bldg.	24.26	38.38	2.29	0.79	4.25	3.11	2.08	0.77	1.78	0.78	0.60	0.91	3.84	3.15
Northern Electric Lab.	24.14	32.56	1.77	0.52	4.43	2.18	1.07	0.26	2.48	0.30	0.15	1.20	6.00	3.78
Systems Dimensions Ltd.	22.58	23.17	1.76	0.24	3.94	2.22	1.39	0.55	1.91	1.02	0.25	0.83	5.34	3.10

- 1: Indirect & General Expenses; 2: Substructure; 3: Horizontal Structure; 4: Exterior Cladding; 5: Interior Cladding;
 6: Multi-storey; 7: Interior Finishes; 8: Fittings & Fixtures; 9: Cash Allowance; 10: Plumbing; 11: HVAC;
 12: Electrical.


HVAC

Tons/ 1000 GSF	CFM/ GSF	BTU/ HR/ GSF	Shell Cost	Ser- vices Cost	Unit Cost of Exterior Walls	Cost/GSF Ext. Wall	Ratio Ext./ GSF	Unit Cost of Int. Vert. Partitions	Cost/ GSF of Interior Vertical	Ratio of Interior Vertical/ GSF
2.7	0.78	40.0	8.89	8.62	4.72	2.21	0.57	1.57	1.51	1:11.8
4.4	1.59	14.6	7.65	11.79	4.23	1.59	0.42	2.48	0.93	1:23.7
2.6	0.97	65.0	6.90	9.99	2.14	0.70	0.48	2.39	1.13	1:38.5

ELEMENT COSTS PROFILE

MATHS. AND COMPUTER BLDG. \$ 24.26 / G.S.F.
NORTHERN ELECTRIC LAB. \$ 24.14 / G.S.F.
SYSTEM DIMENSION LTD. \$ 22.58 / G.S.F.

DOLLARS PER GROSS SQUARE FOOT



For the costs of shell and services, the spread is higher for the services (\$3.17/GSF) than for the shell (\$1.99/GSF). Northern Electric Laboratory has a high HVAC cost (\$6.00/GSF) as against Systems Dimensions Limited (\$5.34/GSF) and Maths & Computer (\$3.84/GSF) but the capacity of the Northern Electric Laboratory HVAC system is almost double the other two buildings in cooling and ventilation. Its heating capacity, however, is of the order of 25-30% of the other buildings, and this is due to high electrical equipment and lighting loads. This building also had approximately \$.75/GSF extra electrical cost in providing voltage at 21 KV.

Maths & Computer had a high cost for Interior Vertical elements (\$2.07/GSF) as against \$1.07/GSF for Northern Electric Laboratory and \$1.39/GSF for Systems Dimensions Limited. The unit price for partitions for Maths & Computer was low (\$1.57/GSF vs. \$2.48/GSF for Northern Electric Laboratory, and \$2.39/GSF for Systems Dimensions Limited). However, a low unit price for Maths & Computer could not offset a much higher partition ratio of 1:11.8 (Interior Vertical/GSF) for Maths & Computer as against 1:38.5 for Northern Electric Laboratory and 1:23.7 for Systems Dimensions Limited.

Northern Electric Laboratory had a high cost for interior finishes (\$2.48/GSF, rank 3 in overall sample) although this building ranks 9 in overall cost, demonstrating the small impact of the cost of interior finishes on overall cost (see Finding e.).

Northern Electric Laboratory also had the lowest cost/GSF for exterior cladding of the entire sample, and Systems Dimensions Limited ranked 10. Maths & Computer had the lowest cost of the university sample, but was still approximately \$.90/GSF more expensive than the other two buildings. Both non-university buildings had a better exterior/GSF ratio than Maths & Computer (0.42, as against 0.57). Systems Dimensions Limited also had a very low unit cost for exterior cladding (\$2.14/GSF as against \$4.86/GSF for Maths & Computer, and \$4.23/GSF for Northern Electric Laboratory), but also had a large area of walls below grade, so that the low cost for above-grade cladding was somewhat offset.

The DCU study provided a detailed analysis of the Northern Electric Laboratory on the basis that there "is no difference between this project and university projects". The analysis performed by the Task Force enables one to see this building in perspective, as predominantly an office building with a relatively small area of electrical laboratories, and with no special plumbing or institutional furnishings.

d. Comments on Other Buildings

(1) Child Study Center

This building ranked 4 in overall cost, at \$33.61/GSF, or \$54.28/NASF. Its assignable floor area was utilized as 25.8% classroom, 10.6% office, and 42.4% special purpose. The building had a number of spaces containing specialized electronic and audiovisual equipment for the testing and training of children and also included complete

school facilities, a cafeteria, and residential facilities. Programmatically, this was probably the most unusual building in the group.

Horizontal structural costs were the lowest for the group of university buildings; however, the exterior cladding costs were highest for the entire group of buildings.

The cost of the interior finishes was the highest of the entire sample group, much of this attributable to an expensive metal ceiling and to special floor finishes (carpet and quarry tile) necessitated by the building function. Plumbing costs were also high, due to the very high incidence of toilet fixtures.

(2) Crop Science Building

This building ranked highest in overall cost, at \$42.39/GSF, or \$71.27/NASF. Its assignable floor area was utilized as 76.2% special purpose (laboratories and preparation areas), the highest percentage of the sample. Offices accounted for some 16.2% of the floor area.

Not only was the percentage of the space given over to laboratories very high, but many of their laboratories were engaged in special research (plant growth) calling for special environmental conditions. These involved 1500 foot-candle intensity lighting (fluorescent tubes approximately 9 inches in center, plus incandescent lighting) and very high heating loads. As a result, both electrical and HVAC costs were highest of the sample, and the service elements together cost \$20.81/GSF. Fittings and fixtures also ranked high (rank 3, at \$3.38/GSF), typical of heavily serviced laboratory buildings.

Shell costs were high (rank 4 at \$10.38/GSF), mainly due to a high cost for horizontal structure.

All other elemental costs were modest. Clearly, a combination of high shell costs and very high services costs makes this an expensive building which modest costs in all other elements cannot counterbalance.

This building clearly illustrates the impact of programmatic and functional needs on overall building costs.

(3) Engineering IV

This building ranked second in overall cost, at \$36.80/GSF, or \$62.33/NASF. Its assignable floor area was utilized as 4.3% classroom, 13.5% office, and 62.6% special purpose, predominantly teaching and specialized laboratories and workshops for a variety of engineering tasks.

This building had the highest shell cost of the entire sample. Its exterior wall/GSF ratio of 0.79:1 is very high, and its unit cost for walls above grade was the highest of the university sample at a cost of \$5.14/GSF.

Substructure costs for the Engineering IV Building were the highest of the entire sample, a combination of poor soil conditions and a large foundation area. Interior vertical costs were high (rank 2) and intensity of partitions was also high at a linear foot partition/GSF ratio of 1:12.4.

Both HVAC requirements and cost are high, although this building ranked 3 in comparison with the heavily serviced university buildings.

(4) Georgian CAAT (IIIA)

This building ranked 9 in overall cost, at \$23.93/GSF, or \$34.17/NASF. Its assignable area was utilized as 2.12% classroom, 5.9% office, 11.9% general use, and 52.1% special purpose, predominantly simple teaching laboratories and workshops.

A small, two-storey building, its costs in all elements were consistently modest. Its electrical costs were a little higher than its overall rank, but its HVAC costs were bettered only by the two high-rise office buildings. HVAC performance matched the costs, although the building is, unlike the office buildings, 100% airconditioned.

5. ADDITIONAL TABLES

The following tables are presented to illustrate some useful ways of comparing some of the information gathered in this study.

Table 4 compares some of the characteristics of the sample buildings that relate to the building configurations.

Table 5 compares the functional mix of space comprising the net assignable floor areas of each sample building.

Table 6 groups some of the elemental costs (from Table 3) in order to isolate the costs of the building shell and services.

Table 7 isolates some comparable measurable characteristics of the HVAC and plumbing elements of the buildings.

CONFIGURATION RATIOS

(High elements underlined; Low elements underlined)

	GSF	NASF	NASF/GSF ratio	Volume/GSF ratio	Wall/GSF ratio	Roof/GSF ratio	Floors above grade	Floors below grade
Child Study Building	58,150	36,000	0.62	11.52	0.51	0.20	6	1
Law Building	85,140	52,311	0.61	14.27	0.50	0.39	<u>2</u>	1
Crop Science Building	106,069	63,087	0.59	13.34	0.68	0.50	4	1
Petrie Science Building	131,000	74,710	0.57	12.51	0.57	0.24	3	1
Maths & Computer Building	299,736	189,117	0.63	12.76	0.57	0.18	6	1
Engineering IV Building	170,907	100,908	0.59	14.66	<u>0.79</u>	0.48	av.2	1
Northern Electric Laboratory	90,147	66,820	0.74*	<u>14.74</u>	0.42	<u>0.59</u>	<u>2</u>	<u>-</u>
Systems Dimensions Limited	102,930	79,323	0.77*	13.67	0.48	0.37	<u>2</u>	1
Varette Office Building	317,400	N.A.	N.A.	<u>10.38</u>	0.37	0.05	19	<u>4</u>
General Purpose Office Building	433,410	N.A.	N.A.	11.19	<u>0.31</u>	<u>0.04</u>	<u>22</u>	1
Food & Drug Building	105,675	53,865	<u>0.51</u>	12.57	0.54	0.23	3	1
Georgian CAAT (IIIA)	<u>43,140</u>	<u>30,210</u>	0.70	14.41	0.55	0.55	<u>2</u>	<u>-</u>

- 62 -

TABLE 4

* Includes large undivided office areas

N.A. indicates not applicable. See discussion on measurement of NASF in Section 6c.

TABLE 4

PERCENTAGE DISTRIBUTION OF NET ASSIGNABLE AREA BY FUNCTION (DCU SPACE CLASSIFICATION)

	Classroom	Special Purpose	Office	Library	Special Use	General Use	Support	Indoor Parking
Child Study Building	25.8	42.4	10.6	-	8.1	13.2	-	-
Law Building	16.5	11.8	16.7	50.1	-	4.9	-	-
Crop Science Building	6.3	76.2	16.2	1.4	-	-	-	-
Petrie Science Building	2.2	51.1	21.9	1.4	2.0	2.3	19.1	-
Maths & Computer Building	23.9	3.6	40.5	1.2	-	10.6	19.6	-
Engineering IV Building	4.3	62.6	13.5	-	-	12.0	7.6	-
Northern Electric Laboratory	-	17.8	73.0	-	2.2	7.0	-	-
Systems Dimensions Limited	5.0	-	21.6	1.7	1.5	8.2	40.4*	21.6
Varette Office Building	-	-	78.0	-	-	-	-	22.0
General Purpose Office Building	-	-	92.5	-	-	7.5	-	-
Food & Drug Building	-	31.6	39.5	3.0	1.9	3.8	20.2	-
Georgian CAAT (IIIA)	2.1	52.1	5.9	-	2.7	11.9	6.2	-

TABLE 5

* Data Processing 33.6%.

TABLE 5

SHELL, SERVICES AND OTHER ELEMENTAL COSTS

(High elements underlined; Low elements underlined)

	Shell cost elements 2,3,4, + % of 1 Rank	Services cost elements 10-12 + % of 1 Rank	Fixtures & Fittings element 8 + % of 1 Rank	Multi-storey element 6 + % of 1 Rank	Balance elements 5,7,9 + % of 1 Rank
Child Study Building	2	11.84	5	12.00	7
Law Building	3	11.54	9	<u>8.79</u>	8
Crop Science Building	4	10.83	1	<u>20.81</u>	3
Petrie Science Building	5	9.68	3	14.12	1
Maths & Computer Building	6	8.89	10	8.62	8
Engineering IV Building	1	<u>13.30</u>	4	13.80	4
Northern Electric Laboratory	8	7.65	6	11.79	10
Systems Dimensions Limited	9	6.90	7	<u>9.99</u>	5
Varette Office Building	12	<u>4.82</u>	12	<u>5.16</u>	11
General Purpose Office Building	11	5.93	11	6.54	12
Food & Drug Building	10	6.78	2	16.49	2
Georgian CAAT (IIIA)	7	8.31	8	9.61	5

TABLE 6

HVAC AND PLUMBING COSTS

	Tons/ 1000 GSF	Cost	% AC	CFM/ GSF	BTU/HR/ GSF	Thermo- stats/ 1000 GSF	Vol/GSF ratio	Cost/ GSF	Plumbing Fixtures/ 1000 GSF
Child Study Building	3.2	4.90	100	1.00	63.8	1.95	11.52:1	1.92	2.20
Law Building	3.2	4.50	100	1.03	43.5	1.13	14.27:1	0.72	0.64
Crop Science Building	5.7	9.86	100	2.43	102.4	0.95	13.34:1	2.64	0.60
Petrie Science Building	4.4	6.33	100	1.00	61.0	1.55	12.51:1	2.11	0.48
Maths & Computer Building	2.7	3.84	100	0.78	40.0	0.85	12.76:1	0.91	0.63
Engineering IV Building	3.9	6.14	100	1.33	101.5	0.70	14.66:1	1.84	0.50
Northern Electric Laboratory	4.4	6.00	100	1.59	14.6	0.24	14.74:1	1.20	0.63
Systems Dimensions Limited	2.6	5.34	65	0.97	65.0	0.62	13.67:1	0.83	0.70
Varette Office Building	1.6	2.69	67	0.41	26.4	1.40	10.38:1	0.76	0.95
General Purpose Office Building	2.7	2.88	90	0.62	62.3	1.40	11.19:1	0.81	1.10
Food & Drug Building	3.5	7.76	75	0.96	110.0	1.20	12.57:1	3.36	0.78
Georgian CAAT (IIIA)	2.4	3.14	100	0.96	40.0	1.10	14.41:1	1.71	1.49

- 65 -

TABLE 7

TABLE 7

6. COST ANALYSIS - ISSUES

a. The Interim Capital Formula

The interim capital formula dollar allowance presently administered by DCU is set out in Table CS-1 of the DUA Cost Study: Interim report to the CUA (December 1970) as follows:

Construction Cost	\$25.19/GSF
Fees and Contingency	2.52/GSF (10% of Construction Cost)
Furniture and Equipment	3.78/GSF (15% of Construction Cost)
Construction Cost Escalation (one year)	1.51/GSF (6% per annum)
GSF/NASF ratio (100/60)	
Total Project Cost Allowance	\$55.00/NASF

It is recognized (though not explicitly) that university buildings may vary considerably in their cost because of programmatic requirements: a science laboratory, for example, will cost considerably more than a minimum-serviced arts building. The capital formula allowance is an average figure, and the discrepancy between the costs of different types of buildings is expected to be averaged out over time on a given campus. This expectation assumes that, if a science building may cost more than \$55/NASF, it will be compensated for by other structures which will cost less. Thus, justification for each new building must be accompanied by negotiation between the campus planners and the DCU on a basis of mutual understanding, but not explicit budget guidelines.

The interim capital formula allowance procedure raises three major issues to which this Task Force has directed its attention. These issues are:

- (1) Is the establishment by DCU of a capital formula dollar allowance a beneficial procedure?

The Task Force considers that the use of a capital formula dollar allowance procedure is beneficial, and should be maintained as a budgeting and cost control tool.

- (2) Should the capital formula dollar allowance be a single, average figure, or should it be more explicitly related to the type of building being budgeted?

The Task Force reviewed in some detail the development of a capital formula dollar allowance that would vary with the type of building proposed. The main benefits would be the potential of making the budgeting and cost planning process more precise, reducing the negotiation between the university and DCU, and providing a more explicit basis for whatever negotiation still remained. However, the Task Force agreed that the formula dollar allowance should

remain a single average figure, for the following reasons:

- (a) The attempt to provide explicit allowances based on building types would require extensive study and analysis. This present study showed up some of the potential complexity.
 - (b) A multi-figure allowance would be more difficult to administer, and probably would not reduce significantly the amount of negotiation.
 - (c) The average figure allows for flexibility in planning, both on the part of the university and DCU, and the necessary negotiations are simpler and more fruitful than if they were more explicitly constrained by cost figures related to building type.
 - (d) There is now a history of working with an average figure, and to institute a new procedure would entail a new educational process and overall administrative changes.
- (3) Is the present average figure of \$55/NASF adequate, and upon what basis should it be reviewed?

The present study of comparative costs of university and non-university building has shown that the costs of university buildings are higher. The higher cost results from programme and design requirements. It is beyond the scope of this study to establish whether these requirements are essential or not. This should be the subject of further examination. If it is assumed that they are essential, it does not then make sense to include non-university buildings in a study of an adequate cost allowance for university buildings, particularly when the sample of non-university buildings is so small and diverse. It might be mentioned parenthetically that even if one includes all the non-university buildings in the sample and applies the DCU Basic Analytic Framework one arrives at a capital dollar allowance of \$56.26/NASF.

When the DCU Basic Analytic Framework, from which the total project cost allowance of \$55/NASF was derived, is applied to the sample of six university buildings the results are illuminating. Though six buildings is obviously a very small sample, it should be recalled that they represent the 25th, 50th, and 75th percentiles in cost range from a total sample of 39 university buildings (Section 8a). The buildings are further divided into three lightly serviced and three heavily serviced.

Cost Analysis - Issues...

- 68 -

	<u>Light Service</u>	<u>Heavy Service</u>
Construction cost * (as of Sept. 1971)	\$32.50/GSF 27.01/GSF <u>23.53/GSF</u>	\$41.12/GSF 33.90/GSF <u>35.70/GSF</u>
Average	\$27.68/GSF	\$36.91/GSF
Fees and contingency costs (10% construction cost)	2.77/GSF	3.69/GSF
Furniture and equipment (15% construction cost)	4.15/GSF	5.54/GSF
Total project cost GSF/NASF ratio (100/60)	\$34.60/GSF \$57.30/NASF	\$46.14/GSF \$76.90/NASF

Average (light and heavy service)

Construction cost	\$32.29/GSF
Fees and contingency costs (10%)	3.23/GSF
Furniture and equipment (15%)	<u>4.84/GSF</u>
Total project cost	\$40.36/GSF
GSF/NASF ratio (100/60)	\$67.26/NASF

These figures at least suggest some measure of the cost of a group of university buildings, normalized to a single place (Toronto) and a single time (September 1971). Even if the formula allowance was deliberately kept low as a tool of cost reduction control in the expectation that designers will improve on previous average figures, the above figures suggest that \$55/NASF is now outdated.

If one takes the lowest-cost university buildings in the sample (representing the 75th percentile of the gross sample) and combines the light-and heavy-service buildings, the result is as follows:

Construction cost	\$28.71/GSF
Fees and contingency costs (10%)	2.87/GSF
Furniture and equipment cost (15%)	<u>4.30/GSF</u>
Total project cost	\$35.88/GSF
Gross/net ratio (100/60)	\$59.80/NASF

It is not suggested that the above figure is definitive. In order to arrive at a valid average figure, it would be necessary to establish a weighted average for each university, based on the relative quantities of light-and heavy-service buildings. This calculation has not been done. The intent here is to establish some orders of magnitude as a prelude to a more detailed study.

* 3% deducted for federal tax rebate

In arriving at an acceptable single figure, the data in this cost study provides much detailed information to assist in arriving at a budget allowance for a specific building. Areas where costs will be incurred through programmatic requirements can be estimated, and the magnitude of these costs gauged and identified on an elemental basis. Areas where savings can be made can similarly be identified. Thus, this study provides a basis for a much more sophisticated development of an average figure than is now possible. Extension and continuation of the development of this cost information, as suggested in Recommendation 7a, together with an examination of furniture and equipment costs, would result in an increasingly more refined and valid information base for reviewing and establishing the formula allowance. Once an acceptable single figure has been established, it could be expected to remain valid only for a short time if building costs continue to escalate.

It is recommended that the formula allowance be formally reviewed yearly by a joint DCU/COU staff committee, not only to take escalation into account, but also new information arising from on-going studies and further experience. As a result of this review, full understanding would be reached between all parties as to the basis of the formula allowance for the following year.

b. Cost Escalation

The methodology for the cost study, which involved re-estimating the study sample, provides a useful check on the effects of cost escalation. While any measure of cost escalation (short of bidding a control group of identical buildings at regular intervals) must be hypothetical, it is felt that the method used here should give a reasonably accurate estimate.

The figures shown in the table make an interesting comparison with those derived from published indices of cost escalation. In general, the study figures show an escalation some 50% less than that suggested by the published indices for the particular group of buildings listed.

Escalation Table

	Total escalation percentage	Southam percentage
<u>University Buildings</u>		
Child Study Center	14.8	32.4
Law Building	18.0	34.3
Crop Science Building	20.8	47.4
Petrie Science Building	19.5	47.4
Maths & Computer Building	25.6	47.4
Engineering IV	10.4	19.5
<u>Non-University Buildings</u>		
Northern Electric Laboratory	22.7	44.7
Systems Dimensions Ltd. Building	17.3	32.9
Varette Office Building	19.7	31.9
General Purpose Office Building	25.3	38.5
Food & Drug Laboratory	--	--
Georgian CAAT (IIIA)	11.0	16.1

c. Measurement of Assignable Area

The gross area of a building is defined as the total area measured flat on a plan for each floor from outside to outside of exterior walls. It includes the actual areas of balconies and mezzanines where these occur within the exterior walls of the building.*

The net assignable area of a building is defined as the area which may be assigned to a specific academic, administrative or general university function. This area does not include circulation and general service areas, such as corridors, staircases, restrooms, washrooms, janitors' closets, mechanical and electrical service rooms, building service staff facilities and general storage areas.

The ratio of net assignable area to gross area of a building is a commonly used measure of the efficiency of a building plan.

NASF/GSF ratios for university buildings nationwide generally average around 0.60. The ratios for the six university buildings in this study ranged from 0.57 to 0.62. Since programming of university facilities is based on assignable area, and building costs are generally budgeted on the basis of cost/assignable area, it is clear that the NASF/GSF ratio may have a considerable effect on building programs and budgets. A difference in NASF/GSF ratio from .55 to .65 represents an 18% increase in assignable area, or potentially a budget decrease of about 15% in planning a new facility. For this reason, the NASF/GSF ratio currently has great force.

This ratio then, provides a measure of that space in the building which is not functionally useful. The largest amount of this non-useful space is taken up by circulation -- corridors, hallways, etc. Effective use of this measure for comparing buildings depends on precise definition of the terms of measurement. Where there is no such agreement comparisons must be treated with the greatest caution. This became apparent in the study when comparing the two high rise buildings (Varette and General Purpose) to the rest of the sample. No information is available on the circulation space used in these buildings except for a standard area around the service core. In addition, the actual layout of many of these office floors, as is typical in commercial office buildings, comprises large open floors in which the circulation space that does exist is not defined by corridor walls. In this study, it was decided that no valid net assignable square foot ratios could be provided for the two general office buildings, and so this measure is omitted rather than to attempt to provide measures of efficiency and cost which would not be comparable to other buildings in the study.

In some other buildings in the study, the NASF/GSF ratios must be treated with caution. Both the Northern Electric Laboratory and the Systems Dimensions Limited Building provide large areas of open office space, which is treated as 100% assignable, although in fact, an indeterminate amount of this space must be used for circulation.

* See Section 8b for further notes on defining gross area

Concepts of the open planning of office space are starting to invalidate the use of the NASF/GSF ratio as a definitive measure of building efficiency. Office landscaping, as the more sophisticated concepts of open office planning are often called, is starting to be used on university buildings, at present mainly in administrative areas. In elementary and high schools, open planning is being increasingly used in academic areas. If this spreads to university buildings then the NASF/GSF ratio will become even more suspect as an absolute measure, and it seems that cost per gross square foot will become an increasingly useful measure for cost control.

d. University Design Requirements

The variables which make up the cost of a building are complex and hard to identify because their analysis is a relatively new form of study. They are not, however, mysterious or irrational. Higher design requirements will mean higher cost. In looking for cost reduction, it is essential to make a careful distinction between those items which provide higher functional performance and those which do not. Increased floor loading of a horizontal structure, increased capacity in the air-conditioning system, increased intensity of plumbing fixtures -- are specific items of higher performance, and these can be objectively measured. However, the need for that higher performance must of course be judgemental.

Additionally, universities by virtue of their programme requirements must often plan for and incorporate a higher degree of flexibility and longevity into their buildings. It goes without saying that these objectives can only be attained by accepting higher unit costs for some of the building elements.

e. University Identity

In those factors which do not provide objectively measured higher performance, the element of judgement may enter very strongly. Some of these factors are of an esthetic nature. Once they can be identified, then conscious statements of esthetic objectives must be made by the owner and responded to by the architect. Traditionally, the university, nationwide and in most countries, has consciously expressed the desire for high esthetic content in its buildings, even if this demand has not been either stated or implemented with the precision that can be applied to objective standards.

This desire for high esthetic content was once expressed in elaborate facades copying medieval or classical models. None of the buildings in this study attempt this form of expression which, today, is very costly indeed. However, university buildings do, in general, use good exterior materials, and considerable care is taken, both in materials and workmanship, to relate one building to another. This is an essential difference between the campus and private building environment, and the university building designer is consciously asked to enhance a coherently designed environment.

To regard low cost as the highest priority, and to remove or minimize the esthetic content of university buildings, would be to impose a significant change of attitude on the physical culture of the campus. Traditionally, it has been accepted that scholarship, research and cultural and social education flourish in a certain kind of environment, not well defined, but generally understood by academicians and designers alike. This environment has been created with greater or lesser success, whether related to the environment as a whole or to the individual buildings. The fact that an individual may greatly dislike the esthetic appearance of a particular building does not invalidate in the least the attempt upon everyone's part -- the academic, the university administrator, the architect -- to ask for, design and pay for a building in which an attempt is made in the best of faith to respond to the traditional demands of the university environment.

Many university buildings are unique in function and use, and do not have equivalents in the outside world. For this reason, they look different and they may cost more money. A few buildings may have functional equivalents in the outside world, but they may, because of the demands of the university environment, also look different, and their costs may also be more.

The university setting is different from the outside world. These differences run deep in our cultural heritage and should not be swept away without serious and careful consideration. The universities, nationwide, have proven to be one of man's most enduring institutions, and in general they have been built to respect this, and have respected it superbly. The university may indeed become more related to the community around it; its activities may in the future take place more in community facilities than on an ivory tower campus. The decision is not lightly to be made that the notion of the campus as a place different in physical atmosphere, and intellectual and social climate from anything else in society, should be abolished, and that there is no reason why the university building should differ in cost or appearance from the commercial office building, the factory, or the grade school.

7. RECOMMENDATIONS

1. The systematic cost/design analysis developed in this study should be applied to the continuing university construction program. In this way, a body of coherent information will be developed which will be of immense value for future cost planning and cost control.

Design requirements and statistical data can be provided by the architect as part of the design package. Cost analysis on an elemental basis can be provided by a cost consultant at the time tenders are received. On this basis, the costs of procuring the information will be minimal.

2. The cost/design information developed in this study provides essential data which could provide a basis for the study of an effective systems building program for the Ontario University system. A study should be instituted to establish the objectives for future university buildings, to establish the cost/benefit parameters for such a program, and to estimate potential benefits and constraints of such programs.

It is suggested that the university might investigate the use of a systems program with the following attributes:

- (1) Concentrate on reducing shell costs by providing a simple repetitive structure that could save money with minimum impact on program requirements. Volume purchase of structure for packages of two to four buildings might serve to reduce the university's present disadvantage in having to construct relatively small facilities.
- (2) Limit the scope of the systems program to buildings containing the space types exemplified in this study, with the possible addition of libraries. In this way, the systems program will begin to develop for the universities an inventory of simple, inexpensive but highly flexible space.
- (3) Select subsystems, from available components, that meet the university's performance requirements within stated elemental cost targets. The time and expense of a large-scale developmental program such as SCSD or SEF is thus obviated.
- (4) Begin by running a small-scale pilot program - three or four subsystems for two to four projects - in order to develop procedures and accustom all participants with minimum expenditure of time and money. The program could later be expanded and run on a yearly serial basis, with definition of size of program, scope of components, and cost and performance parameters reviewed each year to keep pace with university needs and those of the local and national economy.

- (5) Besides structure, concentrate on the HVAC, partitions, lighting/ceiling and electrical/electronic subsystems as offering the best benefits. Omit the exterior wall from system consideration but set careful cost targets on this element to control conventional design. In this way, individual campus and architect preferences can be maintained.
3. The data in this report provides a basis for establishing design and cost guidelines, for all building elements, to assist university design architects and engineers. These guidelines should be developed by each university.

Scrutiny of the elemental costs provided in this study should enable elemental cost targets to be set with some degree of accuracy. Guidelines should take the form of suggested cost ranges for those elements that are particularly susceptible to design influence. These are suggested as being elements 3 (Horizontal Structure), 4 (Exterior Cladding), 5 (Interior Vertical), 7 (Interior Finishes), 8 (Plumbing and Drainage), 11 (HVAC) and 12 (Electrical).

4. Each University should initially concentrate on setting guidelines for the cost characteristics of the shell of future projects.

It is apparent that shell costs of university buildings are consistently high. Some of this (related to exterior wall in particular) may be specifically due to high quality exterior design, and this should be carefully evaluated as to its esthetic and functional characteristics, e.g., long life and low maintenance. The remainder is due to complexities of plan form, and the cost of horizontal structure, and savings should be possible here without jeopardizing legitimate programmatic or performance requirements.

5. The second phase of this study should be immediately implemented so as to include life costs, costs of maintenance, operations and change, and to analyze the validity of programmatic needs that result in higher performance requirements and higher cost elements.

While the present investigation provides good information on the relative costs of the elements of the buildings studied, and relates many of these costs to programmatic or performance needs, it cannot justify these needs themselves. To do this requires some study of requirements related to activities - what services and equipment are essential to what activities. In addition some performance items may be justified on a qualitative basis in that they may lengthen the life and reduce the costs of maintenance, operations, or change but this can only be demonstrated by an investigation of long-term building performance.

6. It is recommended that the formula allowance be formally reviewed yearly by a joint DCU/COU staff committee, not only to take escalation into account but also new information arising from on going studies and further experience.

Recommendations

- 75 -

7. It is further recommended that because all the unit costs derived above, including that for the total sample of university and non-university buildings, exceed \$55/NASF, an upward adjustment should be made in the unit cost allowance.

8. METHODOLOGY

a. Gross Building SamplesGross Sample and Selection of University Buildings - Heavy Service

The costs of heavy-service buildings were adjusted by the Southam Index to August 1971 (187.5).

		Project	Cost* /NASF	Tender Date	Southam Index	Adjusted Cost	Rank
Carleton	13	Social Science	\$63.76	3/66	127.4	\$ 93.70	3
Carleton	19	Biology	74.84	7/67	135.3	103.10	1
Carleton	29	Engineering	39.59	10/67	136.9	54.40	15
Guelph	04	Crop Science	58.98	7/66	131.3	84.10	5
Guelph	05	Animal Science	71.00	9/66	131.3	101.30	2
Guelph	07	Physical Sciences	55.18	6/67	135.1	77.00	6
McMaster	17	Psychology	54.16	3/68	139.8	73.00	7
McMaster	46	Life Sciences	55.31	8/70	168.6	61.50 ^{1/}	13
Ottawa	14	Engineering	42.69	2/69	146.2	54.80	14
Waterloo	35	Engineering	53.53	3/70	162.0	62.00	12
Western	34	Social Sciences	49.57	10/70	173.3	53.56	16
Windsor	03	Administration	42.57	3/66	127.4	62.80	11
Erindale	08	Research Laboratory	64.42	9/68	143.3	84.20	4
York	26	Science	47.06	9/66	131.3	67.20	8
Waterloo	58	Chemistry I	55.50	4/70	162.0	64.24	10
Western	22	Engineering	54.10	9/69	155.4	65.28	9

From this list, the 25th, 50th and 75th percentile buildings were selected. This would imply selecting the buildings with rank 4 or 5 (25th percentile), rank 8 or 9 (50th percentile) rank 12 or 13 (75th percentile). Therefore, the following buildings were selected for further study: GU04, WA35 and Y026.

*Cost shown on UACP Supplement D Report, subtotal "A" minus site development cost (element 9).

(1) not completed.

Methodology...

- 77 -

Gross Sample and Selection of University Buildings - Light Service

A selection procedure similar to that used for buildings with heavy-service was utilized for this category.

	Project		Cost* /NASF	Tender Date	Southam Index	Adjusted Rank Cost
Carleton	25	Administration	\$44.21	11/67	138.6	\$60.13 5
Carleton	49	Arts I	56.06	11/69	157.3	67.00 (1) 1
Carleton	58	Architecture	46.13	5/71	183.3	47.30 (1) 17
Erindale	13	Library	41.20	6/71	183.5	42.20 (1) 18
Lakehead	32	Academic Building	46.25	3/71	181.1	47.90 16
McMaster	35	Humanities & Soc. Sci.	46.06	3/69	146.2	59.10 9
Ottawa	34	New Child Study Center	45.42	3/69	146.2	59.60 6
Waterloo	17	Math & Computer	27.75	8/66	131.3	38.90 (1) 21
Waterloo	67A	Administration	34.28	3/71	181.1	35.50 (1) 23
Waterloo	67B	Student Services	35.01	3/71	181.1	36.30 (1) 22
York	44	Administrative Studies	47.82	8/70	168.6	53.20 (1) 10
York	63	College F	40.87	6/71	183.5	41.70 (1) 20
York	35	General Purpose	44.07	11/67	138.6	59.60 6
York	32	Law	42.86	6/67	135.1	59.48 8
York	36	Library	37.80	5/68	142.3	49.81 12
Queen's	631	Education	38.11	3/69	146.2	48.88 14
Queen's	632	Education	52.51	12/69	157.3	62.59 3
Western	20	Library	37.50	9/68	143.3	48.75 (1) 15
Ottawa	13	Library	57.19	5/70	166.8	41.90 (1) 19
Windsor	33	Library	44.00	11/69	157.3	52.40 11
Guelph	06	Library	42.40	8/66	131.1	61.00 4
Waterloo	28	Humanities	50.53	5/68	142.3	66.60 2
Windsor	24	Law	38.20	11/68	144.1	49.60 13

*Cost shown on UACP Supplement D report, subtotal "A" minus site development cost (element 9).

(1) not completed.

The projects ranked 13th and 6th were selected to represent the 50th and 25th percentile respectively. Since the buildings ranked 16th, 17th, 18th, 19th and 20th were not available for selection (they have not been completed and occupied and therefore would not satisfy the requirements for the second phase of the study) it was agreed to select the 21st-ranked building to represent the 75th percentile.

Gross Sample of Non-University Buildings

Gross Sample and Selection of Non-University Buildings - Light Service

Seneca College (1), North York
Seneca College (2), North York
Conestoga College, Kitchener
George Brown College, Toronto
York School of Nursing, North York
Etobicoke Education Center, Etobicoke
Brock Teachers College, St. Catherines
Sudbury Technical College
Greb Administration Building, Kitchener
Queen's Park II Offices, Toronto
Ogilvie Public School, Blackburn
Shoreham Public School
Jane Junior High School, North York
Aurora High School, Aurora
East End High School, Toronto
West End Secondary School, Toronto
Drug Addiction Research, Toronto
Bonaventure Office (General Purpose), Ottawa
Dept. of National Defense Offices, Ottawa
Dominion Bureau of Statistics Office, Ottawa
Royal Canadian Mounted Police Information Center, Toronto
Royal Canadian Mounted Police, National Police Sciences Office
Varette Office Building, Ottawa
AECL Administration Building, South March
System Dimension Limited, Offices, Ottawa
Morse Street Public School, Toronto
Special Vocational School for Girls, Toronto
Mississauga High School, Mississauga
North Bay High School, North Bay
York High School
Sudbury High School, Sudbury

Gross Sample and Selection of Non-University Buildings - Heavy Service

Dow Laboratory 1, Sarnia
Georgian CAAT IIIA, Barrie
West Park Vocational School, Toronto
Northern Electric Laboratory, Toronto
Agricultural Research Laboratory, Harrow
Food & Drug Laboratory, Toronto
AECL, Research and Development Building, Pinawa, Manitoba
AECL, Isotope Production Building, South March
St. Lawrence College, Kingston
Sheridan College, Oakville

b. Rules for Measurement of Areas

GROSS AREA - is the total areas measured flat on a plan for each floor from outside to outside of exterior walls. It includes the actual areas of balconies and mezzanines where these occur within the exterior walls of the building.

Floor areas of spaces extending through two or more floors shall be measured for the largest area at one level only. Such areas will not be factored as suggested by AIA, but the totals should be identified, if significant, for assessment purposes.

It includes all floor areas that have a headroom of six (6) feet or more, penthouses, machine rooms, enclosed connecting links, rooms below grade or sidewalks, true areas of columns, dormers and the like, provided these extend vertically for the full floor height.

It excludes tunnels with less than 6'0" head room, exterior balconies, canopies, areaways, covered walkways, unenclosed exterior staircases and fire escapes, exterior steps and landings, patios, terraces, roof overhangs and cornices and enclosed areas without roofs.

NET ASSIGNABLE AREA - is the area which may be assigned to a specific academic administrative, or general university activity function. This area does not include circulation and general service areas, such as corridors, staircases, restrooms, washrooms, janitors' closets, mechanical and electrical service rooms, building service staff facilities and general storage areas.

c. Element Descriptions

1. INDIRECT AND GENERAL EXPENSES

(a) Indirect and General Expenses

1. Access to site
2. Site offices, storage sheds, latrines, canteens, etc.
3. Site office expenses-telephone, stationery, etc.
4. Hoardings and barricades.
5. Temporary steps, stairs, ladders, scaffolding, etc.

6. Building permit.
7. Bonds - performance and payment.
8. Insurance - fire, public liability, payroll.
9. Financing.
10. Plant and equipment
11. Small tools.
12. Watching.
13. Final clean-up
14. Restoring sidewalks, curbs, etc.
15. Supervision - superintendent, engineer, clerks, etc.
16. Travelling and board.
17. Double shifting and overtime.
18. Job signs.
19. Photographs.
20. Special consideration such as traffic control, road cleaning, etc.

(b) Temporary Roads and Services

1. Temporary fire protection.
2. Temporary lighting, power and water.
3. Temporary roads and parking.

(c) Winter Conditions

1. Winter heat and protection.

(d) Head Office overhead and profit

2. SUBSTRUCTURE

- (a) Normal Foundations - this element includes excavation and concrete for wall and column footings, column caps, grade beams, foundation walls and for weeping tile.
- (b) Basement - this element includes the additional excavation and backfill required to construct a basement

Items excluded: basement walls and waterproofing, etc.

- (c) Special Foundations - this element includes caissons, piling, extra cost of excavating in rock, special shoring or dewatering, and other special foundation conditions.

3. HORIZONTAL STRUCTURAL ELEMENTS

- (a) Slabs on Grade - this element includes the slab, fill under the slab, waterproofing and skim coat, or vapour barrier to the slab and small sump pits, construction, expansion and waterproof joints.

Items excluded: final finish to the slab; machinery or boiler bases, structural slabs over crawl spaces.

- (b) Floor and Roof Construction - this element includes columns, beams, slabs, floor joists and sub-floors, base plates, anchor bolts and fireproofing for all suspended floors. Rafters, purlins, trusses, roof boarding, roof lights, etc., for the roof construction.

Items excluded: floor finishes, ceiling finishes roof finishes, insulation, cant strips, flashings, roof drains, eavestrough and rainwater leaders.

- (c) Roof Finish - this element includes the roof finish, insulation, cant strips, flashings, fascias, eaves, soffit, finish, barge boards, rooflights.

4. EXTERIOR CLADDING

- (a) Walls Below Grade - this element includes walls below grade level including waterproofing, insulation and integral pilasters.

Items excluded: wall finishes to the interior face of the wall.

- (b) Walls above Grade - this element includes all facing materials, backup, insulation, vapour barriers, strapping, damp-proof courses, construction and expansion joints and any applied finishes to external exposed parapet walls above roof line, etc. This element includes items associated with window openings, viz., lintels to support walls above, damp-proof courses, caulking, ornamental exterior treatment.

Items excluded: all finishes to the interior face of the wall.

- (c) Windows - this element includes frames, sash and glazing, hardware, mullions, transoms, sills, flyscreens, storm windows, curtain and window walls.

Items excluded: venetian blinds or sun-shades, valances, curtain tracks, curtains.

- (d) Exterior Doors, Entrances & Screens - this element includes doors, roll-up shutters, revolving doors, frames, sub-frames, and sills, lintels, damp-proof courses, surrounds, fly-screen and storm doors, decorations, caulking and special electric or hand-operated opening devices.

This element also includes all store fronts, glazed screens, decorative and functional screens and louvres.

- (e) Projections, Balconies, etc. - this element includes any item which, because of its existence, increases the area and cost of the exterior cladding. Examples are:

(1) Overhangs: If one floor projects beyond the floor below it, the exposed ceiling (but not the floor slab) will be included in this element.

(2) Balconies: Projecting balconies will be included in their entirety. Recessed balconies will include the cost of the balcony railing and the floor and exposed ceiling finishes to the balcony (not the building wall or floor slabs).

(3) Fixed and movable sunshades.

As it is often difficult to distinguish between walls, doors, windows and screens, as in the case of curtain walls, the above is given as a guide. Certain elements may have to be combined to avoid entirely arbitrary divisions.

5. INTERIOR VERTICAL ELEMENTS

- (a) Partitions - this element includes all interior walls and partitions including structural walls, glazed partitions, movable partitions.

Items excluded: All applied finishes to the partitions.

- (b) Folding Doors and Sliding Partitions - this element includes folding or rolling doors, screens and partitions that slide.

- (c) Doors - this element includes all interior doors including special doors, frames, decorations.

6. MULTI-STOREY ELEMENTS

- (a) Stairs, Steps and Ladders - this element includes all the treads, risers, stringers, landings, supporting framework, balustrades, handrails, soffit finishes, steps and ladders.
- (b) Catwalks and Gratings - this element includes service platforms, ladders, handrails, catwalks, usually associated with Laboratory Buildings.
- (c) Elevators and Hoists - this element includes all the passenger and freight elevators and hoists, entrances, cars, guides, machinery and general contractors' work to provide bases, sumps, fixings, etc.
- (d) Escalators

7. INTERIOR FINISHES

- (a) Floor Finishes - this element includes all floor finishes together with bases, curbs, mat sinkages, frames and mats.
- (b) Ceiling Finishes - this element includes all ceiling finishes, together with cornices.

Items excluded: Special illuminated or heated ceilings, valance boxes.

- (c) Wall Finishes - this element includes all applied finishes to walls and partitions.

Items excluded: Walls which are self-finished, when part of Element 5.

- (d) Special Finishes - this element includes such finishes as cork insulation for refrigerators, lead lining for x-ray rooms, special murals and similar unusual floor, ceiling and wall finishes.

Items excluded: prefabricated cold and refrigerated rooms, sound chambers, etc.

8. FITTINGS, FURNISHINGS AND BUILDING EQUIPMENT

- (a) Non Instructional - this element includes all special general service equipment such as kitchen equipment, pneumatic tube despatch system, stage, swimming pool or laundry equipment, etc.

All fittings and furnishings normally supplied under the general contract, such as: Cupboards, counters, benches, shelving, mirrors, washroom accessories, sculptures, planting boxes, magazine and record racks, tackboards and pinboards, etc., not used for teaching purposes.

- (b) Instructional - this element includes all fittings, furnishings and equipment normally supplied under the general contract, for teaching or research purposes and includes chalkboards, projection screens, built-in seats, etc.

9. CASH ALLOWANCES

This element includes all cash allowances which are normally stated in the specification and which cannot be allocated to any specific element. These might include: Critical Path, Testing and Inspection of Materials, Finishing Hardware, Laboratory Furniture, etc.

Design Contingency and Escalation Allowances shall be excluded.

10. PLUMBING & DRAINS

- (a) Roughing-in (Standard) - this element includes all storm, sanitary, hot and cold water piping systems within the exterior walls to washrooms, janitor's closets and all areas not included in 10 b below.
- (b) Roughing-in (Special) - this element includes all items in 10 a above to special laboratory instructional areas.
- (c) Plumbing Fixtures (Standard) - this element includes all finished plumbing such as water closet bowls, basins, sinks, trim, etc., to all areas not included in 10 d below.
- (d) Plumbing Fixtures (Special) - as 10 c above to laboratory and instructional areas.
- (e) Fire Protection - this element includes standpipe, fire hose cabinets and sprinkler systems within the building.

Exclude: fire alarm system, if carried in Element 12 d

- (f) Special Services System - this element includes the various special plumbing systems, such as glass and resistant waste, ionized water, liquid soap, waste neutralization facilities, etc.

11. HEATING, VENTILATING, AIR CONDITIONING

- (a) HVAC - this element includes heating systems, air conditioning and refrigeration, ventilation systems, controls, insulation and plant.
- (b) Special Systems - this element includes compressed air, vacuum, oxygen or other gas and special facility distribution systems.

12. ELECTRICAL

- (a) Transformers and Distribution - this element includes the primary and secondary transformers and the power and lighting distribution system panels, receptacles and outlets.
- (b) Lighting Fixtures and Branch Wiring - this element includes all lighting fixtures, tubes and branch wiring.
- (c) Underfloor Duct Systems - this element includes the complete underfloor duct system for power, telephone, P.A., T.V.

Exclude: Cellular decks that are included in 3 b.

- (d) Special Services - this item includes all special services such as: wiring and equipment as appropriate for P.A., telephones, radio, fire alarm, emergency lighting, connections for kitchen, laboratory and other special teaching and research equipment, stage lighting, doctors' and nurses' call systems, intercom, central dictaphone, automatic electric locks, T.V. system, provision for future expansion, etc.

Exclude: conduit, if carried in a.

9. GLOSSARY

A.C.	Air Conditioning
BTU/HR	British Thermal Units per hour
CAAT	College of Applied Arts & Technology
CCF	Committee on Capital Financing
C.F.	Cubic Feet
C.F.M.	Cubic feet per minute
COU	Council of Ontario Universities
DCU	Department of Colleges and Universities, previously known as Department of University Affairs (DUA) and recently changed to Ministry of Colleges and Universities.
Element	A major component common to most buildings, usually fulfilling the same function irrespective of its design, specification or construction.
GSF	Gross Square Feet measured in accordance with the rules set out in Section 8b.
Heavy Service Buildings	Science or Engineering buildings containing a high proportion of laboratories or research space.
H.V.A.C.	Heating, Ventilating and Air Conditioning
Light Service Buildings	All buildings not regarded as being heavy service.
NASF	Net Assignable Square Feet, measured in accordance with rules set out in Section 8b.
Shell	All elements comprising the basic building carcass, being foundations, slabs on grade, floor and roof construction, roof finish and all exterior cladding, together with a pro rata allocation of indirect and general expenses.

ED 069254

SUPPLEMENT TO
REPORT OF THE TASK FORCE - BUILDING COSTS

Council of Ontario Universities
Conseil des Universités de l'Ontario
102 Bloor Street West, Toronto 181, Ontario

72-12S
August 1972

This supplement contains the elemental cost analysis and performance and statistical data upon which the report of the C.O.U. Task Force - Building Costs is based. The material has been copied on pre-punched paper and it is suggested that it be placed in a three-ring binder for the convenience of the user.

INDEX

	Page
A. <u>Elemental Cost Analysis and Performance and Statistical Data</u>	
1) Child Study Centre, Ottawa	1
2) Law Building, Windsor	14
3) Crop Science Building, Guelph	27
4) Petrie Science Building, York	40
5) Mathematics and Computer Building, Waterloo	53
6) Engineering IV Building, Waterloo	66
7) Northern Electric, Toronto	79
8) Systems Dimensions Limited, Ottawa	92
9) Varette Office Building, Ottawa	105
10) General Purpose Office Building, Ottawa	118
11) Food and Drug Building, Toronto	131
12) Georgian CAAT IIIA, Barrie	145
B. <u>Elemental Unit Rates</u>	157

- 1 -

CHILD STUDY CENTRE, OTTAWA

Project: OTTAWA 34 - CHILD STUDY CENTRE
COST ANALYSIS

ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet
No: 1

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / CFSF
		Quantity	Unit Rate	Unit of Measure	Sub-Element	Element
1	INDIRECT & GENERAL EXPENSES	-	-	-	177,000	3.Cu 0.0
2	SUBSTRUCTURE	11,010	5.41	SF Grade Area	55,590	1.62 3.C
	a) Normal Foundations	148	118.64	CY Concrete	17,560	0.30
	b) Basement Excavations	55,800	0.19	CY Basement Vol.	10,520	0.10
"	c) Special Foundations	4,120	7.64	L.F PC Piles	31,500	0.54
3	HORIZONTAL STRUCTURAL ELEMENTS	64,405	3.46	SF Struct. Area	223,950	3.84 11.5
	a) Slabs on Grade	11,010	1.25	SF Slab Area	13,840	0.24
	b) Floor & Roof Construction	53,395	3.47	SF Slab Area	185,210	3.12
	c) Roof Finish	11,070	2.17	SF Roof Finish	24,000	0.41
4	EXTERIOR CLADDING	60,224	5.72	SF Wall Area	343,530	6.03 17.8
	a) Walls below Grade	5,873	4.25	SF Wall Area	24,980	0.43
	b) Walls above Grade	46,981	5.04	SF Wall Area	237,130	4.87
	c) Windows	6,410	12.29	SF Window Area	78,810	1.35
	d) Exterior Doors, Entrances, Screen	312	18.62	SF Opening Area	5,810	0.10
	e) Projections, Balconies, Etc.	610	2.91	SF Soffit Area	1,890	0.03
5	INTERIOR VERTICAL ELEMENTS	54,386	2.45	SF Part. Area	133,780	2.30 6.8
	a) Partitions :	49,513	1.87	SF Part. Area	92,170	1.58
	b) Folding or Sliding Partitions	568	14.34	SF Part. Area	8,150	0.14
	c) Doors	205	163.21	Per Door Leaf	33,460	0.58

Hanscomb
Roy
Associates




Project: OTTAWA 34 - CHILD STUDY CENTRE
COST ANALYSIS - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet
No: 2

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / OSRF	%
		Quantity	Unit Rate	Unit of Measure	Sub-Element	Element	Sub-Element
6	MULTI-STORRY ELEMENTS	-	-	-	20,950	1.39	11.2
a)	Stairs, Steps & Ladders	21	2093	SF on Plan: SF on Plan:	113,950	0.76	
b)	Catwalks, Gratings	-	-	SF on Plan'	-	-	
c)	Elevators & Hoists (Garbage Lift)	6	6166	Per Stop	37,000	0.63	
d)	Escalators	-	-	Per Floor	-	-	
7	INTERIOR FINISHES	-	-	-	182,076	3.13	2.3
a)	Floor Finishes	46,614	1.54	SF Finished Area	71,800	1.23	
b)	Ceiling Finishes	52,040	1.34	SF Finished Area	70,030	1.21	
c)	Wall Finishes	66,181	0.60	SF Fin. Wall Area	40,240	0.69	
d)	Special Finishes	-	-	-	-	-	
8	FITTINGS, FIXTURES & EQUIPMENT	-	-	-	57,400	0.99	3.0
a)	Non Instructional	-	-	-	50,100	0.87	
b)	Instructional	-	-	-	7,000	0.12	
9	CASH ALLOWANCES	-	-	-	52,000	0.89	2.6
a)	Hardware	205	1.95	Per Unit	10,000	0.69	
b)	Testing and Inspection	-	-	-	12,000	0.20	

E-9

97



Hanscomb
Roy
Associates


Project: OTTAWA 34 - CHILD STUDY CENTRE
 - ALL COSTS ON A SIGHTMEP 1971 TORONTO BASE

Sheet
No: 3

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / OSRF	%
		Quantity	Unit Rate	Unit of Measure	Sub-Element	Sub-Element	Element
10	PLUMBING & DRAINS	-	-	-	112,000	1.33	5.7
a)	Roughing-In (Standard)	95	533	Per Fixture	51,250	0.23	
b)	Roughing-In (Special)	46	476	Per Fixture	21,945	0.38	
c)	Plumbing Fixtures (Standard)	95	215	Per Fixture	20,750	0.35	
d)	Plumbing Fixtures (Special)	36	224	Per Fixture	8,755	0.14	
e)	Fire Protection	8	1250	Per Cabinet or Per Head	10,000	0.17	
f)	Special Services	-	-	Per Outlet	-		
11	HEATING, VENTILATING & AIR COND'G.	-	-	-	285,000	4.90	14.6
a)	HVAC	-	-	-	285,000	4.90	
b)	Special Systems	-	-	-	-	-	
12	ELECTRICAL	-	-	-	243,000	4.18	12.5
a)	Transformers & Distribution	-	-	-	31,200	0.54	
b)	Lighting Fixtures & Branch Wiring	-	-	-	33,860	1.61	
c)	Underfloor Duct Systems	-	-	-	-	-	
d)	Special Systems	-	-	-	117,920	2.03	
	Federal Sales Tax				1,954,360 (78,160)	\$ 32.61 (1.33)	100%
					\$ 376,200	\$ 32.27	

♦ \$54.28 / OSRF

Hanscom
Roy
Associates




E-9

CO

Project: OTTAWA 34 - CHILD STUDY CENTRE COST RECC ORGANIZATION			Sheet No. 11
A)	BUILDING CONTRACT COST (Low Bid)	\$ 1,863,900	
	<u>DEDUCTIONS</u>		
	1. Contingency (Specified Allowance)	\$ 40,000	
	2. Kitchen Equipment (Low Bid)	25,000	
	3. Exterior Services (Low Bid)	12,000	
	4. Exterior Light Standards (Specified Allowance)	1,500	
	5. Landscaping, Paving and Miscellaneous Site Work (Low Bid)	58,000	
	6. Miscellaneous Alterations (Estimated)	15,000	
	7. Tunnel (Estimated)	<u>10,000</u>	
		<u>161.500</u>	
	8. Federal Sales Tax		
b)	ADJUSTED BUILDING COST AT APRIL, 1969	\$ 1,634,300	
c)	BUILDING CONTRACT COST AT SEPTEMBER 1971 PER COST ANALYSIS	<u>1,876,200</u>	
d)	COST INCREASE - APRIL 1969 to SEPTEMBER 1971	\$ <u>241,900</u>	

The above reflects an increase, or escalation factor of 14.8% of adjusted original low bid amount.


99



E-9

GENERAL DATA:

Cross Floor Area	58,150 Sq. Ft.
Net Assignable Floor Area	35,000 Sq. Ft.
Cubic Volume	670,000 Cu. Ft.
Net Assignable Floor Area/Cross Floor Area	0.62:1 Ratio
Exterior Wall Area/Cross Floor Area	1.02:1 Ratio
Roof Area/Cross Floor Area	0.20:1 Ratio
Volume/Cross Floor Area	11.52:1 Ratio
Floors At and Above Grade	6 No.
Floors Below Grade	1 No.



Hanscomb
Roy
Associates

Project: OTTAWA 34 - CHILD STUDY CENTRE
PERFORMANCE & STATISTICAL DATA

**Sheet
No:** 1

1. INDIRECT & GENERAL EXPENSES


Construction Period	17 months
Winter Construction Period	5 months
Performance Bond	\$500
Fire Insurance by Owner	No
Market Conditions	Slack (3 bids, range 12%)

2. SUBSTRUCTURE

Type of Soil	Layered fill, sand, clay, silt, shale.
Water-table	Not known
Bearing Capacity of Soil	Not known - but poor since piles are required.
Slope of Site	Fill

3.(b) HORIZONTAL STRUCTURAL ELEMENTS

Structure Type and Material	Reinforced concrete, flat slab and bears on columns.
Shear Structure	Reinforced concrete wall.
Structural Bay Sizes	Average 24' x 24'
Floor to Floor Heights	2' 11" 5-1/2"; 4' 2" 10" u"
Structural Depth	Average 8"
Floor Live Loading	130 lbs./sq. ft. - average
Roof Live Loading	48 lbs./sq. ft. - average



**Hanscomb
Roy
Associates**

Project: OTTAWA 34 - CHILD STUDY CENTRE
PERFORMANCE & STATISTICAL DATA

Sheet
No: 7

3.(c) ROOF FINISH

Roof Finish Type	4 ply felt and asphalt with gravel surface;
Vapour Barrier; 1-1/2" insulation.	
Rooflights	24
Perimeter/Roof Area	1:21 Ratio
"U" Factor	0.15

4. EXTERIOR CLADDING


Total Sq. Ft. Glazed (Above Grade)	125
Gross Glazed Area Openable	71%
Sun Control Measures	Tinted glass
Wall Thickness	15" (4" P.C.: 2" Air: 1" insul.: 2" concrete deckings)
Unlazed "U" Factor	0.144
Inside Face Material	Concrete, concrete block
Exterior Face Material and Finish	Precast concrete-expired multi-coloured aggregate in white cement finish: high proportion of non-repetitive panels : poured concrete-sandblasted finish.
Window Type	Aluminum framed projected, top hinge or hinge-in vents, permanent finish.
Glazing Type	Double

5. INTERIOR VERTICAL ELEMENTS

Linear Feet Partitions/Cross Floor Area	1:11.63 Patio
---	---------------

E-9

**Hanscomb
Roy
Associates**



5. INTERIOR VERTICAL ELEMENTS (cont'd.)


Partition Types	Type	% Area	Height
- Structural (Load-Bearing)	Concrete	17%	Av. 10' 0"
- Replaceable	Concrete Block	30%	Av. 2' 4"
.....	Drywall and S.S.	50%	Av. 9' 0"
.....	Glazed	2%	Av. 3' 0"
- Sliding and Folding	Vinyl Clad Steel	1%	2' 0"
Door Types	Hollow metal, solid core wood, some having glazed panels.		
Doors Ratio	4.1 per 100 Lin. Ft. Partition		

6. MULTI-STORY ELEMENTS

Staircase Types	Poured concrete, spine wall, sandblasted finish.
Elevator Types	Electric traction 1 - 2500# passenger, 200 rpm., 6 floors, 6 openings.
Hoist Types	Mil

7. INTERIOR FINISHES

Floors	Generally carpet, 1/8" vinyl asbestos tile, quarry tile, resilient wood.
Ceilings	Generally suspended painted metal "paraline"; suspended gypsum with painted or texture sprayed finish, acoustic tile on fyrroc.



Project: OTTAWA 3H - CHILD STUDY CENTRE
PERFORMANCE & STATISTICAL DATA


Sheet
No.: 3

- 10 -

7.	<u>INTERIOR FINISHES (cont'd.)</u>	
	Walls	Generally painted concrete, block and drywall; plastic paint, painted plaster on block and concrete, ceramic tile.
8.	<u>FITTINGS, FIXTURES & EQUIPMENT</u>	
	(a) Non-Instructional	Washroom accessories, vanities, shelving, coat closets and cupboards, valances, curtains, miscellaneous metal items.
	(b) Instructional	Chalk and tack boards, projection screens.
9.	<u>CASH ALLOWANCES</u>	
	(a) Finishing Hardware	
	- Type	Standard
	- Finish	Stainless steel
	(b) Inspection and Testing	Pile load, compaction, concrete, roofing, precast concrete.
10.	<u>PLUMBING AND DRAINS</u>	
	Hot and Cold Water Pipe Type	Type "L" Copper
	Sanitary Soil Pipe Type	Cast Iron
	Sanitary Waste, Ventilating Piping Type	D'V Copper
	Special Piping Type	N/A
	Plumbing Fixtures Density per 1000 S.F.	2.2

E-9

**Hanscomb
Roy
Associates**



Project: OTTAWA 34 - CHILD STUDY CENTER
PERFORMANCE & STATISTICAL DATA

Sheet
No: 1.)


10. PLUMBING AND DRAINS (cont'd.)

Special Services Mil

11. HEATING, VENTILATING, AIR CONDITIONING (HVAC)

% Building Served by AC	100%
Heating Source	Remote
Fuel	Remote
Cooling Source	Remote
Air Handling Source	Building
Capacities Heating	3,700,000 BTU/hp
Cooling Capacity	167 tons
Air Handling CFM	62,000 CFM
Heating Ratio	63.5 BTU/Hp per Sq. Ft.
Cooling Ratio	3.21 tons per 1000 SF
Ventilation Ratio	1.09 CFM per Sq. Ft.
% Return Air	82%
% Main Exhaust	2%
Thermostats per 1000 SF	1.95
Control Zones	None -(individual control)
Special Systems	Mil

**Hanscomb
Roy
Associates**



Project: OTTAWA 34 - CHILD STUDY CENTRE
PERFORMANCE & STATISTICAL DATA

**Sheet
No: 11**

12. ELECTRICAL

1. Substation

- Characteristics of Primary Volt: 370 .. Not applicable (voltage was obtained at 600v from nearby structure.)
- KVA Rating/Area Sq. Ft. Not applicable
- Primary Protection Not applicable
- Secondary Protection Breaker
- Main Distribution Board Not applicable

2. Distribution

- Related to Type of Structure Mixed
- Voltage of Main Distribution 600v
- Transformation to 120/240v Scattered

3. Lighting


- Average Intensity of General Lighting In F.C. 70
- Average Cost of General Lighting Fixtures 65
- Branch Circuit Characteristics 120/240v
- Switching Local Switching

4. Motors

- Motor Control Centre Included
- Base Building Facilities Air Conditioning

5. Fire Alarm

- Requirements Heavy



Project: OTTAWA 34 - CHILD STUDY CENTRE
PERFORMANCE & STATISTICAL DATA


Sheet
No: 12

12. ELECTRICAL (cont'd.)

- 5. Fire Alarm (cont'd.)
 - Smoke Detection
- 6. Clocks
 - Average Number Clocks Minimum
- 7. Telephone
 - Average Number Telephones Minimum
- 8. T.V.
 - Characteristics
- 9. Special Requirements of Typical Occupancy:
 - Some Stage Lighting Approx. \$15,500
 - Some Intercom Approx. \$4,500
 - Some Snow Melting Approx. \$7,000
 - Lighting on 120/208V System
 - Sound System Approx. \$25,000
 - Telephone Approx. \$1,000
 - Emergency Generator Approx. \$15,000

- 13 -

E-9



Hanscomb
Roy
Associates

- 14 -

LAW BUILDING, WINDSOR

Project: WINDSOR 24 - LAW BUILDING
COST ANALYSIS

ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / OGSR	Sub-Element	Element	S.
		Quantity	Unit Rate	Unit of Measure			Sub-Element		
1	INDIRECT & GENERAL EXPENSES	-	-	-	215,000			2.53	9.1
2	SUBSTRUCTURE	29,700	3.44	SF Grade Area	102,250			1.20	4.3
	a) Normal Foundations	275	13.45	SF Concrete	25,700	0.30			
	b) Basement Excavations	175,811	0.08	SF Basement Vol.	14,550	0.17			
"	c) Special Foundations	-	-	Caisson Piling	62,000	0.73			
3	HORIZONTAL STRUCTURAL ELEMENTS	116,933	4.32	SF Struct. Area	513,500			6.03	21.6
	a) Slabs on Grade	29,700	1.06	SF Slab Area	31,450	0.37			
	b) Floor & Roof Construction	87,233	4.76	SF Slab Area	415,250	4.88			
	c) Roof Finish	32,305	2.03	SF Roof Finish	65,800	0.78			
4	EXTERIOR CLADDING	46,480	6.14	SF Wall Area	285,490			3.35	12.0
	a) Walls below Grade	4,737	4.10	SF Wall Area	19,450	0.23			
	b) Walls above Grade	27,806	4.55	SF Wall Area	126,410	1.48			
	c) Windows	9,565	12.84	SF Window Area	122,850	1.44			
	d) Exterior Doors, Entrances, Screen	571	12.67	SF Opening Area	7,240	0.09			
	e) Projections, Balconies, Etc.	3,800	2.50	SF Soffit	9,510	0.11			
5	INTERIOR VERTICAL ELEMENTS	66,208	2.50	SF Part. Area	165,390			1.34	7.0
	a) Partitions	61,560	1.85	SF Part. Area	113,860				
	b) Folding Partitioning	1,120	20.53	SF Part. Area	23,000			0.27	
	c) Doors	168	170.00	Per Door Leaf	28,530			0.33	

E-9

Transcom
TROY
Associates



Project: WINDSOR 24 - LAW BUILDING

ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / GCSF	%
		Quantity	Unit	Unit of Measure			
6	MULTI-STORY ELEMENTS	-	-	Per Flight Staircase/Plank	68,750	0.81	2.9
a)	Stairs, Steps & Ladders	23	1807	Per Flight Staircase/Plank	41,570	0.49	
b)	Catwalks, Gratings	-	-	SF on Plan	-	-	
c)	Elevators & Hoists	4	6750	Per Stop	27,000	0.32	
d)	Escalators	-	-	Per Floor	-	-	
-	INTERIOR FINISHES	-	-	-	231,866	2.72	9.8
a)	Floor Finishes	82,000	1.06	SF Finished Area	86,466	1.02	
b)	Ceiling Finishes	82,000	1.01	SF Finished Area	82,000	0.96	
c)	Wall Finishes	128,000	0.45	SF Fin. Wall Area	63,340	0.74	
d)	Special Finishes	-	-	-	-	-	
8	FITTINGS, FIXTURES & EQUIPMENT	-	-	-	66,000	0.77	2.8
a)	Non Instructional	-	-	-	32,000	0.37	
b)	Instructional	-	-	-	34,000	0.40	
9	CASH ALLOWANCES	-	-	-	37,000	0.44	1.6
a)	Hardware	188	165	Per Unit	31,000	0.36	
b)	Inspections and Testing	-	-	-	6,000	0.08	

- 16 -

110

E-9



Hanscomb
Roy
Associates


Project: WINDSOR 24 - LAW BUILDING

- ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet
No. 3

No.	ELEMENT	ELEMENTAL COST			Sub-Element	UNIT RATE / OSF	%
		Quantity	Unit Rate	Unit of Measure			
10	PLUMBING & DRAINS	-	-	-	61,200	0.72	2.5
	a) Roughing-In (Standard)	54	830	Per Fixture	48,000	0.56	
	b) Roughing-In (Special)	-	-	Per Fixture	-	-	
	c) Plumbing Fixtures (Standard)	54	223	Per Fixture	12,000	0.14	
	d) Plumbing Fixtures (Special)	-	-	Per Fixture	-	-	
	e) Fire Protection	23	52	Per Cabinet or Door Head: Fire Outlets	1,200	0.02	
	f) Special Services				-	-	
11	HEATING, VENTILATING & AIR COND'G.	-	-	-	383,000	4.50	16.2
	a) HVAC	-	-	-	383,000	4.50	
	b) Special Systems	-	-	-	-	-	
12	ELECTRICAL	-	-	-	241,640	2.84	10.1
	a) Transformers & Distribution	-	-	-	67,710	0.90	
	b) Lighting Fixtures & Branch Wiring	-	-	-	114,350	1.34	
	c) Underfloor Duct Systems	-	-	-	-	-	
	d) Special Systems	-	-	-	59,530	0.70	
	Federal Sales Tax Rebate				2,371,080 (94,950)	27.65 (1.11)	100.3
					\$ 2,270,230	26.74	

* \$45,33 / OSF

Hanscomb
Roy
Associates

E-9

111

Project: WINDSOR 24 - LAW BUILDING
COST RECONCILIATION


Sheet
No: 4

A) BUILDING CONTRACT COST (Low Bid)

DEDUCTIONS:

1.	Landscaping	(Specified Allowance)	\$ 20,000
2.	Paving	(Low Bid)	4,500
3.	Seed and Sod	(Low Bid)	730
4.	Miscellaneous Exterior Work (Estimated)		20,000
5.	Tunnel - Complete	(Estimated)	32,000
6.	Contingency	(Specified Allowance)	<u>1,000</u>
7.	Federal Sales Tax		<u>87,230</u>
			2,009,770
			<u>80,350</u>
B)	ADJUSTED BUILDING CONTRACT COST AT OCTOBER 1968		1,929,380
C)	BUILDING CONTRACT COST AT SEPTEMBER 1971 PER COST ANALYSIS		<u>2,276,230</u>
			<u>\$ 346,850</u>

The above reflects an increase, or escalation factor of
18% of adjusted original low bid amount.



**Hanscomb
Roy
Associates**

Project: WINDSOR 24 - LAW BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 5

GENERAL DATA:


Gross Floor Area	85,146 Sq. Ft.
Net Assignable Floor Area	52,311 Sq. Ft.
Cubic Volume	1,214,843 Cu. Ft.
Net Assignable Floor Area/Gross Floor Area	0.61:1 Ratio
Exterior Wall Area/Gross Floor Area	0.50:1 Ratio
Rooftop Area/Gross Floor Area	0.39:1 Ratio
Volume/Gross Floor Area	14.27:1 Ratio
Floors At and Above Grade	2 No.
Floors Below Grade	1 No.

- 19 -

E-9

113

Hanscomb
Roy
Associates



Project: WINDSOR 24 - LAW BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: C

1. INDIRECT & CAPITAL EXPENSES


Construction Period	22 months
Winter Construction Period	9 months
Performance bond	5C%
Fire Insurance by Owner	No
Market Conditions	Slack (4 bids, range 11%)

2. SUBSTRUCTURE

Type of Soil	Varied - dry brown clay to very wet silty blue clay to bedrock at 90' + 15 feet below grade
Watertable	Varies with depth of excavation - 4000 to 6000 lbs./Sq. Ft. at 4' to 3', reducing to 0 at 20'.
Bearing Capacity of Soil	
Slope of Site	0%.

3. (b) HORIZONTAL STRUCTURAL ELEMENTS

Structural Type	Slab, beam and girder.
Material	Reinforced concrete
Shear Structure	Wall
Structural Bay Sizes	30' x 20'
Floor to Floor Heights	12' 5-3/8" (2) and 12' 3-7/8"
Structural Depth	Top of slab to bottom of girder - 4' 3-1/2"
Floor Live Loading	Library 150 lbs./Sq.Ft.; classrooms 100 lbs./Sq.Ft. Mech. room 125 lbs./Sq. Ft.
Roof Live Loading	30 lbs./Sq. Ft.



**Hanscomb
Roy
Associates**

**Project: WINDSOR 24 - LAW BUILDING
PERFORMANCE & STATISTICAL DATA**


Sheet
No: 7

3. (c) ROOF FINISH

Roof Finish Type	4 ply felt and pitch, double gravel surfacing:
	vapour barrier: 1-1/2" insulation: aluminum
	flashings with duracron finish.
Rooflights	nil
Perimeter/Roof Area	1:18
"U" factor	0.15

4. EXTERIOR CLADDING

% Total Sq. Ft. Glazed (Walls above grade)	25%
% Glazed area operable	25
Sun Control Measures	nil
Wall Thickness	9", 13", 17"
Un glazed "U" Factor	Gyproc
Inside Face Material	Facebrick
Exterior Face Material)
Exterior Finish)
Window Type	Aluminum, duracron finish. 50% of windows are sloped or skylight type.
Glazing Type	Hermetically sealed double in windows- wired Georgian cast and fiberglass reinforced translucent panels in skylights



Project: WINDSOR 24 - **W** BUILDING
PERFORMANCE & STATISTICAL DATA

**Sheet
No:** 3

5. INTERIOR VERTICAL ELEMENTS

Linear Feet Partitions/Gross Floor Area	Type	% Area	Height
1:16.4	Concrete	33	11' 9"
- Structural (Load Bearing)	Facebrick	17%	Av. 11' 0"
- Replaceable	Concrete Block	31%	Av. 11' 0"
.....	Drywall	45%	Av. 9' 0"
.....	Glazed	2%	Av. 8' 0"
- Folding	Insul. Steel Soundroof	2%	16' 0"
.....			16' 0"

Door Types Hollow metal, plastic laminate solid core, steel vault, some doors with glazed panels.

Doors Ratio 3.2 per 100 Lin. Ft. partition

6. MULTI-STORY ELEMENTS

Staircase Types	Concrete filled steel pan, quarry tile finish
Elevator Types	Electric traction - i No. 250K passenger, 100 FPM, 3 floors, 5 openings.
Hoist Types	nil

7. INTERIOR FINISHES

Floors Generally carpet, 1/8" vinyl asbestos tile, quarry tile, ceramic tile, scolded concrete.

**Hanscomb
Roy
Associates**

Project: MINDORP 2N - LAW BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 9

- 23 -

7. INTERIOR FINISHES (cont'd.)

- | | |
|----------------|--|
| Ceilings | Generally suspended lay-in acoustic tile;
suspended metal linear acoustic system,
suspended dryproc, special sloped plaster. |
| Walls | Generally painted block, concrete and drywall;
ceramic tile, vinyl fabric; special acoustic
finish. |

8. FIXTURES, FIXTURES & EQUIPMENT

- | | |
|-----------------------------|--|
| (a) Non-Instructional | Mashrobi accessories, vanities, shelving,
cupboards, lockers. |
| (b) Instructional | Laboratory furniture, chalk and tack boards,
book shelving, projection screens. |


9. CASH ALLOWANCES

- | | |
|----------------------------------|--------------------------------------|
| (a) Finishing Hardware: | |
| - Type | Standard |
| - Finish | Stainless Steel |
| (b) Inspection and Testing | Concrete, roofing, structural steel. |

10. PLUMBING AND DRAINS

- | | |
|---------------------------------------|---|
| Hot and Cold Water Piping Type | Type K Copper |
| Sanitary Soil Pipe Type | Cast iron - Type K Copper |
| Sanitary Waste, Ventilating Piping .. | Vents: below floor - Type K Copper
above floor - Type K Copper |

**Hanscomb
Roy
Associates**



E-9

**Project: MINDOR 24 - LAW BUILDING
PERFORMANCE & STATISTICAL DATA**


**Sheet
No: 2.5**

10. PLUMBING AND DRAINS (cont'd.)

Special Piping Type	None
Plumbing Fixtures Density per 1000 S.F.	0.64
Special Services	None

11. HEATING, VENTILATING AIR CONDITIONING (HVAC)

% Building Serviced by AC	100%
Heating Source	Remote
Fuel	None
Cooling Source	Remote
Air Handling Source	Building
Capacities Heating	4000 BTU radiation 3,300 BTU heating coils 40,000 CFM
Cooling Capacity	272 tons -
Air Handling CFM	87,100 CFM
Heating Ratio	43.5 BTU/BTU/SF
Cooling Ratio	3.2 tons/1000 SF
Ventilation Ratio	1,025 CFM/SF
% Return Air	Summer - 73%: Winter - 65%
% Main Exhaust	Summer - 27%: Winter - 35%
Thermostats per 1000 SF	1.13
Control Zones	Dual duct mixing units - total 101 room thermostats.
Special Systems	Mashroom exhaust - 3600 CFM; tunnel exhaust - 2500 CFM; "tech. room exhaust - 1000 CFM; transformer room exhaust - 3600 CFM.



12. ELECTRICAL

1. Substation

- Characteristics of Primary Voltage . 5 kV
- Characteristics of Secondary Voltage
- kVA Rating/Cross Area Sq. Ft. 120/208v
- Primary Protection 10 Watts/Sq. Ft.
- Secondary Protection Load Break Switch
- Main Distribution Board Breaker
- Main Distribution board Molded Case

2. Distribution


- Related to Type of Structure Mixed
- Voltage of Main Distribution 120/208v
- Transformation to 120/208v Central

3. Lighting

- Average Intensity of General Lighting in F.C. 80
- Average Cost of General Lighting Fixtures \$25.00
- Branch Circuit Characteristics ... E.T
- Switching L.V. switching

4. Motors

- Motor Control Centres Included
- Ease Building Facilities Air Conditioning;



Hanscomb
Roy
Associates


Project: WINDSOR 24 - LAW BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 12

12. ELECTRICAL (cont'd.)

5. Fire Alarm
- Requirements minimum
- Smoke Detection
6. Clocks
- Average Number Clocks 1:2,000 Sq. Ft.
7. Telephone
- Average Number Telephones None
8. T.V.
- Characteristics Close Cct. System
9. Special Requirements of Typical
Occupancy
- Laboratory None

120



Hanscomb
Roy
Associates

- 27 -

CROP SCIENCE BUILDING, GUELPH


Project: CULLIPI 04 - CPOP SCIENCE BUILDING
COST ANALYSIS - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASIS:

Sheet
No: 1

No.	ELEMENT	ELEMENTAL COST			Sub-Element	UNIT RATE / OGSF	%
		Quantity	Unit	Rate	Unit of Measure		
1	INDIRECT & GENERAL EXPENSES	-	-	-	-	304,000	3.11
2	SUPERSTRUCTURE	50,700	3.08	SF Grade Area	16,000	1,47	3.5
a)	Normal Foundations	630	139.37	CY Concrete	87,800	0.83	
b)	Basement Excavations	150,164	0.45	CF Basement Vol.	68,240	0.64	
c)	Special Foundations	-	-	-	-	-	
3	HORIZONTAL STRUCTURAL ELEMENTS	172,611	3.60	SF Struct. Area	623,360	5.68	13.3
a)	Slabs on Grade	50,115	1.46	SF Slab Area	73,160	0.69	
b)	Floor & Roof Construction	122,696	3.93	SF Slab Area	488,580	4.61	
c)	Roof Finish	53,490	1.15	SF Roof Finish	61,600	6.58	
4	EXTERIOR CLADDING	75,131	5.62	SF Wall Area	472,200	3.37	1.4
a)	Walls below Grade	18,547	5.17	SF Wall Area	95,810	0.99	
b)	Walls above Grade	46,231	4.25	SF Wall Area	229,560	2.16	
c)	Windows	5,889	10.50	SF Window Area	61,830	5.98	
d)	Exterior Doors, Entrances, Screen	1,473	14.22	SF Opening Area	20,250	0.29	
e)	Projections, Balconies, Etc.	2,891	4.85	SF Soffit Area	14,050	0.14	
5	INTERIOR VERTICAL ELEMENTS	83,367	2.35	SF Part. Area	194,720	1.84	4.3
a)	Partitions	76,097	1.93	SF Part. Area	141,160	1.33	
b)	Folding or Sliding Partitions	520	12.03	SF Part. Area	6,240	0.07	
c)	Doors	291	160.00	Per Door Leaf	46,560	0.14	

E-9

Hanscomb
Roy
Associates



Project: CWFPHI Out - CROP SCIENCE BUILDING
COST ANALYSIS - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet
No: 2

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / ORSF	%
		Quantity	Unit Rate	Unit of Measure			
6	MULTI-STORY ELEMENTS	-	-	-	71,360	71.36	1.6
a)	Stairs, Steps & Ladders	9	1.84	Per Flight	16,600	0.15	
b)	Catwalks, Gratings	788	3.00	SF on Plan	2,360	0.02	
c)	Elevators & Hoists	9	5,778	Per Step	52,000	0.43	
d)	Escalators	-	-	Per Floor	-	-	
-	-	-	-	-	218,360	2.05	4.5
7	INTERIOR FINISHES	-	-	-			
a)	Floor Finishes	47,524	1.44	SF Finished Area	69,630	0.66	
b)	Ceiling Finishes	106,732	0.87	SF Finished Area	83,800	0.79	
c)	Wall Finishes	126,572	0.44	SF Fin. Wall Area	53,160	0.55	
d)	Special Finishes	22,549	0.33	SF Finished Area	6,770	0.05	
8	FITTINGS, FIXTURES & EQUIPMENT	-	-	-	459,430	4.31	7.6
a)	Non Instructional	-	-	-	12,440	0.12	
b)	Instructional	-	-	-	338,990	3.19	
9	CASH ALLOWANCES	-	-	-	41,000	0.31	0.7
a)	Hardware	300	120.00	Per Unit	36,000	0.31	
b)	Inspections & Testing	-	-	-	5,000	0.05	

E-9



Hanscomb
Roy
Associates

123

Project: GUELPH ON - CPOP SCIENCE BUILDING
 COST ANALYSIS - FULL COSTS OF A SEPTEMBER 1971 TORONTO MARKET

Sheet
No: 3

No.	ELEMENT	ELEMENTAL COST			Sub-Element	UNIT RATE / CFSF	\$
		Quantity	Unit	Rate	Unit of Measure		
10	PLUMBING & DRAINS	-	-	-		280,000	2.04
a)	Roughing-In (Standard)	64	1,030	Per Fixture	65,500	0.62	
b)	Roughing-In (Special)	#100	400	Per Fixture	40,000	0.38	
c)	Plumbing Fixtures (Standard)	64	227	Per Fixture	14,500	0.13	
d)	Plumbing Fixtures (Special)	5	200	Per Fixture	1,000	0.01	
e)	Fire Protection	13	1,111	Per Cabinet ea.	20,000	0.19	
f)	Special Services			Per Head	130,000	1.31	
				Per Outlet			
11	HEATING, VENTILATING & AIR COND'G.	-	-	-		1,045,000	1.86
a)	HVAC	-	-	-			23.2
b)	Special Systems	-	-	-		650,000	6.13
						395,000	3.73
12	ELECTRICAL	-	-	-		708,000	6.47
a)	Transformers & Distribution	-	-	-		277,200	2.61
b)	Lighting Fixtures & Branch Wiring	-	-	-		254,100	2.40
c)	Underfloor Duct Systems	-	-	-		23,100	0.22
d)	Special Systems	-	-	-		153,600	1.45
	Federal Sales Tax Rebate					\$ 4,496,050 (134,880)	100.0
						\$ 3,361,170	

* \$71,271.55

Assumed - no drawings

Hanscomb
 Roy
 Associates

E-9



Project: AIR LPH 04 - CROP SCIENCE BUILDING
COST RECONCILIATION

**Sheet
No: 14**

A)	BUILDING CONTRACT COST (Low bid)	\$ 4,624,000
<u>DEDUCTIONS:</u>		
1.	Sitework (Low bid)	\$ 90,000
2.	Lorrie Components (estimated)	60,000
3.	Furniture (Low bid)	14,300
4.	C.P.M. Consultant (Low bid) ...	6,000
5.	Building Furniture (Low bid) ..	<u>103,000</u>
		<u>299,300</u>
6.	Federal Sales Tax 3%	
		3,702,300
		<u>111,300</u>
7)	ADJUSTED BUILDING CONTRACT COST AT SEPTEMBER 1966	3,590,200
C)	BUILDING CONTRACT COST AT SEPTEMBER 1971 PER COST ANALYSIS	<u>6,264,170</u>
D)	COST INCREASE - SEPTEMBER 1966 TO SEPTEMBER 1971	<u>776,230</u>
		<u>=====</u>

The above reflects an increase, or escalation factor, of 20% of adjusted original low bid amount.



**Hanscomb
Roy
Associates**


Project: CULLEN 04 - CPGP SCIENCE BUILDING
PERIOD: WHICH & STATISTICAL, DATA

Sheet
No: 5

GENERAL DATA:

Gross Floor Area	105,319 ±
Net Assimilable Floor Area	63,077 Sq. Ft.
Cubic Volume	1,415,760 Cu. Ft.
Net Assimilable Floor Area/Gross Floor Area	0.69:1 Ratio
Exterior Wall Area/Gross Floor Area	0.69:1 Ratio
Roof Area/Gross Floor Area	0.55:1 Ratio
Volume/Gross Floor Area	13.34:1 Ratio
Floors + and above Grade	4 No.
Floors Below Grade	1 No. (partial)

* Room area check = 105,344 Sq. Ft. excluding 14,001 Sq. ft.
of atrial space and plenums. P.U.A. report figures therefore
have been accepted.



Hanscomb
Roy
Associates

1. DIRECT & GENERAL EXPENSES

Construction Period	18 Months
Winter Construction Period	9 Months
Performance Bond	\$60,000
Fire Insurance by Owner	Yes
Market Conditions	Busy (four bids, range 9%)


2. SUBSTRUCTURE:

Type of Soil	Very Granular Soil
Instrumental	5'0" below grade.
Bearing Capacity of Soil	8,000 lbs./sq. ft.
Slope of Site	H:1

3. (b) HORIZONTAL SPACERUAL ELEMENTS

	5-Story/Section	1-Story/Section
Structural Type	P.C. flat slab	Steel and Steel I-beam
Material	()	()
Shear Structure	"Open"	"Open"
Structural Bay Sizes	24'0" x 20'0" (av.)	24'0" x 32'0" (m.)
Floor to Floor Heights	10'0"	18'11"
Structural Depth	13'	13'
Floor Live Loading	{ 190 lbs./sq. ft. in conformity with dead live loading	E-9

**Hanscomb
Roy
Associates**



Project: GULCH 04 - CROP SCIENCE BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 7

3.(c) ROOF FINISH

Roof Finish Type	4-ply felt and asphalt gravel surface, galvanized flashings, vapour barrier, 1-1/2" rigid insulation.
Slopes	None
Perimeter/Roof Area	1:21 Ratio
"U" Factor	0.12


4. EXTERIOR GLAZING

% Total Sq. Ft. Glazed (off Walls Above Grade)	15%
% Gross Area Openable	None
Sur Control Measures	Tinted glass and curtains
wall Thickness	11-1/2", 13", 3-1/2"
Unplastered "U" Factor	0.49 0.4 0.97
Inside Face Material	Concrete block
Exterior Face Material	Precast concrete, exposed concrete, painted concrete, block and metal siding.
Exterior Finish	
Window Type	Aluminum with "Duracrol" finish
Glazing Type	Double Single in stairways.

5. INTERIOR WALLS

Linear Feet Partitions/Cross Floor Area	1:12.18 Ratio
--	---------------

Hanscomb
Roy
Associates



E-9

Project: GUELPH OH - CROP SCIENCE BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 2

5. INTERNAL VERTICAL ELEMENTS (cont'd.)

	Type	% Area	Height
Partition Types	Concrete	12%	12' 9"
- Structural (Load-bearing)	Concrete block	52%	5' 2" and 13' 0"
- Venlaceable	3" solid plaster	4%	7' 6"
.....	Glazed	1%	7' 0"
- Demountable	Steel panels, aluminum frames	15	5' 0"
		136.3	=====


Door Types Plastic laminate, solid core wood, louvre, some vit.
Plastered panels, hollow metal.
Doors Ratio 3.34 per 100 Lin. Ft. Partition.

6. MULTI-STORY ELEMENTS

Staircase Types Reinforced concrete, steel ladders.
Elevator Types Hydraulic - 1 No. 4000 lbs., 150 FPM., 5 floors.
Hoist Types 6 openings.
lift

7. INTERIOR FINISHES

Floors Generally 1/8 vinyl tile, broadloom, brick paving, ceramic tile and unfinished concrete.
Ceilings Generally acoustic tile, painted plaster, ruled and painted concrete, painted steel deck, plasticised pyro. c. t.




Hanscomb
Roy
Associates

**Project: CUELMH 04 - CROP SCIENCE BUILDING
PERFORMANCE & STATISTICAL DATA**

**Sheet
No: 3**

7. INTERIOR FINISHES (cont'd.)	Malls	Generally plasticized vinyl, painted plaster, painted block and concrete.
8. FITTINGS, FIXTURES AND EQUIPMENT		
(a) Non-Instructional	Vishroom accessories, vanities, noticeboard, rat sinkers, lockers, corner guards and miscellaneous metal items.	
(b) Instructional	Laboratory equipment and furniture, building furniture and furnishings, chalk and tack boards, coolers and freezers, soil conveyor and bins, spray equipment and miscellaneous.	
9. CASH ALLOWANCES		
(a) Finishing board:are		
- Type	Standard	
- Finish	Brushed aluminum finish	
(b) Inspection and Testing	Concrete, steel, roofing, fill compaction.	
10. PLUMBING AND DRAINS		
Hot and Cold Water piping Type	Type K Copper	
Sanitary Soil piping Type	Cast iron	
Sanitary Waste, Ventilating piping Type	Type DW Copper	
Special Piping Type	PVC, Duron, aluminum	

**Hanscomb
Roy
Associates**



**Project: CULIPH 34 - CROP SCIENCE BUILDING
PERFORMANCE & STATISTICAL DATA**

**Sheet
No: 19**


10. PLUMBING AND PNEUMIC (cont'd.)

Plumbing Fixtures Density per 1000 S.F.	0.6
Special Services	De-ionized and distilled water, vacuum, natural gas, compressed air, acid drainage.

11. HEATING, VENTILATING, AIR CONDITIONING (HVAC)

% Building Served by AC	100%
Heating Source	Remote
Fuel	N.A.
Cooling Source	Remote
Air Handling Source	Building
Capacities Heating	10,263,000 BTU/hr
Cooling Capacity	512 tons
Air Handling CHP	257,000 CFM
Heating ratio	102.4 BTU/hr per sq. ft.
Cooling ratio	5.7 tons per 1000 CSR
Ventilation Ratio	2.43 CFM per sq. ft.
% Return Air	75% in office areas
% Main Reheat	25% in office areas
Thermostats per 1600 CSR95
Control Zones	39 (excluding stairs and fan coil units)
Special Systems	Frame hood exhaust ducts and fans. High volume ventilation systems to growth rooms. Dust arrestors. Heating and Cooling system water treatment. Special controls.

E-9



**Hanscomb
Roy
Associates**

12. ELECTRICAL

1. Substation

- Characteristics of Primary 13.8 kV
- Voltage 120/240
- Characteristics of Secondary
- Voltage 18 Watts/Sq. Ft.
- KVA Rating/Cross Area Sq. Ft. Load Break Switch
- Primary Protection Breaker
- Secondary Protection Molded Case
- Main Distribution Board

2. Distribution


- Related to Type of Structure.. Horizontal
- Voltage of Main Distribution.. 120/209

3. Lighting

- Average Intensity of General Lighting in F.C. 3.5
- Average Cost of General Lighting Fixtures \$30.00
- Branch Circuit Characteristics ENT
- Switching I.V. Switching

4. Motors

- Motor Control Centres Included
- Base Building Facilities Air Conditioning



Hanscomb
Roy
Associates

Project: GULPH 34 - CROP SCIENCE BUILDING
PERFORMANCE & STATISTICAL DATA


**Sheet
No: 12**

- 39 -

12. ELECTRICAL (cont'd.)

- | | | | |
|----|--|-------|-----------------------------|
| 5. | <u>Fire Alarm</u> | | minimum |
| | - Requirements | | |
| | - Smoke Detection | | |
| 6. | <u>Clocks</u> | | 1 minimum sq. ft. |
| | - Average Number Clocks | | |
| 7. | <u>Telephone</u> | | 1 minimum sq. ft. |
| | - Average Number Telephones | | |
| 8. | <u>T.V.</u> | | Close Cct. System - minimum |
| | - Characteristics | | |
| 9. | <u>Special Requirements of Typical
Occupancy</u> | | |
| | - Special lighting in Growth Area | | |
| | - Frequency Systen (no detail) | | |
| | - Other for Int. requirement | | |

E-9



**Hanscomb
Roy
Associates**

- 40 -

PETRIE SCIENCE BUILDING, YORK

Project: YORK 26 - PETRIE SCIENCE BUILDING
COST ANALYSIS

ALL COSTS ON A SEPTEMBER 1971 TORONTO BASIS

Sheet
No: 1

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / CGSF	%
		Quantity	Unit Rate	Unit of Measure		Sub-Element	
1	INDIRECT & GENERAL EXPENSES	-	-	-	387,000		2.95 5.5
2	SUBSTRUCTURE	34,807	1.65	SF Grade Area	57,480		0.43 3.2
	a) Normal Foundations	289	57.98	CY Concrete	16,700	0.12	
	b) Basement Excavations	334,592	0.12	CY Basement Vol.	40,780	0.31	
	c) Special Foundations	-	-	-	-	-	
3	HORIZONTAL STRUCTURAL ELEMENTS	170,520	3.64	SF Struct. Area	622,280		4.75 15.7
	a) Slabs on Grade	34,807	1.19	SF Slab Area	40,930	0.31	
	b) Floor & Roof Construction	135,713	3.62	SF Slab Area	491,410	3.75	
	c) Roof Finish	45,798	1.96	SF Roof Finish	89,940	0.63	
4	EXTERIOR CLADDING	83,455	5.83	SF Wall Area	491,540		3.75 11.5
	a) Walls below Grade	19,124	4.49	SF Wall Area	85,830	0.66	
	b) Walls above Grade	43,363	4.62	SF Wall Area	200,000	1.52	
	c) Windows	11,694	14.11	SF Window Area	165,000	1.26	
	d) Exterior Doors, Entrances, Screen	965	8.73	SF Opening Area	8,430	0.06	
	e) Projections, Balconies, Etc.	8,302	3.89	SF Soffit Area	32,230	0.25	
5	INTERIOR VERTICAL ELEMENTS	137,165	2.53	SF Part. Area	356,840		2.73 7.1
	a) Partitions	126,226	2.23	SF Part. Area	280,830	2.15	
	b) Folding or Sliding Partitions	205	18.00	SF Part. Area	3,630	0.03	
	c) Doors	455	57.6	Per Door Leaf	72,350	0.55	

E-9




Hanscomb
Roy
Associates

Project: YORK 26 - PETRIE SCIENCE BUILDING
COST ANALYSIS - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet
No: 2

No.	ELEMENT	ELEMENTAL COST			Sub-Element	UNIT RATE / OS&F %
		Quantity	Unit Rate	Unit of Measure		
6	MULTI-STORY ELEMENTS	-	-	-	105,090	0.83 2.1
a)	Stairs, Steps & Ladders	15	1,878	Per Flight	28,180	0.22
b)	Catwalks, Gratings	145	14.51	SF on Plan	1,910	0.01
c)	Elevators & Hoists	9	8,333	Per Stop	75,000	0.57
d)	Escalators	-	-	Per Floor	-	-
-	-	-	-	-	192,030	1.47 4.2
7	INTERIOR FINISHES	-	-	-		
a)	Floor Finishes	127,335	0.42	SF Finished Area	53,600	0.41
b)	Ceiling Finishes	135,480	0.61	SF Finished Area	83,110	0.64
c)	Wall Finishes	269,476	0.20	SF Fin. Wall Area	53,760	0.41
d)	Special Finishes	960	1.56	SF Finished Area	1,500	0.01
-	-	-	-	-	150,000	0.25 1.25
8	FITTINGS, FIXTURES & EQUIPMENT	-	-	-		
a)	Non Instructional	-	-	-	78,000	0.60
b)	Instructional	-	-	-	482.00	3.68
9	CASH ALLOWANCES	-	-	-	74,250	0.57 1.1
a)	Hardware	475	150.00	Per Unit	71,250	0.55
b)	Inspection & Testing	-	-	-	3,000	0.02

E-9




Hanscomb
Roy
Associates

Project: YORK 26 - PETRIE SCIENCE BUILDING
COST ANALYSIS - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet
No: 3

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / OGSF	\$
		Quantity	Unit Rate	Unit of Measure	Sub-Element	Sub-Element	
10	PLUMBING & DRAINS	-	-	-	277,000	2.11	6.1
a)	Roughing-In (Standard)	50	1.300	Per Fixture	65,000	0.50	
b)	Roughing-In (Special)	≈200	273	Per Fixture	54,600	0.41	
c)	Plumbing Fixtures (Standard)	50	200	Per Fixture	10,000	0.07	
d)	Plumbing Fixtures (Special)	12	200	Per Fixture	2,400	0.02	
e)	Fire Protection	26	1,250	Per Cabinet	32,500	0.25	
f)	Special Services	-	-	-	112,500	0.86	
11	HEATING, VENTILATING & AIR COND'G.	-	-	-	626,000	6.33	18.2
a)	HVAC	-	-	-	€28,000	4.79	
b)	Special Systems	-	-	-	200,000	1.54	
12	ELECTRICAL	-	-	-	599,860	4.57	13.2
a)	Transformers & Distribution	-	-	-	76,010	0.58	
b)	Lighting Fixtures & Branch Wiring	-	-	-	258,720	1.97	
c)	Underfloor Duct Systems	-	-	-	28,000	0.21	
d)	Special Systems	-	-	-	237,130	1.81	
	Federal Sales Tax Rebate (4%)				4,551,370 (182,050)	34.7% (1.3%)	190.0
					\$ 4,369,320	33.35	

Hanscomb
Roy
Associates




560.92/MCF

E-9

Project: YORK 26 - PETRIE SCIENCE BUILDING COST RECONCILIATION		Sheet No.: E
A)	BUILDING CONTRACT COST (Low Bid)	\$ 3,508,800
	<u>DEDUCTIONS</u>	
	1. Observatory and Link (Estimated)	\$ 160,000
	2. Tunnels (Estimated)	44,000
	3. Ext. Precast Steps and Loring Components (Estimated)	<u>22,500</u>
		<u>206,500</u>
		3,302,300
	4. Federal Sales Tax %	<u>125,250</u>
		<u>3,245,720</u>
	<u>ADDITION:</u>	
	1. Laboratory Furniture (Low Bid)	<u>410,000</u>
B)	ADJUSTED BUILDING CONTRACT COST AS OF SEPTEMBER 1966	3,656,720
C)	BUILDING CONTRACT COST AT SEPTEMBER 1971 FPP COST ANALYSIS	<u>4,360,320</u>
D)	COST INCREASE - SEPTEMBER 1966 TO SEPTEMBER 1971	<u>\$ 712,600</u>

The above reflects an increase, or escalation factor, of 19.5% of adjusted original low bid amount.



**Hanscomb
Roy
Associates**


Project: YORK 26 - PETTIE SCILICE BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 5

GENERAL DATA:


Gross Floor Area	131,000 Sq. Ft.
Net Assignable Floor Area	74,710 Sq. Ft.
Cubic Volume	1,639,620 Cu. Ft.
Net Assignable Floor Area/Cross Floor Area	6.57:1 Ratio
Exterior Wall Area/Cross Floor Area	0.51:1 Ratio
Roof Area/Cross Floor Area	0.24:1 Ratio
Volume/Cross Floor Area	12.51:1 Ratio
Floors At and Above Grade	3 No.
Floors Below Grade	1 No. (plus one partial sub-basement).

Hanscomb
Roy
Associates



Project: WORK 26 - PETRIN SCIENCE BUILDING PERFORMANCE AND STATISTICAL DATA		Sheet No: 5
1. INDIRECT & GENERAL EXPENSES		
Construction Period	20 months
Winter Construction Period	9 months
Performance Bond	50 Per Cent
Fire Insurance by Owner	Yes
Market Conditions	Stable - 4 bids, range 100..
2. SUBSTRUCTURE		
Type of Soil	Sandy Silt to Clay at 21'
Water-table	15 Ft. Below Grade
Bearing capacity of Soil	2,000 lbs./Sq. Ft.
Slope of Site	10 %
3. (L) HORIZONTAL STRUCTURAL ELEMENTS		
Structural Type	70% R.C. Joist/Slab
Material	21% S.C. Flat Slab and Beams
Shear Structure	S.C. Walls
Structural Bay Sizes	27'0" Span: Joist/Slab 10'0" x 10'0" Flat Slab
Floor to Floor Heights	Av: 12'0"
Structural Depth	16' Joist/Slab 6" Flat Slab
Floor Live Loading	35 lbs./Sq. Ft. Offices 150 lbs./Sq.Ft. Lab.
Roof Live Loading	45 lbs./Sq. Ft.

Hanscomb
Roy
Associates




Project: YORK 26 - PETRIE SCIENCE BUILDING
PERFORMANCE & STATISTICAL DATA

**Sheet
No: 7**

3. (c) ROOF FINISH

Roof Finish Type	4 ply felt & pitch; double gravel surfacing; vapour barrier; 1 1/2" insulation; lead coated copper flashings
Rooflights	2.25%
Perimeter/Roof Area	1:16 Ratio
"U" Factor	0.15
4. EXTERIOR CLADDING	
% Total sq. ft. glazed	19 %
(of walls above grade)	
% Glazed area openable01 %
Sun Control Measures	Between glass venetian blinds
Wall Thickness	16" 13" 8"
Unlazed "U" Factor	Av. 0.47
Inside Face Material	Concrete block, concrete
Exterior Face Material	Exposed concrete sandblasted, brick, metal louvres
Exterior Finish	Thermal broken aluminum, Duracron finish
Window Type	Double
Glazing Type	



**Hanscomb
Roy
Associates**

Project: YORK 26 - PETRIE SCIENCE BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 9

5. INTERIOR VERTICAL ELEMENTS

Linear Ft. Partitions/Gross Floor Area 1:10:80 Ratio

Partition Types	Type	C Area	Height
- Structural (load-bearing)	Concrete	29%	Av. 11'0"
- Replacable	Concrete Block	68%	Av. 11'0"
- Replaceable	Glazed	1%	9'0"
- Demountable	Steel Panel	2%	9'8"
		100%	

Doors Types Hollow metal, solid core wood, some having glazed panels

Doors Ratio 4.04 per 100 Lin. Ft. Partition

6. MULTI-STORY ELEMENTS

Staircase Types

Steel with P.C. Terrazzo treads & landing;

Steel ladders

Elevator Types

Hydraulic - 1 ho. 3500" passenger,

150 RPM., 4 floors, 4 openings,

Hydraulic - 1 ho. 7000" freight, 100 RPM.,

5 floors, 5 openings

Hoist Types

Kill

7. INTERIOR FINISHES


Floors

Generally unfinished exposed concrete,
1/8 vinyl asbestos tile, terrazzo

Ceilings

Generally rubbed & painted concrete
ribbed structure, lay-in acoustic tile,

**Hanscomb
Roy
Associates**



**Project: YORK 26 - PETRIE SCIENCE BUILDING
PERFORMANCE & STATISTICAL DATA**

Sheet
No.: :

- 49 -

7. INTERIOR FINISHES (cont'd.)

- | | |
|--------------------------|---|
| Ceilings (cont'd.) | lath & plaster |
| Walls | Generally painted concrete & concrete block, ceramic tile, plastic painted concrete & concrete block. |


8. FITTINGS, FIXTURES & EQUIPMENT

- | | |
|-----------------------------|---|
| (a) Non-Instructional | Washroom accessories, vanities, shelving, coat closets & cupboards, lockers - monorail, mailboxes & miscellaneous metal items |
| (b) Instructional | Laboratory equipment & furniture, building furniture & furnishings, chalk & tack boards, floating floor |

9. CASH ALLOWANCES

- | | |
|--------------------------------|---|
| (a) Finishing hardware | |
| - Type | Standard |
| - Finish | Brushed Aluminum |
| (b) Inspection & Testing | Soil & fill compaction, concrete, roofing, precast concrete |

**Hanscomb
Roy
Associates**




E-9

Project: YORK 26 - PLATEAU SCIENCE BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 2

		- 50 -
10.	<u>PLUMBING AND DRAINS</u>	
	Hot & Cold Water Piping Type	Copper type "K"
	Sanitary Soil Piping Type	Cast Iron
	Sanitary Ventilating Piping Type	Copper type "D.V."
	Special Piping Type	Glass, PVC
	Plumbing Fixtures Density per 1000 S.F.	0.48
	Special Services	Acid drainage, natural gas, compressed air, de-ionized water, vacuum, lab exhaust piping
11.	<u>HEATING, VENTILATING, AIR CONDITIONING (HVAC)</u>	
	% Building Served by AC	100%
	heating Source	Remote
	Fuel	N.A.
	Cooling Source	Remote
	Air Handling Source	Building
	Capacities:Heating	8,000,000 BTU/Hr.
	Cooling	580 Tons
	Air Handling CFM	130,000 CFM
	Heating Ratio	61 BTU/Hr per sq. ft.
	Cooling Ratio	4.42 Tons per 1000 CFM
	Ventilation Ratio	1.00 CFM per sq. ft.
	% Return Air	Nil % in office areas
	% Main Exhaust	100 % in office areas
	Thermostats per 1000 GSF	1.55

**Hanscomb
Roy
Associates**



E-9

Project: YORK 2C - PURPLE SCHWAB BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 11

11. HEATING, VENTILATION, AND CONDITIONING (HVAC) (cont'd.)

- Control Zones 17 main zones
- Special systems Room hood exhaust ducts and fans - interior exhaust systems

12. ELECTRICAL

1. Substation


- Characteristics of Primary Voltage 12.8 kV
- Characteristics of Secondary Voltage 247/0.00 and 120/208v
- KVA Rating/Cross Area Sq. Ft. 1000/131,400 - 9 Watts/Sq. Ft.
- Secondary Protection breaker
- Main Distribution Board

2. Distribution

- Related to Type of Structure "Line"
- Volts or kva distributor 347/0.00 and 120/208

3. Lighting

- Average Intensity of General Lighting:
 - in R.C. 100
- Average Cost of General Lighting:
 - Fixtures 235.00
 - Branch Circuit Characteristics F.T
 - Switching 6.V. switching



Hanscomb
Roy
Associates


**Project: WEX 26 - PORTAL SCIENTIFIC BUILDING
PLACEMENT & STATISTICS DATA**

**Sheet
No: 12**

12. ELECTRICAL (cont'd.)

- | | |
|--|----------------------------------|
| 4. <u>Motors</u> | Includes: |
| - Motor Control Centre | |
| - Basic Building Facilities | Air Conditioning |
| 5. <u>Fire Alarm</u> | Minimum |
| - Requirements | |
| - Smoke Detection | |
| 6. <u>Clocks</u> | Minimum |
| - Average Number Clocks | |
| 7. <u>Telephone</u> | Minimum |
| - Average Number Telephones | |
| 8. <u>T.V.</u> | Minimum |
| Characteristics | |
| 9. Special Requirements of Typical
<u>Occupancy</u> | Minimum Drywall Conduit Network. |
| - Laboratory Sq. Ft./Process Area .. | 30% |

E-9



**Hanscomb
Roy
Associates**

- 53 -

MATHEMATICS AND COMPUTER BUILDING, WATERLOO

Project: UNIVERSITY OF WATERLOO
WA. 17 - MATHEMATICS & COMPUTER BUILDING
COST ANALYSIS

ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE:
Sheet No: 1

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / QGSF	%
		Quantity	Unit Rate	Unit of Measure			
1	INDIRECT & GENERAL EXPENSES	-	-	-	660,000	2.30	2.1
2	SUBSTRUCTURE	46,343	5.11	SF Grade Area	235,950	0.73	3.3
	a) Normal Foundations	1,844	95.35	CY Concrete	166,100	0.55	
"	b) Basement Excavations	472,836	0.11	SF Basement Vol.	53,660	0.16	
"	c) Special Foundations	1,140	15.00	SF. Wallpointing	17,100	0.06	
3	HORIZONTAL STRUCTURAL ELEMENTS	346,706	3.07	SF Struct. Area	1,271,580	4.25	17.5
	a) Slabs on Grade	46,343	0.34	SF Slab Area	43,630	0.15	
	b) Floor & Roof Construction	300,363	3.73	SF Slab Area	1,137,680	3.80	
	c) Roof Finish	55,327	1.63	SF Roof Finish	90,270	0.30	
4	EXTERIOR CLADDING	109,905	4.80	SF Wall Area	524,170	3.11	12.8
	a) Walls below Grade	13,667	4.42	SF Wall Area	60,530	0.20	
	b) Walls above Grade	139,540	4.72	SF Wall Area	658,820	2.21	
	c) Windows	15,500	7.82	SF Window Area	121,170	0.41	
	d) Exterior Doors, Entrances, Screen	1,464	11.89	SF Opening Area	17,400	0.07	
	e) Projections, Balconies, Etc.	19,775	3.35	SF Soffit Area	66,250	0.22	
5	INTERIOR VERTICAL ELEMENTS	517,227	1.21	SF Part. Area	623,410	2.06	2.6
	a) Partitions	280,367	1.57	SF Part. Area	453,070	1.51	
	b) Folding & Sliding-Partitions	810	19.00	SF Part. Area	14,500	0.05	
	c) Doors	1,082	1mu.0	Per Door Leaf	155,760	0.52	

Hanscomb
Roy
Associates



Project: UNIVERSITY OF WATERLOO
W.A. 17 - MATHEMATICS & COMPUTER BUILDING
COST ANALYSIS - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet
No: 2

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / C.R.S.F
		Quantity	Unit Rate	Unit of Measure	Sub-Element	Sub-Element
6	MULTI-STORY ELEMENTS	-	-	-	231,000	0 .77 3.1
a)	Stairs, Steps & Ladders	32	2,238	Per Flight	94,020	6 .31
b)	Catwalks, Gratings	300	3.53	SF on Plan	1,050	0 .01
c)	Elevators & Hoists	24	5,666	Per Stop	136,000	0 .45
d)	Escalators	-	-	Per Floor	-	-
7	INTERIOR FINISHES	-	-	-	533,640	1 .73 7.2
a)	Floor Finishes	289,873	0 .70	SF Finished Area	201,930	0 .67
b)	Ceiling Finishes	298,033	0 .63	SF Finished Area	196,390	0 .62
c)	Wall Finishes	512,945	0 .29	SF Fin. Wall Area	145,320	0 .43
d)	Special Finishes	-	-	-	-	-
8	FITTINGS, FIXTURES & EQUIPMENT	-	-	-	236,000	0 .73 3.2
a)	Non Instructional	-	-	-	147,000	0 .43
b)	Instructional	-	-	-	82,000	0 .23
9	CASH ALLOWANCES	-	-	-	160,300	0 .60 2.5
a)	Hardware	1,082	150.00	Per Unit	162,300	0 .55
b)	Inspection & Testing	-	-	-	8,000	0 .05

E-9

149



Project: UNIVERSITY OF WATERLOO
MA, 17 - MATHEMATICS & COMPUTER BUILDING
COST ANALYSIS - ALL COSTS ON A SEPT/BEP 1971 TORONTO BASE

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / OSRF Sub- Element	% Element
		Quantity	Unit	Rate			
10	PLUMBING & DRAINS	-	-	-	272,000	0.91	3.8
a)	Roughing-In (Standard)	214	Per Fixture	795.00	170,000	0.57	
b)	Roughing-In (Special)	-	Per Fixture	-	-	-	
c)	Plumbing Fixtures (Standard)	214	Per Fixture	1280.00	60,000	0.20	
d)	Plumbing Fixtures (Special)	-	Per Fixture	-	-	-	
e)	Fire Protection	55	Per Cabinet & F-Head	763.00	42,000	0.14	
f)	Special Services	-	Per Outlet	-	-	-	
11	HEATING, VENTILATING & AIR COND'G.	-	-	-	1,147,000	3.84	15.8
a)	HVAC	-	-	-	1,019,000	3.41	
b)	Special Systems	1) Computer A/C 2) Glycol	-	-	103,000 25,000	0.34 0.09	
12	ELECTRICAL	-	-	-	342,480	3.15	13.0
a)	Transformers & Distribution	-	-	-	213,650	0.71	
b)	Lighting Fixtures & Branch Wiring	-	-	-	456,250	1.53	
c)	Underfloor Duct Systems	-	-	-	113,100	0.39	
d)	Special Systems	-	-	-	159,390	0.53	
	Federal Sales Tax Rebate				7,258,520 (217,760)	# 24.26 (.73)	100%
					7,040,760	23.53	

* \$38.38 / MASF

Hanscomb
Roy
Associates

E-9

150

Project: MA.17 MATHEMATICS & COMPUTER BUILDING
COST RECONCILIATION

Sheet No: 4

A) BUILDING CONTRACT COST (Low Bid Alternative)

DEDUCTIONS:

1.	Sitework (low bid)	20,000	
2.	Landscape & Paving (low bid)	33,000	
3.	Contingency (Spec'd. All'nce)	75,000	
4.	Critical Path Scheduling (Spec'd. All'nce)	15,000	
5.	P.C. & Brick Paving (low bid)	45,000	
6.	Miscellaneous Ext. Work (estimated)	7,000	195,000
			\$ 5,974,000
7.	Federal Sales Tax		<u>173,373</u>
			\$ 5,799,000

B) ADJUSTED BUILDING CONTRACT COST AT JUNE, 1966

C) BUILDING CONTRACT COST AT SEPTEMBER 1971
PER. COST ANALYSIS

D) COST INCREASE - JUNE 1966 TO SEPTEMBER 1971

The above reflects an increase, or escalation factor
of 25.6% of adjusted original low bid amount.



Hanscomb
Roy
Associates

Project: WATERLOO 17 - MATHEMATICS & COMPUTER BUILDING
PERFORMANCE & STATISTICAL DATA


Sheet
No: 5

GENERAL DATA:

Gross Floor Area	299,736 Sq. Ft.
Net Assimilable Floor Area	189,117 Sq. Ft.
Cubic Volume	3,825,330 Cu. Ft..
Net Assimilable Floor Area/Gross Floor Area	0.63:1 Ratio
Exterior Wall Area/Gross Floor Area	0.57:1 Ratio
Poof Area/Cross Floor Area	0.19:1 Ratio
Volume/Cross Floor Area	12.76:1 Ratio
Floors At and Above Grade	6 No.
Floors Below Grade	1 No.

- 58 -

E-9



**Hanscomb
Roy
Associates**

Project: MATERLOO 17 - MATHEMATICS & COMPUTER BUILDING
PERFORMANCE & STATISTICAL DATA


**Sheet
No: 6**

- 59 -

1. INDIRECT & GENERAL EXPENSES	
Construction Period	30 Months
Winter Construction Period	13-1/2 Months
Performance Bond	100%
Fire Insurance by Owner	Yes
Market Conditions	Slack (6 Lids, range 10 ³)
2. SUBSTRUCTURE:	
Type of Soil	Dense granular silt
Water-table	15-20' feet below grade
Bearing Capacity of Soil	8,000 lbs/Sq. Ft.
Slope of Site	Nil
3. (b) HORIZONTAL STRUCTURAL ELEMENTS	
Structural Type	82% reinforced concrete joist/slab
Material	13% reinforced concrete flat slab and bear
Shear Structure	Reinforced concrete walls
Structural bay Sizes	19'6" x 32'0" joist/slab; average 12'0" span flat slab
Floor to Floor Heights	Average 13'0"; 2-average 12'1"; 1- 15'3".
Structural Depth	21-1/2" joist/slab; average 7" flat slab.
Floor Live Loading	100 lbs./Sq. Ft.
Roof Live Loading	48 lbs/Sq. Ft.

153

E-9



**Hanscomb
Roy
Associates**

Project: WATERLOO 17 - MATHEMATICS & COMPUTER BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 7

3. (c) ROOF FINISH

Roof Finish Type	4 ply felt and asphalt; gravel surfacing;
Rooflights	vapour barrier; 1-1/2" and 2" insulation;
Perimeter/Roof Area	mill finished aluminum flashings.
"U" Factor	0.0143

4. EXTERIOR CLADDING


Total Sq. Ft. Glazed (Walls above Grade)	113
Glazed Area Openable	None
Sun Control Measures	None
Wall Thickness	15", 12", 8", 6".
Un glazed "U" Factor	Average 0.133 floors 1-3; average 0.15 floors 4-6.
Inside Face Material	Concrete block, concrete, plaster.
Exterior Face Material	Pre cast concrete - harmered rib and plain smooth finish.
Exterior Finish	Facing brick, metal louvers.
Window Type	Aluminum, Duracron finish
Glazing Type	Single

5. INTERIOR VERTICAL ELEMENTS

Linear Ft. Partitions/Gross Floor Area . 1:11.8 Ratio

E-9

**Hanscomb
Roy
Associates**



Project: MATHEMATICS & COMPUTER BUILDING
PERFORMANCE & STATISTICAL DATA


Sheet
No: 2

5. INTERIOR VERTICAL ELEMENTS (cont'd.)

	Type	% Free	height
Partition Types	Concrete	11.4%	ft. 11' 2"
- Structural (Load-Bearing)	Concrete block	74.7%	11' 9"
- Perforated	brick and concrete block	1.6%	11' 9"
	Glazed	1.0%	3' 0"
	Steel stud and drywall	9.3%	8' 0"
	Steel panel	0.6%	13' 0"
- Removable	Vinyl covered steel	0.3%	10' 0"
- Folding		100.0%	=====
Doors Types			Glazed aluminum, solid core wood, plastic laminate, some laminated panels, transom panels.
Doors Ratio			4.25 per 100 Lin. ft. partition

6. MULTI-STORY ELEMENTS

Staircase Types	Concrete with P.C. Terrazzo treads and landings, steel ladders, (stairs large scale).
Elevator Types	Electric traction - 4 No. 3500# passenger, 300 FPM, 6 floors, 6 openings.
Hoist Types	====



Project: MATHEMATICS & COMPUTER BUILDING
PERFORMANCE & STATISTICAL DATA

**Sheet
No: 9**

7. INTERIOR FINISHES

- | | |
|----------------|---|
| Floors | Generally 1/8" vinyl asbestos tile, terrazzo, ceramic tile, hardwood block, carpet, and exposed concrete. |
| ceilings | Generally suspended lay-in acoustic tile, rubber and painted exposed concrete structure, painted plaster, special amphitheatre acoustic ceiling. |
| walls | Generally rubbed and painted concrete, painted and concrete block, painted plaster, painted drywall, acoustic plaster in amphitheatre, ceramic tile, plastic painted concrete and concrete block. |


8. FITTINGS, FIXTURES & EQUIPMENT

- | | |
|-----------------------------|---|
| (a) Non-Instructional | Washroom accessories, vanity, medicine cupboards, coat and hat racks, sigma, paper baler and miscellaneous metal items. |
| (b) Instructional | Laboratory furniture, chalk and tack boards, aluminum pedestal floating floor, projection screens. |

9. CASH ALLOWANCES

- | | |
|------------------------------------|--|
| (a) Finishing Hardware | Standard |
| - Type | Brushed aluminum |
| - Finish | Soil and fill compaction, concrete, roofing, precast concrete. |
| (b) - Inspection and Testing | E-9 |

**Hanscomb
Roy
Associates**



Project: MATHEMATIC 17 - MATHEMATICS & COMPUTER BUILDING
PERFORMANCE & STATISTICAL DATA

**Sheet
No: 17**


10. PLUMBING AND DRAINS

Hot and Cold Water Piping Type	Type K Copper
Sanitary Soil Piping Type	Cast iron
Sanitary Waste, Ventilating Piping Type	Type K/W Copper
Special Piping Type	None
Plumbing Fixtures Density per 1000 SF .	0.7
Special Services	None

11. HEATING, VENTILATING, AIR CONDITIONING (HVAC)

% Building Served by AC	100%
Heating Source	Remote
Fuel	Gas
Cooling Source	Remote
Air Handling Source	Building
Capacities Heating	12,000,000 BTU/HR
Cooling Capacity	820 tons
Air Handling CFM	234,000 CFM
Heating Ratio40 BTU/HR per Sq. Ft.
Cooling Ratio	2.7 tons per 1000 GSF
Ventilation Ratio78 CFM per Sq. Ft.
% Return Air	88%
% Main Exhaust	12%
Thermostats per 1000 GSF	0.85

E-9



**Hanscomb
Roy
Associates**

Project: WATERLOC 17 - MATHEMATICS & COMPUTER BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 11

11. HEATING, VENTILATING, AIR CONDITIONING (HVAC) (cont'd.)

Control Zones	255
Special Systems	Computer Air Conditioning, Glycol overheat heating.

12. ELECTRICAL

1. Substation


- Characteristics of Primary Voltage 14,200
- Characteristics of Secondary Voltage 600 and 120/208
- KVA Rating/Cross Area Sq. Ft. 6.7 Watts/Sq. Ft.
- Primary Protection Load break switch
- Secondary Protection Breakers
- Main Distribution Board Molded Case

2. Distribution

- Related to Type of Structure ... Mixed
 - Voltage of Main Distribution (Secondary) 600
 - Transformation to 120/208V
- 3. Lighting**
- Average Intensity of General Lighting in F.C. 70
 - Average Cost of General Lighting, Fixtures \$40.00

E-9

**Hanscomb
Roy
Associates**




Project: WATERLOO 17 - MATHEMATICS & COMPUTER BUILDING
PERFORMANCE & STATISTICAL DATA

Sheet
No: 12

12. ELECTRICAL (cont'd.)

3. Lighting (cont'd.)
 - Branch Circuit Characteristics .. Lift and L/X
 - Switching Local switching and some L.V. switching
4. Motors
 - Motor Control Centres Included
 - Base Building Facilities Air Conditioning
5. Fire Alarm
 - Requirements Minimum
 - Smoke Detection Minimum
6. Clocks
 - Average Number Clocks 1:2,530 Sq. Ft.
7. Telephone
 - Average Number Telephones 1:1,740 Sq. Ft.
8. T.V.
 - Characteristics Empty conduit network.
9. Special Requirements of Typical Occupancy
 - Office and Classroom Sq. Ft. 60% GFA
 - Computer Sq. Ft. 10% GFA



**Hanscomb
Roy
Associates**

- 66 -

ENGINEERING IV BUILDING, WATERLOO

Project: WATERLOO 35 - ENGINEERING IV
COST ANALYSIS

ALL COSTS ON A SEPTEMBER 1971 TORONTO BASIS

**Sheet
No: 1**

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / OGSE	%
		Quantity	Unit Rate	Unit of Measure	Sub-Element	Sub-Element	Element
1	INDIRECT & GENERAL EXPENSES	-	-	-	470,000		2.75
2	SUBSTRUCTURE	€1,2€1	3.€1	SF Grade Area	254,820		1.41
a)	Normal Foundations	1,762	1.3123	CY Concrete	231,530	1.35	
b)	Basement Excavations	288,650	0.05	CF Basement Vol.	23,290	0.14	
c)	Special Foundations	-	-	-	-	-	
3	HORIZONTAL STRUCTURAL ELEMENTS	243,411	4.22	SF Struct. Area	1522,260	6.01	11.2
a)	Slabs on Grade	€1,264	1.13	SF Slab Area	78,410	0.46	
b)	Floor & Roof Construction	174,147	4.76	SF Slab Area	828,420	4.84	
c)	Roof Finish	75,961	1.60	SF Roof Finish	121,430	0.71	
4	EXTERIOR CLADDING	144,462	5.77	SF Wall Area	933,230	4.88	13.3
a)	Walls below Grade	7,603	4.17	SF Wall Area	31,710	0.19	
b)	Walls above Grade	106,654	5.14	SF Wall Area	548,100	3.20	
c)	Windows	20,000	11.00	SF Window Area	220,000	1.26	
d)	Exterior Doors, Entrances, Screen	1,205	6.05	SF Opening Area	8,380	0.05	
e)	Projections, Balconies, Etc.	8,950	2.75	SF Coffer	25,040	0.15	
5	INTERIOR VERTICAL ELEMENTS	170,273	2.21	SF Part. Area	-	447,800	2.62
a)	Partitions	156,224	2.21	SF Part. Area	350,150	2.65	
b)	Folding or Sliding Partitions	1,440	16.00	SF Part. Area	14,400	0.03	
c)	Doors	1,677	1782t	Per Door Leaf	83,250	0.49	

E-9



**Hanscomb
Roy
Associates**

Project: WATERLOO 35 - ENGINEERING IV
COST ANALYSIS - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet
No: 2

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / OGSR
		Quantity	Unit Rate	Unit of Measure	Sub-Element	Sub-Element
6	MULTI-STORY ELEMENTS	-	-	-	100,170	0.52
a)	Stairs, Steps & Ladders	21	1075	Per Flight	35,170	0.21
b)	Catwalks, Gratings	2,600	5.00	SF on Plan	13,000	0.018
c)	Elevators & Hoists	8	6500	Per Stop	52,000	0.30
"	Escalators	-	-	Per Floor	-	-
7	INTERIOR FINISHES	-	-	-	334,620	1.36
a)	Floor Finishes	270,000	0.35	SF Finished Area	144,770	0.35
b)	Ceiling Finishes	148,000	0.91	SF Finished Area	138,510	0.31
c)	Wall Finishes	102,000	0.50	SF Fin. Wall Area	51,340	0.30
d)	Special Finishes	-	-	-	-	-
8	FITTINGS, FIXTURES & EQUIPMENT	-	-	-	514,400	3.01
a)	Non Instructional	-	-	-	151,300	0.82
b)	Instructional	-	-	-	363,100	2.12
9	CASH ALLOWANCES	-	-	-	110,000	0.65
a)	Hardware	512	135.0	Per Unit	95,000	0.56
b)	Tests and Inspections	-	-	-	15,000	0.09

E-9

Project: WATERLOO 35 - ENGINEERING IV
COST ANALYSIS - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet
No: 3

No.	ELEMENT	ELEMENTAL COST			Sub-Element	Element	UNIT RATE / QCSF	%
		Quantity	Unit Rate	Unit of Measure				
10	PLUMBING & DRAINS	-	-	-		315,000	1.84	5.0
a)	Roughing-In (Standard)	36	1100	Per Fixture	94,500		0.55	
b)	Roughing-In (Special)	26	320	Per Fixture	39,200		0.22	
c)	Plumbing Fixtures (Standard)	35	230	Per Fixture	20,500		0.12	
d)	Plumbing Fixtures (Special)	13	150	Per Fixture	2,000		0.01	
e)	Fire Protection	22	1100	Per Cabinet	25,000		0.15	
f)	Special Services				135,000		0.75	
11	HEATING, VENTILATING & AIR CONDITIONING.	-	-	-		1,050,000	6.14	16.7
a)	HVAC	-	-	-	210,000		5.32	
b)	Special Systems	-	-	-	140,000		6.82	
12	ELECTRICAL	-	-	-		531,000	4.86	13.2
a)	Transformers & Distribution	-	-	-	60,800		0.39	
b)	Lighting Fixtures & Branch Wiring	-	-	-	314,000		1.04	
c)	Underfloor Duct Systems	-	-	-	39,250		0.23	
d)	Special Systems	-	-	-	410,250		2.40	
	Federal Sales Tax Rate - 3%					6,283,300	# 36.8C	100
						(183,700)	(1.10)	
						5,100,600	35.70	

\$62.33 / MACF

Hanscom
Roy
Associates



Project: MA. 35 - ENGINEERING TV
COST RECONCILIATION:

Sheet
No: 4

A) BUILDING CONTRACT COST (Low bid)


DEDUCTIONS:

1.	100% to 50% Performance Bond (low bid)	\$ 5,100
2.	Critical Path Scheduling (low bid)	19,000
3.	Contingencies (Spec'd. Allow.)	63,250
4.	Demolitions (low bid)	5,000
5.	Exterior Works (low bid)	44,448
6.	Equipment (low bids)	39,501
7.	Pedestrian Overpass (low bid)	155,156
8.	Alterations (low bids)	289,100
9.	Utilities & Sitework (low bids)	35,625
		<u>657,783</u>
10.	Federal Sales Tax	
		\$ 5,600,220
		<u>170,000</u>
5)	ADJUSTED BUILDING CONTRACT COST AT MARCH 1, 1970	\$ 5,515,620
C)	BUILDING CONTRACT COST AT SEPTEMBER 1, 1971 PER COST ANALYSIS	<u>6,100,600</u>
D)	COST INCREASE - MARCH 1970 TO SEPTEMBER 1971	\$ 594,980
		<u><u>=====</u></u>

The above reflects an increase, or escalation factor of
10.63 of adjusted original low bid amount.

E-9

Hanscomb
Roy
Associates



Project: WATERLOO 35 - ENGINEERING IV
PERFORMANCE & STATISTICAL DATA


**Sheet
No: 5**

GENERAL DATA:

Gross Floor Area	170,300 S.F.
Net Assimilable Floor Area	100,900 S.F.
Cubic Volume	2,505,000 C.F.
Net Assimilable Floor Area/Cross Floor Area	0.59:1 Patio
Exterior Wall Area/Cross Floor Area	0.79:1 Patio
Roof Area/Cross Floor Area	0.44:1 Patio
Volume/Cross Floor Area	14.66:1 Ratio
Floors at and above Grade	1 2 1 2 4 No.
Floors below grade	Mixed 0 0 1 1 0 No.

- 71 -

E-9



**Hanscomb
Roy
Associates**

Project: MATHIASO 35 = ENGINEERING IV
PERFORMANCE & STATISTICAL DATA

**Sheet
No: 6**

1. INDIRECT & CAPITAL EXPENSES


Construction Period	17 Months
Winter Construction Period	6 Months
Performance Bond	100%
Fire Insurance by Owner	Yes
Market Conditions	Slack (5 bids, range 4%)

2. SUBSTRUCTURE

Type of Soil	Poor - brown and gray silts with some clay
Watertable	Ground water seepage - erratic, average 5' to 6'
Bearing Capacity of Soil	3,000 to 6,000 lbs/Sq.Ft.
Slope of Site	0.02%

3. (b) HORIZONTAL STRUCTURAL ELEMENTS

Structural Type	Structural steel frame, OWSJ, steel deck and metal pans, concrete topping, all fireproofed.
Shear Structure	None
Structural Bay Sizes	Extremely varied- 21'6" x 40'0" to 10'0" x 20'0"
Floor to Floor Heights	Average 12' 5"
Structural Depth	Average 18"
Floor Live Loading	Generally 85 lbs./Sq.Ft
Roof Live Loading	40 lbs./Sq.Ft.



Project: WATERLOO 35 - ENGINEERING IV
PERFORMANCE & STATISTICAL DATA


Sheet
No: 7

3. (c) ROOF FINISH

Roof Finish Type	4 poly felt and asphalt; gravel surface;
vapour barrier; 1-1/2" insulation; painted galvanized iron flashings.	
Rooflights	0.007%
Perimeter/Roof Area	1:1y Ratio
"U" Factor	0.14

4. EXTERIOR CLADDING

Total Sq. Ft. Glazed (of walls above grade)	16.5%
% Glazed Area Openable	Nil
Sun Control Measures	Tinted glass
Wall Thickness	18" 16" 14" 12" 6"
Unplastered "U" Factor	Average 0.14
Invisible Face Material	Smooth faced clay tile, concrete block
Exterior Face Material	Precast concrete broken ribbed, brick,
Exterior Finish	metal louvres
Window Type	Thermal broken aluminum, hardcolour finish
Glazing Type	Double, single in some corridor areas.



Hanscomb
Roy
Associates

Project: MATERLOO 35 - ENGINEERING IV
PERFORMANCE & STATISTICAL DATA

Sheet
No: E

5. INTERIOR VERTICAL ELEMENTS

Linear Ft. Partitions/Cross Floor Area		1:12:39 Ratio	% Area	Height
Partition Types	Type			
- Structural (Load-bearing)	Concrete	0.52		11' 0"
- Replaceable	Clay tile brick	61. n.		Avg. 12' 0"
	Clay tile and brick Glazed	6. 5.		12' 0"
	St. Stud and Drywall	12.	9' 0" and 12' 0"	
- Demountable	Steel panel	10.5		9' 0"
- Folding	Vinyl covered steel	1. 100%		
Door Types	Hollow metal, solid core wood, plastic laminate, some having glazed panels. 1 special radiation door.			
Doors Ratio		3.39 per 100 Lin.Ft. Partition		


6. MULTI-STORY ELEMENTS

Staircase Types	Concrete filled steel pan, steel ladders.
Elevator Types	Hydraulic - 2 No. 3500" Passenger, 200 rev., 4 floors, 4 openings.
Hoist Types	Nil

7. INTERIOR FINISHES

Floors	Generally 1/8 vinyl asbestos tile, carpet, quarry tile, travertine, epoxy paint, ceramic tile, sealed concrete.
--------	---

Hanscomb
Roy
Associates



E-9

Project: WATERLOO 35 - EXPERIMENTAL IV
PERFORMANCE & STATISTICAL DATA

Sheet
No.: 1

7. INTERIOR FINISHES (Cont'd.)

- | | |
|----------------|---|
| Ceilings | Generally suspended perforated metal acoustic system; suspended lay-in acoustic tile, suspended painted drywall, unfinished exposed fireproofing, painted exposed concrete, porcelain enameled panel. |
| Walls | Generally untreated clay tile, painted concrete block, painted drywall, ceramic tile, rubbed concrete. |


8. FITTINGS, FIXTURES & EQUIPMENT

- | | |
|-----------------------------|--|
| (a) Non-Instructional | Washroom accessories, vanities, shelving, coat closets and cubboards, lockers, monorail and cranes, miscellaneous metal items. |
| (b) Instructional | Laboratory furniture, chalk and tack boards, steel pedestal floating floor, projection scrubs. |

9. CASH ALLOWANCES

- | | |
|-----------------------------------|--|
| (a) Finishing, Hardware | |
| - Type | Standard |
| - Finish | Stainless Steel |
| (b) Inspection and Testing, | Soil and fill compaction, concrete, structural steel, roofing, precast concrete. |

- 75 -



**Hanscomb
Roy
Associates**

**Project: WATERLOO 35 - ENGINEERING IV
PERFORMANCE & STATISTICAL DATA**

**Sheet
No: 10**

- 76 -


10. PLUMBING AND DRAINS

Hot and Cold Water Piping Type	Type U copper
Sanitary Soil Piping Type	Cast iron
Sanitary Waste, Ventilating, Riping Type	DW copper
Special Piping Type	Polypropylene, UPVC.
Plumbing Fixtures density per 1000 S.F.5
Special Services	de-ionized water, vacuum 9 as compressed air, acid drainate, hydraulic oil.

11. HEATING, VENTILATION, AIR CONDITIONING (HVAC)

% Building Served by AC	100%
Heating Source	Remote
Fuel	Gas
Cooling Source	Remote
Air Handling Source	Building
Capacities Heating	17,348,000 BTU/HR
Capacity Cooling	671 tons
Air Handling CFM	226,286 CFM
Heating Ratio	161.5 BTU/10 ³ per G.S.F.
Cooling Ratio	3.9 tons per 1000 G.S.F.
Ventilation Ratio	1.33 C.F.M. per sq. ft.
% Return Air	75%

E-9



**Hanscomb
Roy
Associates**


Project: WATERLOO 35 - ENGINEERING IV
PERFORMANCE & STATISTICAL DATA

**Sheet
No: 11**

11. HEATING, VENTILATION, AIR CONDITIONING (HVAC) (contd.)
- | | | |
|-----------------------------|-------|--|
| % Main Exhaust | | 25% |
| Thermostats per 1000 G.S.F. | | 0.7 No. |
| Control Zones | | 72 No. |
| Special Systems | | Fume hood exhaust ducts and fans, make-up air to laboratories, special exhaust hoods, corruter air conditioning. |
12. ELECTRICAL
1. Substation
 - Characteristics of Primary Voltage 14.2 kv
 - Characteristics of Secondary Voltage 347/603 kv
 - KVA Rating/Cross Area Sq.Ft. 11.8 Watts/Sq.Ft.
 - Primary Protection Load Break Switch
 - Secondary Protection Breaker
 - Main Distribution Board Molded Case
 2. Distribution
 - Related to Type of Structure ... Horizontal
 - Voltage of Main Distribution ... 347/603
 - Transformation to 120/208V Scattered
 3. Lighting
 - Average Intensity of General Lighting in F.C. 3.5 Watts/Sq. ft.


E-9

**Hanscomb
Roy
Associates**



12. ELECTRICAL (cont'd.)

- | | |
|---|--|
| - Average cost of General Lighting Fixtures | \$25.00 |
| - Branch Circuit Characteristics | Galvanized |
| - Switching | Local switching and some low voltage switching |
| 4. Motors | |
| - Motor Control Centers | Included |
| - Base Building Facilities | Air Conditioning |
| 5. Fire Alarm | |
| - Requirements | Heavy |
| - Smoke Detection | Minimum |
| 6. Clocks | |
| - Average Number Clocks | 1:3,400 Sq. ft. |
| 7. Telephone | |
| - Average Number Telephones | 1:2,000 Sq. ft. |
| 8. T.V. | |
| - Characteristics | Empty Conduit Network |
| 9. Special Requirements of Typical Occupancy | |
| - Laboratory | 62.66 Sq. ft./O.C.S.F. |



Hanscomb
Roy
Associates

- 79 -

NORTHERN ELECTRIC, TORONTO

Project: NORTHERN ELECTRIC - TORONTO BRANCH LABORATORY
 COST ANALYSIS All Costs on a September 1971 TORONTO BASIS

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / CSCF	%
		Quantity	Unit Rate	Unit of Measure	Sub-Element	Sub-Element	Element
1	INDIRECT & GENERAL EXPENSES	-	-	-	160,000	1.77	7.3
2	SUBSTRUCTURE	53,184	6.62	SF Grade Area	46,946	0.62	2.1
a)	Normal Foundations	413	112.0	CY Concrete	-	0.52	
b)	Basement Excavations	-	-	CF Basement Vol.	-	-	
c)	Special Foundations	-	-	-	-	-	
3	HORIZONTAL STRUCTURAL ELEMENTS	146,574	2.50	SF Struct. Area	359,180	0.42	19.4
a)	Slabs on Grade	53,184	1.02	SF Slab Area	54,380	0.69	
b)	Floor & Roof Construction	93,390	2.61	SF Slab Area	230,500	2.66	
c)	Roof Finish	53,184	1.98	SF Roof Finish	105,302	1.17	
4	EXTERIOR CLADDING	10,756	4.82	SF Wall Area	196,649	2.10	7.7
a)	Walls below Grade	-	-	SF Wall Area	-	-	
b)	Walls above Grade	23,753	4.22	SF Wall Area	102,920	1.59	
c)	Windows, Entrances, Screens	3,426	12.00	SF Window Area	41,460	0.45	
d)	Exterior Doors, Entrances, Screens	350	8.45	SF Opening Area	2,950	0.03	
e)	Projections, Balconies, Etc.	3,243	3.00	SF Soffit Area	9,730	0.10	
5	INTERIOR VERTICAL ELEMENTS	36,120	2.65	SF Part. Area	96,920	1.07	4.4
a)	Partitions	33,750	2.48	SF Part. Area	83,930	0.93	
b)	Folding or Sliding Partitions	-	-	Per Door Leaf	12,170	0.14	
c)	Doors	70	154.35	-	-	-	

E-9

Hanscomb
 Roy
 Associates



Project: NORTHBEN ELECTRIC - TORONTO BRANCH LABORATORY
 COST ANALYSIS - ALI, COSTS ON A SEPTEMBER 1971 TORONTO BASIS.

Sheet
No: 2

No.	ELEMENT	ELEMENTAL COST			A'OUNT	UNIT RATE / CSRF	Sub-Sub-Element	Element	%
		Quantity	Unit Rate	Unit of Measure					
6.	MULTI-STORY ELEMENTS	-	-	-	23,610	-	0.57	1.1	
a)	Stairs, Steps & Ladders	3	2536	Per Flight	7,708	0.03			
b)	Catwalks, Gratings	-	-	SF on Plan	-	-			
c)	Elevators & Hoists	2	7,25	Per Stop	15,850	0.17			
"	Escalators	-	-	Per Floor	-	-			
7	INTERIOR FINISHES	-	-	-	223,630	2.43	10.3		
a)	Floor Finishes	90,147	0.43	SR Finished Area	34,160	0.43			
b)	Ceiling Finishes	90,147	1.50	SR Finished Area	135,480	1.50			
c)	Wall Finishes	55,152	0.63	SR Fin. Wall Area	37,246	0.41			
d)	Special Finishes	2,270	3.00	SR Fin. Col. Are:	6,810	0.39			
8	FITTINGS, FIXTURES & EQUIPMENT	-	-	-	27,380	0.36	1.2		
a)	Non Instructional	-	-	-	27,380	0.36			
b)	Instructional	-	-	-	-	-			
9	CASH ALLOWANCES	-	-	-	13,500	0.15	0.15	0.4	
a)	Hardware	90	150	Per Unit	13,500	0.15			
b)		-	-	-	-	-			

E-9



Project: NORTHERN ELECTRIC - TORONTO BRANCH LABORATORY
 COST ANALYSIS - ALL COSTS ON A SIGHTLINE 1971 TORONTO BASE

Sheet
No: 3

No.	ELEMENT	ELEMENTAL COST			Sub-Element	UNIT RATE / GSF	%
		Quantity	Unit Rate	Unit of Measure			
10	PLUMBING & DRAINS	-	-	-	102,060	1.20	5.0
a)	Roughing-In (Standard)	6.1	41.9	per Fixture	59,304	0.00	
b)	Roughing-In (Special)	-	-	per Fixture	-	-	
c)	Plumbing Fixtures (Standard)	5.3	20.8	per Fixture	11,993	0.12	
d)	Plumbing Fixtures (Special)	-	-	per Fixture	-	-	
e)	Fire Protection	71.1	5.3	per Cabinet or per Head	38,905	0.42	
f)	Special Services	-	-	per Outlet	-	-	
11	HEATING, VENTILATING & AIR COND'G.	-	-	-	540,000	6.00	24.7
a)	HVAC	-	-	-	540,000	0.00	
b)	Special Systems	-	-	-	-	-	
12	ELECTRICAL	-	-	-	340,000	3.70	15.7
a)	Transformers & Distribution	-	-	-	157,700	1.75	
b)	Lighting Fixtures & Branch Wiring	-	-	-	108,000	1.20	
c)	Underfloor Duct Systems	-	-	-	32,400	0.36	
d)	Special Systems	-	-	-	42,700	0.47	
					2,175.300	24.14	10.5

\$32.56 / MAST

Hanscom
Roy
Associates



E-9

Project: NORTHERN ELECTRIC - TORONTO BRANCH LABORATORY

Sheet
No: 4

A) BUILDING CONTRACT COST (Low Bid) \$ 1,382,000

DEDUCTIONS


1. General Site Work (Low Bids)	\$ 43,000
2. Asphalt Roads and Curbs (Low Bids)	51,000
3. Landscaping and P.C. Paving (Low Bids) ...	37,000
4. Mechanical and Electrical Services (Low Bids)	55,000
5. Exterior Limiting (Low Bid)	10,000
	<u>209,000</u>

B) ADJUSTED BUILDING COST AT MARCH, 1967 \$ 1,773,000

C) BUILDING CONTRACT COST AT SUMMER/BEP 1971
Per Cost Analysis 2,175,800

D) COST INCREASE MARCH 1967 TO SEPTEMBER 1971
\$ 402,800

The above reflects an increase, or escalation factor, of 22.7% of adjusted low bid amount.



**Hanscomb
Roy
Associates**

Project: NORTHERN ELECTRIC - TORONTO BRANCH LABORATORY
PERFORMANCE & STATISTICAL DATA


**Sheet
No: 5**

PRINCIPAL DATA:

Gross Floor Area	97,417 sq. ft.
Net Usable Floor Area	66,820 sq. ft.
Cubic Volume	1,279,125 cu. ft.
Net Usable Floor Area/cubic Floor Area	0.74:1 ratio
Retention Wall Area/Cross Floor Area	0.42:1 ratio
Roof Area/Cross Floor Area	0.59:1 ratio
Volume/Gross Floor Area	14.74:1 Ratio
Floors At and Above Grade	2 No.
Floors Below Grade	- No.

- 84 -

E-9



**Hanscomb
Roy
Associates**

Project: NORTHWESTERN ELECTRIC - TORONTO BRANCH LABORATORY
PERFORMANCE & STATISTICAL DATA

Sheet
No: 6

- 85 -

1. INFECT & GENERAL EXEMPTS

Construction Period	11 Months
Winter Construction Period	4 Months
Performance bond	Nil
Fire Insurance by Owner	Yes
Market Conditions	Very (3 bids, range 14%)

2. SUBSTRUCTURE


Type of Soil	sandy gravelly clay
Watertable	2 to 5 feet below grade
Bearing Capacity of Soil	4000 lbs./sq. ft.
Slope of Site	2.5%

3. OPTIONAL STRUCTURAL ELEMENTS

Structure Type and Material	Structural steel frame. First floor - composite steel deck and concrete fill. Roof - steel deck.
Shear Structure	-
Structural Bay Sizes	30' 0" x 30' 0"
Floor to Floor Heights	14' 8" and 14' 3"
Structural Pents	1' 6"
Floor Live Loading	100/125 lbs./sq. ft.
Roof Live Loading	40 lbs./sq. ft.

E-9

Hanscomb
Roy
Associates



Project: NORTHERN ELECTRIC - TORONTO BRANCH LABORATORY
PERFORMANCE & STATISTICAL DATA

Sheet
No: 7

3.(c) ROOF FINISH


Roof Finish Type	" Ply built up felt and pitch, double gravel surfacing, vapour barrier, 1-1/2" rigid insulation, lead covered copper flashing throughout.
Rooflights	0.10sf.
Perimeter/Perf. Area	1:33 ratio
"W" Factor	0.14

4. EXTERIOR CLADDING

% Total Sq. Ft. Glazed (slope crate)	10.7%
% Glazed Area Operable	nil
Sun Control Measures	Solar Gray Glass
Wall Thickness	12", 6"
Unlazed "W" Factor	0.14
Inside Face Material and Finish	brick, Silicone S.P. finish
Window Type	Aluminum, Perforated finish
Cladding Type	single

5. INTERNAL VERTICAL ELEMENTS

Linear Feet Partitions/Cross Floor Area	1:32.40 "ratio
Partition Types	Type % Area Height
- Structural (load-bearing)	brick and concrete block 14% 14'0" av.



Project: INSTITUTIONAL - TORONTO BRANCH LABORATORY
PERFORMANCE & STATISTICAL DATA

Sheet
No: E

5. INTERIOR VERTICAL ELEMENTS (cont'd.)

Partition Types (cont'd.)	Type	" Area	Height
- Perforable	Concrete block	363	16' 0" av.
.....	brick and concrete block	556	16' 0" av.
.....	1991
Floor Type
.....
Floors Ratio


6. MULTI-STORY ELEMENTS

Staircase Types	Concrete: (a) with quarry tile finish; (b) with exposed concrete finish
Elevator Types	Hydraulic 1500 ft/min., 20 rpm up and 30 rpm down, 2 floors, 3 stops.
Hoist Types	None

7. INTERIOR FINISHES

Floors	generally 1/8" vinyl asbestos tile, sealed and hardened exposed concrete, quarry tile, ceramic tile
Ceilings	generally surfaced "Soundlock" metal acoustic panel, "Luxacore" aluminum acoustic slat, gypsum drywall, plaster painted, vinyl strip, radiation shield deck.
Walls	generally painted block, painted plaster, epoxy painted block; ceramic tile (i.e. large proportion facebrick finished partitions).

**Hanscomb
Roy
Associates**




Project: NORTHWEST ELECTRIC - TORONTO BRANCH LABORATORY
PERFORMANCE & STATISTICAL DATA

Sheet
No: 3

8. FITTINGS, FIXTURES AND EQUIPMENT	(a) Non-Instructional	Vashbroch accessories, counters, shelving, vanities, miscellaneous metal items.
9. CAS. ALLOWANCES	(a) Finishing, Hardware	
	- Type	
	- Finish	
10. PLUMBING AND DRAINS	Hot and Cold Water Piping, Type	Type L copper and galvanized steel
	Sanitary Soil Piping, Type	Cast iron
	Sanitary Waste, Ventilating, Piping, Type	Galvanized steel and Type K copper
	Special piping, Type	None
	Plumbing fixtures density per 1000 S.F.	0.63 "o.
	Special Services	None
11. HEATING, VENTILATING, AIR CONDITIONING (HVAC)	Building served by AC	100%
	Heating Source	Remote

**Hanscomb
Roy
Associates**



E-9

Project: MORTIMER ELECTRIC - TORONTO BRANCH LABORATORY
Performance & Statistical Data

Sheet
No. 10

- 89 -

11. METRIC, VENTILATION, AIR CONDITIONING (HVAC) (cont'd.)


Fuel	Oil
Cooling Source	Building
Air Handling Source	Building
Capacity Heating	1,200,000 BTU/Hr.
Cooling Capacity	300 tons
Air Handling CFM	152,800 CFM
Heating Ratio	14.6 BTU/BF per sq. ft.
Cooling Ratio	4.4 tons per 1000 G.S.F.
Ventilation Ratio	1.5% CFM per sq. ft.
Return Air	30%
Main Exhaust	2%
Thermostats per 1000 SF	0.2u
Control Zones	u

12. ELECTRICAL

1. Substation

- Characteristics of Primary
Voltage 21 kV/u/kv
- Characteristics of Secondary
Voltage 4200/277-480v
- MVA Rating/Phase Area S.F. u watts/Sq. Ft.
- Primary Protection Load break switch
- Secondary Protection rise

E-9



Hanscomb
Roy
Associates


Project: MONTREAL ELECTRIC - TORONTO SPINCH LABORATORY
Performance & Statistical Data

Sheet
No: 11

12. Electrical (cont'd.)

1. Substation (cont'd.)
 - Main Distribution Board Fuses
2. Distribution
 - Related to Type of Structure .. Horizontal!
 - Voltage of Main Distribution .. 277/500
 - Transformation to 120/240V ... Scattered
3. Lighting
 - Average Intensity of General
Lighting in F.C. 5
 - Average Cost of General Lighting
Fixtures \$30.00
 - Branch Circuit Characteristics.
num
 - Switching Panel Switching,
4. Motors
 - Motor Control Centres Included
 - Base Building Facilities Air Conditioning
5. Fire Alarm
 - Requirements Maximum
6. Clocks
 - Average Number Clocks Meritible
7. Telephones
 - Average Number Telephones Meritible

E-9



Hanscomb
Roy
Associates

Project: NORTHERN ELECTRIC - TORONTO BRANCH LABORATORY
PERFORMANCE & STATISTICAL DATA

Sheet
No: 2


12. ELECTRICAL (cont'd.)

S. T.V.

- Characteristics } Close Cct. System - None
- } Empty Conduit Network - None

9. Special Requirements of "Typical Occupancy"

- The normal electrical cost for this building in 1971 would be \$270,300.
- In the present case, however, primary voltage was supplied at 21 kV, thus necessitating an outdoor substation and expensive cabling not usually associated with this type of building. The cost of this special requirement is estimated at \$71,000.



**Hanscomb
Roy
Associates**

- 92 -

SYSTEMS DIMENSIONS LIMITED, OTTAWA

Project: SDL BUILDING, OTTAWA
COST ANALYSIS

Sheet
No: 1

ALL COSTS ON A SEPTEMBER 1971 TORONTO BASIS

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / QRSF	%
		Quantity	Unit Rate	Unit of Measure			
1	INDIRECT & GENERAL EXPENSES	-	-	-	181.000	1.77	7.7
2	SUBSTRUCTURE	35.673	9.50	SF Grade Area	24.440	1.24	1.1
a)	Normal Foundations	2.87	60.77	CY Concrete	17.447	0.17	
b)	Basement Excavations	70.210	0.10	CF Basement Vol.	7.000	0.07	
"	c) Special Foundations	-	-	-	-	-	
3	HORIZONTAL STRUCTURAL ELEMENTS	103.120	3.97	SF Struct. Area	405.560	2.44	17.1
a)	Slabs on Grade	35.673	0.37	SF Slab Area	33.570	0.33	
b)	Floor & Roof Construction	67.467	5.07	SF Slab Area	341.990	3.37	
c)	Roof Finish	37.825	0.77	SF Roof Finish	30.300	0.23	
4	EXTERIOR CLADDING	49.440	4.67	SF Wall Area	226.810	2.27	8.7
a)	Walls below Grade	18.233	3.70	SF Wall Area	67.460	0.66	
b)	Walls above Grade	33.487	2.10	SF Wall Area	72.530	0.70	
c)	Windows	5.937	10.00	SF Window Area	50.350	0.59	
d)	Exterior Doors, Entrances, Screen	1.269	12.00	SF Opening Area	15.000	0.19	
e)	Projections, Balconies, Etc.	1.200	4.67	SF Canopy Area	8.870	0.09	
5	INTERIOR VERTICAL ELEMENTS	52.063	2.07	SF Part. Area	-	142.760	1.34
a)	Partitions	48.557	2.39	SF Part. Area	115.170	1.13	
b)	Folding or Sliding Partitions	5.96	0.77	SF Part. Area	5.800	0.06	
c)	Doors	97	214.31	Per Door Leaf	20.700	0.20	

E-9

Henscomb
Foy
Associates



Project: S.D.U. INSTITUTE - ~~STRUCTURE~~
COST ANALYSIS - ALL COSTS ON A SCHEDULED 1971 TORONTO BASIS


Sheet
No: 2

No.	ELEMENT	SUBMENTAL COST			AMOUNT	UNIT RATE / COST	%
		Quantity	Unit Rate	Unit of Measure			
6	MULTI-STORY ELEMENTS	-	-	-	55,000	55.00	2.4
a)	Stairs, Steps & Ladders	24	1,824	Per Flight	25,632	1,068	
b)	Catwalks, Gratings	-	-	SF on Plan	-	-	
c)	Elevators & Hoists	6	5,000	Per Stop	31,000	5,167	
d)	Escalators	-	-	Per Floor	-	-	
7	INTERIOR FINISHES	-	-	-	192,700	1,000	4.5
a)	Floor Finishes	99,173	0.67	SF Finished Area	66,700	0.65	
b)	Ceiling Finishes	99,173	0.71	SF Finished Area	70,390	0.65	
c)	Wall Finishes	8,742	0.40	SF Fin. Wall Area	4,2100	0.60	
d)	Special Finishes	-	-	-	-	-	
8	FITTINGS, FIXTURES & EQUIPMENT	-	-	-	105,470	1,000	4.5
a)	Non Instructional	-	-	-	16,400	1.00	
b)	Instructional	-	-	-	30,610	0.95	
9	CASH ALLOWANCES	-	-	-	26,500	1,000	2.7
a)	Hardware	117	200.00	Per Unit	23,500	200.00	
b)	Instructional Equipment	-	-	-	3,000	0.95	

- 94 -

E-9

Hanscom
Roy
Associates



**Project: S.D.L. - OTTAWA
COST ANALYSIS - ALL COSTS ON A CENTRELINE 1971 TORONTO BASE**

Sheet No: 3

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / O&SF
		Quantity	Unit Rate	Unit of Measure		
10	PLUMBING & DRAINS	-	-	-	\$5,300	0.33 3.7
a)	Roughing-In (Standard)	75	657	Per Fixture	50,000	.058
b)	Roughing-In (Special)	-	-	Per Fixture	-	-
c)	Plumbing Fixtures (Standard)	70	214	Per Fixture	15,000	0.15
d)	Plumbing Fixtures (Special)	-	-	Per Fixture	-	-
e)	Fire Protection	2	1500	Per Cabinet or Per Head	3,000	0.03
f)	Special Services	84	83	Per Outlets	7,000	0.07
11	HEATING, VENTILATING & AIR COND'G.	-	-	-	550,000	5.34 23.6
a)	HVAC	-	-	-	125,000	4.12
b)	Special Systems Computer A/C	-	-	-	125,000	1.22
12	ELECTRICAL	-	-	-	319,000	3.10 13.7
a)	Transformers & Distribution	-	-	-	157,600	1.53
b)	Lighting Fixtures & Branch Wiring	-	-	-	99,000	0.96
c)	Underfloor Duct Systems	-	-	-	-	-
d)	Special Systems	-	-	-	62,400	0.61
					\$ 2314,330	22.58 100

E-9



\$29.17 / O&SF

Project: S.D.L. BUILDING - OTTAWA
COST RECONCILIATION

Sheet
No: 4

A) BUILDING CONTRACT COST (Low Bid) \$ 2,047,770

DEDUCTIONS:

1.	Exterior Services (Low Bids)	\$ 19,170
2.	Landscapeing (Low Bid)	4,930
3.	Asphalt Roadways (Low Bids)	32,000
4.	Miscellaneous Sitework and Concrete Paving etc. (Low Bids)	11,420
		<u>66,670</u>
B)	ADJUSTED BUILDING CONTRACT COST AT JANUARY 1969	\$ 1,981,100
C)	BUILDING CONTRACT COST AT SEPTEMBER 1971 PER COST ANALYSIS	<u>2,324,030</u>
D)	COST INCREASE - JANUARY 1969 to SEPTEMBER 1971	<u>\$ 342,930</u>

The above reflects an increase, or escalation factor, of 17.8% of adjusted original low bid amount.



Hanscomb
Roy
Associates


Project: S.D.L. BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA

**Sheet
No: 5**

GENERAL DATA:

Gross Floor Area	≈ 102,930 Sq. Ft.
Net Assignable Floor Area	≈ 73,323 Sq. Ft.
Cubic Volume	1,407,229 Cu. Ft.
Net Assignable Floor Area/Gross Floor Area	0.77:1 Ratio
Exterior Wall Area/Gross Floor Area	0.48:1 Ratio
Perf. Area/Gross Floor Area	0.37:1 Ratio
Volume/Gross Floor Area	13.57:1 Ratio
Floors At and Above Grade	2 No.
Floors Below Grade	1 No.

* Includes approximately 16,500 square feet of indoor at grade basement level parking.



**Hanscomb
Roy
Associates**

Project: S.D.L. BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA

**Sheet
No: 6**

1. INDIRECT & GENERAL EXPENSES


Construction Period	6 Months
Winter Construction Period	4-1/2 Months
Performance Bond	50% (plus 50% labour and material payment bond)
Fire Insurance by Owner	No
Market Conditions	Average (2 bids, range)

2. SUBSTRUCTURE:

Type of Soil	Rock
Water-table	N/A
Bearing Capacity of Soil	N/A
Slope of Site	Hill

3. (5) HORIZONTAL STRUCTURAL ELEMENTS

Structure Type and Material	Structural steel frame, steel deck, concrete topping.
Shear Structure	None
Structural Bay Sizes	20' x 28'
Floor to Floor Heights	13'0"
Structural Depth	(33% - 27% (67% - 30%)
Floor Live Loading	100 lbs./Sq. Ft.
Roof Live Loading	43 lbs./Sq. Ft.



**Hanscomb
Roy
Associates**

**Project: S.D.L. BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA**

Sheet
No: 7

3.(c) ROOF FINISH

Roof Finish Type 4 ply built-up felt and asphalt, gravel surfacing,
2" rigid insulation, extruded aluminum flashing,
anodized finish.


Rooflights	Nil
Perimeter/Roof Area04:1 Ratio
"U" Factor	0.14

4. EXTERIOR CLADDING

% Total Sq. ft. Glazed (Above Grade)	14%
% Glazed Area Openable	Nil
Sun Control Measures	Tinted Glass
Wall Thickness	0' 9"
Unlazed "U" Factor	0.13
Inside Face Material	Cypress board
Exterior Face Material and Finish	Brick face, exposed concrete sandblasted, exposed structural steel painted, metal louvres.
Window Type	Aluminum fixed with permanent bronze hardcoat finish.
Glazing Type	76% Double - 22% triple, hermetically sealed units.

5. INTERIOR VERTICAL ELEMENTS

Linear feet Partitions/Cross Floor Area	1:23.7 Ratio
---	--------------




**Hanscomb
Roy
Associates**

**Project: S.D.L. BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA**

**Sheet
No: 8**

5. INTERIOR VERTICAL ELEMENTS (cont'd.)

<u>Partition Types</u>	<u>Type</u>	<u>% Area</u>	<u>Height</u>
- Structural (Load-Bearing)	Concrete block	11%	9'6"
- Replaceable	Concrete block	13%	11'3" and 13'0"
.....	Aluminum faced	9%	9'3" and 25'0"
.....	Brick	5%	9'6"
.....	Steel stud and plaster	54%	8'6", 9'6" and 18'0"
- Removable	Vinyl clad panels, aluminum frames	8%	8'0" and 9'6"
Doors Types	Walnut veneered solid core wood, matching transom panels, pressed steel frames.	100%	
Doors Patio	1.97 per 100 Lin. Ft. Partition		Nil
6. <u>MULTI-STORY ELEMENTS</u>			
Staircase Types	Concrete filled steel pan		
Elevator Types	Hydraulic 1 No 2500 passenger, 85 FPM up and 115 FPM down, 3 floors, 4 openings. Electric traction 1 No. 250# dumbwaiter, 50 FPM, 3 floors, 3 openings.		
Hoist Types	Nil		
7. <u>INTERIOR FINISHES</u>			
Floors	Coronally carpet. 1/8" vinyl asbestos tile, 1-1/2" terrazzo: ceramic tile, harlcreed concrete.		



**Hanscomb
Roy
Associates**

Project: S.D.I. BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA


**Sheet
No: 3**

- 7. INTERIOR FINISH (cont'd.)**
- | | | |
|----------------|-------|--|
| Ceilings | | Generally suspended lay-in acoustical tile,
suspended 1/2" drywall painted. Painted steel deck. |
| Malls | | Generally painted plaster. Vinyl fabric, ceramic
tile. |
- 8. FITTINGS, FIXTURES & EQUIPMENT**
- | | | |
|-----------------------------|-------|--|
| (a) Non-Instructional | | Watertight accessories, millwork, elevators,
miscellaneous specialties. |
| (b) Instructional | | Steel panel pedestal computer floor, client/
chalkboard units. |
- 9. CASH ALLOWANCES**
- | | | |
|------------------------|-------|-----------------|
| (a) Finishing hardware | | |
| - Type | | Standard |
| - Finish | | Stainless steel |
- 10. PLUMBING AND DRAINS**
- | | | |
|--|-------|-----------------|
| Hot and Cold Water Piping Type | | Type L Copper |
| Sanitary Soil Piping Type | | Cast iron |
| Sanitary Waste, Ventilating Pipe
Type | | Type DWV Copper |
| Special Piping Type | | Welded |
| Plumbing Fixtures Density per
1000 S.F. | | .70 |

**Project: S.D.L. BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA**

**Sheet
No: 10**

10.	<u>Maintain & Repair</u> (cont'd.)	Special Services	None
11.	<u>HEATING, VENTILATING, AIR CONDITIONING (HVAC)</u>		
	Building Served by AC	653	
	Heating Source	Building	
	Fuel	Gas	
	Cooling Source	Building	
	Air Handling Source	Building	
	Capacities Heating	5,700,000 BTU/HR	
	Cooling Capacity	265 tons	
	Air Handling CFM	39,500 CFM	
	Heating Ratio	65.00 BTU/HF/SF	
	Cooling Ratio	2.57 tons per 1000 GSF	
	Ventilation Ratio	0.97 CFM / SF	
	3 Return Air	78%	
	3 Main Exhaust	22%	
	Thermostats per 1000 GSF	.12	
	Control Zones	None	
	Special Systems	Computer Air Conditioning	



**Hanscomb
Roy
Associates**

12. ELECTRICAL

1. Substation

- Characteristics of Primary Voltage 13 kV
- KV Rating/Gross Area Sq. Ft. ... Not available - See # below
- Primary Protection Load Break Switch - breakers.
- Secondary Protection breaker
- Main Distribution Board Cordon type
- Transformers supplied by others . Vault construction

2. Distribution


- Related to Type of Structure ... Mixed
- Voltage of Main Distribution: ... 120/208 and 347/600v
- Transformation to 120/208v ... Central

3. Lighting

- Average Intensity of General Lighting in F.C. 70 F.C.
- Average Cost of General Lighting fixtures \$35.00
- Branch Circuit Characteristics . Galvanized
- Switching Local switching

4. Motors

- Motor Control Centres Included
- Base Building Facilities Air Conditioning



**Project: S.D.L. BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA**

**Sheet
No: 12.**

12. ELECTRICAL (cont'd.)

5. Fire Alarm
- Requirements Minimum
- Smoke Detection Minimum


6. CLOCKS
- Average Number Clocks Minimum

7. TELEPHONE
- Average Number Telephones ... Minimum

8. T.V.
- Characteristics None

**9. SPECIAL REQUIREMENTS OF TYPICAL
OCCUPANCY**

- Space Heaters Approx. \$3,000
- Car Parking Heaters Approx. \$6,000
- Frost Protection Approx. \$2,000
- Outdoor Lighting Approx. \$7,500
- Kitchen Approx. \$2,000
- Lighting Fixtures were
2' x 4' Air handling
- Remote Substation from
Building
- Computer Distribution
Fairly Heavy



**Hanscomb
Roy
Associates**

- 105 -

VARETTE OFFICE BUILDING, OTTAWA

**Project: VARETTE OFFICE BUILDING
COST ANALYSIS**

ALL COSTS OF A SEPTEMBER 1971 TORONTO DASH:

Sheet
No: 1

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / U.S.\$	%
		Quantity	Unit Rate	Unit of Measure			
1	INDIRECT & GENERAL EXPENSES	-	-	-	337.000	1.00	7.2
2	SUBSTRUCTURE	21,380	4.73	SF Grade Area	102,550	2.32	2.2
	a) Normal Foundations	419	53.10	cu Concrete	22,250	0.97	
	b) Basement Excavations	845,315	0.00	CF Basement Vol.: Excav.	23,300	0.25	
	" c) Special Foundations	-	-	-	-	-	
3	HORIZONTAL STRUCTURAL ELEMENTS	317,334	2.37	SF Struct. Area	645,730	2.03	13.8
	a) Slabs on Grade	21,380	0.35	SF Slab Area	20,320	0.06	
	b) Floor & Roof Construction	296,595	2.02	SF Slab Area	600,200	1.83	
	c) Roof Finish	14,753	1.70	SF Roof Finish	25,210	0.08	
4	EXTERIOR CLADDING	117,330	5.22	SF Wall Area	695,230	2.13	14.9
	a) Walls below Grade	21,693	3.32	SF Wall Area	72,280	0.23	
	b) Walls above Grade	75,454	6.52	SF Wall Area	452,430	1.55	
	c) Windows	17,577	4.75	SF Window Area	83,490	0.26	
	d) Exterior Doors, Entrances, Screen	2,436	18.24	SF Opening Area	47,030	0.15	
	e) Projections, Balconies, Etc.	-	-	-	-	-	
5	INTERIOR VERTICAL ELEMENTS	100,137	2.21	SF Part. Area	222,330	0.72	11.2
	a) Partitions (Incl. Shear Walls)	95,374	1.35	SF Part. Area	177,550	5.55	
	b) Folding or Sliding Partitions	-	-	SF Part. Area	-	-	
	c) Doors	203	223	Per Door Leaf	45,280	0.14	

E-9



**Hanscomb
Roy
Associates**

Project: VASCAR OFFICE BUILDING
COST ANALYSIS - AREA COSTS ON A SEPTEMBER 1971 TORONTO BASIS

Sheet
No: 2

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / CASH
		Quantity	Unit Rate	Unit of Measure	Sub-Element	Sub-Element
6	MULTI-STORY ELEMENTS	-	-	-	316,240	1.25
a)	Stairs, Steps & Ladders	45	2157	Per Flight	53,255	3.17
b)	Catwalks, Gratings	-	-	SF on Plan	-	-
c)	Elevators & Hoists	161	4504	Per Stop	405,300	1.46
d)	Escalators	-	-	Per Floor	-	-
7	INTERIOR FINISHES	-	-	-	372,765	1.23
a)	Floor Finishes	256,600	0.35	SF Finished Area	202,540	0.35
b)	Ceiling Finishes	246,760	0.52	SF Finished Area	126,120	0.42
c)	Wall Finishes	249,620	0.68	SF Fin. Wall Area	163,630	0.53
d)	Special Finishes	-	-	-	-	-
8	FITTINGS, FIXTURES & EQUIPMENT	-	-	-	32,600	0.29
a)	Non Instructional	-	-	-	32,600	0.29
b)	Instructional	-	-	-	-	-
9	CASH ALLOWANCES	-	-	-	16,500	0.55
a)	Hardware	225	75.0	Per Unit	16,500	0.55
b)	-	-	-	-	-	-

E9



Manscorn
Roy
Associates

Project: VARETTE OFFICE BUILDING
COST ANALYSIS - ALL COSTS AT SEPTEMBER 1971 TRADING BASE.

Sheet
No: 3

No.	ELEMENT	ELEMENTAL COST		AMOUNT	UNIT RATE / C.R.S.F	\$
		Quantity	Unit Rate	Unit of Measure	Sub-Element	Element
10	PLUMBING & DRAINS	-	-	-	241,000	6.75
	a) Roughing-In (Standard)	302	331	Per Fixture	100,000	0.31
	b) Roughing-In (Special)	-	-	Per Fixture	-	-
	c) Plumbing Fixtures (Standard)	302	199	Per Fixture	60,000	0.15
	d) Plumbing fixtures (Special)	-	-	Per Fixture	-	-
	e) Fire Protection	52	788	Per Cabinet xx	41,000	0.13
	f) Special Services	795	50	Per Head	40,000	0.13
		-	-	Per Outlet	-	-
11	HEATING, VENTILATING & AIR COND'G.	-	-	-	255,000	2.75
	a) HVAC	-	-	-	855,000	2.65
	b) Special Systems	-	-	-	-	-
12	ELECTRICAL	-	-	-	130,000	1.35
	a) Transformers & Distribution	-	-	-	103,000	0.32
	b) Lighting Fixtures & Branch Wiring	-	-	-	278,000	0.87
	c) Underfloor Duct Systems	-	-	-	5,000	0.03
	d) Special Systems	-	-	-	43,000	0.14
					546,750	1.73
					100	

- 108 -

202


Hanscom
Roy
Associates



E-9

Project:	VAPORITE BUILDING - OTTAWA COST RECONCILIATION	Sheet No: 4
A)	BUILDING CONTRACT COST (For Bid)	\$ (Not Available)
	Note: The building owner has requested that the original complete building costs not be disclosed and this is respected. The adjusted building cost below does, however, parallel exactly our cost analysis.	
B)	ADJUSTED BUILDING CONTRACT COST AT MAY, 1969	\$,500,150
C)	BUILDING CONTRACT COST AT SEPTEMBER 1971 PLR COST ANALYSIS	\$,75,250
D)	COST INCREASE MAY 1969 TO SEPTEMBER 1971	\$ 765,340

The above reflects an increase, or escalation factor, of 14.7% of adjusted building Contract Cost.



Hanscomb
Roy
Associates


Project: VARIETTE OFFICE BUILDING - OTTAWA
PREPARATION & STATISTICAL DATA

Sheet
No: 5

GENERAL DATA

Gross Floor Area	317,400 Sq. Ft. ^a
Net Assignable Floor Area	281,569 Sq. Ft. ^a x
Cubic Volume	3,263,753 Cu. Ft.
Net Assignable Floor Area/Cross Floor Area89:1 Ratio
Exterior Wall/Cross Floor Area27:1 ratio
Poor Area/Cross Floor Area05:1 Ratio
Volume/Cross Floor Area	10.38:1 Ratio
Floors At and Above Grade	19 No.
Floors Below Grade	4 No.

- * Includes approximately 62,000 Square Feet of
Infloor "below-grade" level parking ramps.
- * The lack of tenant partitioning information
precluded the determination in the typical manner
of the net assignable floor area of this building.
The figure shown does not take into account
eventual circulation, etc., space created by such
partitioning and is therefore larger than the
actual figure will be when the building is fully
sub-divided. This fact must be borne in mind when
examining cost figures related to this statistic.



**Hanscomb
Roy
Associates**


Project: VAPORITE OFFICE BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA

Sheet
No: 6

<u>1. IMPACT & CENTRAL ELEMENTS</u>	
Construction Period	10 Months
Winter Construction Period	4-1/2 Months
Performance Bond	None
Fire Insurance by Owner	Yes
Market Conditions	N/A (Owner built)
<u>2. STRUCTURE</u>	
Type of Soil	Rock
Waterable	
Bearing Capacity of Soil	
Slope of Site	:11
<u>3.(b) HORIZONTAL STRUCTURAL ELEMENTS</u>	
Structure Type and Material	Reinforced concrete flat slab
Shear Structure	Reinforced concrete central core walls
Structural Bay Sizes	18' x 18'
Floor to Floor Heights	10' 5"
Structural Depth	Average 3-1/2"
Floor Live Loading	50 lbs./sq. ft.
Roof live loading	48 lbs. sq. ft.

205

E-9



**Hanscomb
Roy
Associates**

**Project: VANCOUVER OFFICE BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA**

Sheet
No: 7

3.(c) ROOF FINISH

Roof Finish Type 4 ply built-up felt and asphalt. Gravel surface.
vapour barrier, 1-1/2" mineral insulation, galvanized
flashing.

None

Pooflights03:1 ratio
Perimeter/Roof Area	
"u" Factor	0.145

4. EXTERIOR CLADDING

% Total Sq. Ft. Glazed (above grade). 16%

% Glazed Area Openable None

Sun Control Measures Blinds

Wall Thickness 0'-11"

Unglazed "U" Factor 0.13

Inside Face Material Plaster

Exterior Face Material and Finish Precast concrete and brick

Window Type Aluminum fixed, clear anodized finish (minimum

quality).

Glazing Type Single

5. INTERIOR VERTICAL ELEMENTS

Linear Feet Partitions/Cross Floor Area	1:33.33
--	-------	---------

Project: VAFFETTE OFFICE BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA

Sheet
No. ?

5. INTERIOR VERTICAL ELEMENTS (cont'd.)

<u>Partition Types</u>	<u>Type</u>	<u>% Area</u>	<u>Height</u>
- Structural (Load-Bearing)	Concrete	3%	10'5"
- Replaceable	Concrete Block	5%	7'4"; 8'10"; 10'4" and 12'8"
- Demountable	Metal Glazed	3%	10'0" and 8'5"
- Sliding and Folding	Mil	100%	

Doors Types Hollow metal slabs in pressed steel frames, some with glazed panels.


Doors Ratio 2.19 per 100 Lin. Ft. Partition

6. MULti-STORY ELEMENTS

Staircase Types	reinforced concrete
Elevator Types	Electric traction - 5 No. 3500# passenger, 500 FPM, 4 serving, 10 floors, 13 openings and 1 service. Electric traction - 1 No. 7500# freight, 25 FPM serving 5 floors, 5 openings.
Hoist Types	Mil

7. INTERIOR FINISHES

Floors	Generally carpet; hardened concrete in parking; ceramic tile, terrazzo sealed concrete.
--------------	--



**Hanscomb
Roy
Associates**

Project: VARETTE OFFICE BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA

Sheet
No. 5

- 114 -

7. INTERIOR FINISHES (cont'd.)

- | | |
|----------------|---|
| Ceilings | Generally suspended lay-in acoustic tile,
decorative ceiling in lobby. |
| Walls | Generally painted plaster, ceramic tile, marble
in lobby. |

8. FIXTURES, FIXTURES & EQUIPMENT

- | | |
|-----------------------------|---|
| (a) Non-Instructional | Washroom accessories, vanities, valances, directory
board, plastic signs, mail chute and miscellaneous
metal items. |
| (b) Instructional | Mil |

9. CASE ALLOWANCES


- | | |
|-------------------------|------------------|
| (2) Finishing: Hardware | |
| - Type | Standard |
| - Finish | Brushed aluminum |

10. PLUMBING AND DRAINS

- | | |
|--|---------------|
| Hot and Cold Water piping Type | Type K Copper |
| Sanitary Soil piping Type | Cast iron |
| Sanitary Waste, Ventilating piping
Type | Type K Copper |
| Special piping Type | None |
| Piping fixtures Density per
1000 S.F. | 0.25 |

E-9

**Hanscomb
Roy
Associates**



Project: VALETTTE OFFICE BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA


Sheet
No: 16

10. PLUMBING AND DRAINS (cont'd.)

Special Services None

11. HEATING, VENTILATING, AIR CONDITIONING (HVAC)

% Building Served by FC	100	Building	Building
Heating Source	Oil and Gas	Oil and Gas
Fuel	Building	Building
Cooling Source	Building	Building
Air Handling Source	8,350,000 BTU/Air	8,350,000 BTU/Air
Capacities Heating	500 tons	500 tons
Cooling Capacity	129,900 CFM	129,900 CFM
Air Handling CFM	20.4 BTU/IP per Sq. Ft.	20.4 BTU/IP per Sq. Ft.
Heating Ratio	1.59 tons per 1000 csp	1.59 tons per 1000 csp
Cooling Ratio	0.41 CFH per Sq. Ft.	0.41 CFH per Sq. Ft.
Ventilation Ratio	60%	60%
% Return Air	35%	35%
% Main Exhaust	Thermostats per 1000 rSF	Thermostats per 1000 rSF
Control Zones	1.4	1.4
Special Systems	5	5
		None	None



**Hanscomb
Roy
Associates**

Project: VINTAGE OFFICE BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA

Sheet
No: 11

12. ELECTRICAL

1. Substation

- Characteristics of Primary Voltage 15 kv
- Characteristics of Secondary Voltage 120/208v
- kVA Rating/Cross Area Sq. Ft. 6.3
- Primary Protection: breakers
- Secondary Protection breaker
- Main Distribution Board molded case

2. Distribution


- Related to Type of Structure Vertical
- Voltage of Main Distribution 120/208v
- Transformation to 120/208v Not applicable

3. Lighting

- Average Intensity of General Lighting in fc 70
- Average Cost of General Lighting Fixtures \$18.00
- Branch Circuit Characteristics .. FMT: 5/2
- Switching Panel switching; local switching

4. Motors

- Motor Control Centres Included
- Base Building Facilities Air Conditioning



Hanscomb
Roy
Associates


**Project: VASCETTE OFFICE BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA**

Sheet
No: 2

- 117 -

12. ELECTRICAL (cont'd.)

- | | | |
|---|-------|----------------|
| 5. <u>Fire Alarm</u> | | Minimum |
| - Requirements | | |
| - Smoke Detection | | |
| 6. <u>Clocks</u> | | Not Applicable |
| - Average Number Clocks | | |
| 7. <u>Telephone</u> | | Not Applicable |
| - Average Number Telephones | | |
| 8. <u>T.V.</u> | | None |
| - Characteristics | | |
| 9. <u>Spatial Requirements of Typical
Occupancy</u> | | Not Applicable |
| - Significant characteristic is the
distance of underfloor duct system
throughout the building. | | |



**Hanscomb
Roy
Associates**

- 118 -

GENERAL PURPOSE OFFICE BUILDING, OTTAWA

212

Project: GENERAL PURPOSE OFFICE BUILDING - OTTAWA
COST ANALYSIS

ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet
No: 1

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / OSF	%
		Quantity	Unit Rate	Unit of Measure			
1	INDIRECT & GENERAL EXPENSES	-	-	-	4,87,000	1.13	t.e.
2	SUBSTRUCTURE	20,433	2.55	SF Grade Area	52,220	0.12	0.7
a)	Normal Foundations	3RC	66.13	CY Concrete	25,130	0.06	
b)	Basement Excavations	263,301	6.10	CY Basement Vol.	27,020	0.06	
"	c) Special Foundations	-	-	-	-	-	
3	HORIZONTAL STRUCTURAL ELEMENTS	451,535	2.20	SF Struct. Area	1032,490	2.38	14.0
a)	Slabs on Grade	20,433	1.50	SF Slab Area	30,600	0.07	
b)	Floor & Roof Construction	431,192	2.26	SF Slab Area	975,560	2.25	
c)	Roof Finish	19,125	1.45	SF Roof Finish	26,330	0.06	
4	EXTERIOR CLADDING	137,975	1.62	SF Wall Area	1328,300	3.36	17.8
a)	Walls below Grade	9,253	3.60	SF Wall Area	33,300	0.03	
b)	Walls above Grade	90,800	10.61	SF Wall Area	964,000	2.22	
c)	Windows	33,962	7.80	SF Window Area	265,000	0.61	
d)	Exterior Doors, Entrances, Screen	3,260	15.67	SF Opening Area	66,000	0.15	
e)	Projections, Balconies, Etc.	-	-	-	-	-	
5	INTERIOR VERTICAL ELEMENTS	147,060	2.35	SF Part. Area	346,360	1.85	11.5
a)	Partitions (Incl. Shear Walls)	129,000	2.10	SF Part. Area	304,520	0.76	
b)	Folding or Sliding Partitions	3,324	2.71	SF Part. Area	9,200	0.02	
c)	Doors	183	17.31	Per Door Leaf	32,840	0.08	

E-9

Hanscomb
Roy
Associates



Project: GENERAL PURPOSE OFFICE BUILDING - OTTAWA
 COST ANALYSIS - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet
 No: 2

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / ORSF	
		Quantity	Unit Rate	Unit of Measure	Sub-Element	Sub-Element	Element
6.	MULTI-STORY ELEMENTS	-	-	-	767,300	1.77	10.3
a)	Stairs, Steps & Ladders	44	136.3	per Flight	60,000	0.14	
b)	Catwalks, Gratings	458	15.28	SF on Plan	7,000	0.62	
c)	Elevators & Hoists	11	744.7	Per Stop	700,000	1.61	
d)	Escalators	-	-	Per Floor	-	-	
7	INTERIOR FINISHES	-	-	-	722,470	1.67	9.7
a)	Floor Finishes	395,486	0.58	SF Finished Area	230,160	0.53	
b)	Ceiling Finishes	305,496	0.57	SF Finished Area	227,290	0.52	
c)	Wall Finishes	314,441	0.78	SF Fin. Wall Area	245,020	0.57	
d)	Special Finishes - Mural	2,000	10.00	SF Fin. Wall Area	20,000	0.05	
8	FITTINGS, FIXTURES & EQUIPMENT	-	-	-	30,640	0.07	0.4
a)	Non Instructional	-	-	-	30,640	0.07	
b)	Instructional	-	-	-	-	-	
9	CASH ALLOWANCES	-	-	-	15,000	0.03	0.2
a)	Hardware	202	74.25	Per Unit	15,000	0.03	
b)	-	-	-	-	-	-	

E-9




Project: GENERAL PURPOSE BUILDING - OTTAWA
 COST ANALYSIS - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASIS.

Sheet
No: 3

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / OGSF	%
		Quantity	Unit	Unit of Measure			
10	PLUMBING & DRAINS	-	-	-	350,000	6.81	4.7
a)	Roughing-In (Standard)	472	429	Per Fixture	202,000	0.47	
b)	Roughing-In (Special)	-	-	Per Fixture	-	-	
c)	Plumbing Fixtures (Standard)	472	176	Per Fixture	83,000	0.19	
d)	Plumbing Fixtures (Special)	-	-	Per Fixture	-	-	
e)	Fire Protection	88	633	Per Cabinet & Head	55,700	0.13	
f)	Special Services	168	55	Per Head	9,300	0.02	
		-	-	Per Outlet	-	-	
11	HEATING, VENTILATING & AIR COND'G.	-	-	-	1,245,000	2.87	16.3
a)	HVAC	-	-	-	1,245,000	2.87	
b)	Special Systems	-	-	-	-	-	
12	ELECTRICAL	-	-	-	1,004,300	2.45	14.2
a)	Transformers & Distribution				205,350	0.47	
b)	Lighting Fixtures & Branch Wiring				430,100	0.99	
c)	Underfloor Duct Systems				354,000	0.82	
d)	Special Systems				74,550	0.17	
					\$7,440,480	17.17	100

E-9

Hanscom
Roy
Associates



\$19.96 / SF

Project: GENERAL PURPOSE BUILDING - OTTAWA
COST RECONCILIATION


Sheet
No: 4

- 122 -

A)	BUILDING CONTRACT COST (LOW BID)	\$ 6,594,000
<u>DEDUCTIONS:</u>		
1.	Sitework (Estimated)	\$ 55,000
2.	Substitute excavation in earth for rock (Estimated)	34,000
3.	Demountable Partitions (Specified Allowance)	650,000
4.	Freezers and Equipment (Estimated)	<u>15,000</u>
		<u>754,000</u>
B)	ADJUSTED BUILDING CONTRACT COST AT MARCH 1, 1968	5,940,000
C)	BUILDING CONTRACT COST AT SEPTEMBER 1971 PER COST ANALYSIS	<u>7,440,480</u>
D)	COST INCREASE - FEBRUARY 1968 to SEPTEMBER 1971	<u>\$ 1,500,480</u>

The above reflects an increase, or escalation
factor, of 25.3% of adjusted original low bid
amount.

E-9




**Project: CENTRAL PURPOSE BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA**

Sheet No: 5

GENERAL DATA:

Gross Floor Area	433,410 Sq. Ft.
Net Assignable Floor Area	372,814 Sq. Ft. ^x
Cubic Volume	4,846,413 Cu. Ft.
Net Assignable Floor Area/Cross Floor Area	0.86:1 Ratio
Exterior Wall Area/Cross Floor Area	0.31:1 Ratio
Roof Area/Cross Floor Area	0.04:1 Ratio
Volume/Cross Floor Area	11.19:1 Ratio
Floors At and Above Grade	22 No.
Floors Below Grade	1 No.

- ^x The lack of office partitioning information precluded the computation in the typical manner of the net assignable floor area of this building. The figure shown does not take into account circulation etc. space created on the typical floors by office partitioning and is therefore higher than would be computed from such "as built" conditions. This fact must be borne in mind when examining cost figures related to this statistic.



**Hanscomb
Roy
Associates**


Project: GENERAL PURPOSE BUILDING - OTTAWA

**Sheet
No. E**

- 124 -

1. INDUSTRY & COMMERCIAL EXPENSES	
Construction Period	23 Months
Winter Construction Period	9 Months
Performance Bond	\$500
Fire Insurance by Owner	Yes
Market Conditions	Very Competitive (9 bids, range 11.5%)
2. SUBSTRUCTURE	
Type of Soil	Pack
Water-table	Not known
Bearing Capacity of Soil	60,000 lbs./sq. ft.
Slope of Site	Nil
3.(b) HORIZONTAL STRUCTURAL ELEMENTS	
Structural Type	{ Reinforced Concrete flat slab
Material	
Shear Structure	
Structural Bay Sizes	Centre core walls
Floor to Floor Heights	29'3" x 21'9"
Structural Depth:	10'7"
Floor Live Loading:	8"
Roof Live Loading	75 lbs./sq. ft.
	100 lbs./sq. ft.

E-9



**Project: FOOD & DRUG BUILDING - TORONTO
PERFORMANCE & STATISTICAL DATA**


Sheet
No: 7

3. (b) HORIZONTAL STRUCTURAL ELEMENTS

Structure Type and Material	Reinforced concrete, flat slabs and columns with drop panels
Shear Structure	:nil
Structural Bay Sizes	26' x 26'
Floor to Floor Heights	12'-0"
Structural Depth	10-1/2" x 6" drop panels
Floor Live Loading	Generally 80-100 lbs./Sq. Ft.
Roof Live Loading	40 lbs./Sq. Ft.

3. (c) ROOF FINISH

Roof Finish Type	Built up roofing on 2" rigid insulation
Rooflights	0.5 Per Cent.
Perimeter/Roof Area	1:20 Ratio
'U' Factor	



**Hanscomb
Roy
Associates**

Project: CENTRAL PURPOSE BUILDING - OTTAWA
PURPOSE & STATISTICAL DATA

**Sheet
No: 7**

3.(c) ROOF FINISH

Roof Finish Type	4-ply felt and asphalt, gravel surfacing, galvanized flashings, vapour barrier, 1-1/2"
Rooflights	rigid insulation.
Perimeter/Roof Area	None
"U" Factor	1:38 Ratio


4. EXTERIOR CLADDING

% Total Sq. Ft. Glazed (Walls above Grade)	383
% Glazed Area Openable	None
Sun Control Measures	Tinted glass
Wall Thickness	2 1/8"
Un glazed "U" Factor	0.15
Inside Face Material	Concrete block and reinforced concrete walls
Exterior Face Material	Pre cast concrete
Exterior Finish	Exposed sandblasted
Window Type	Aluminum with thermal break, hard coat bronze finish.
Glazing Type	Double.

5. INTERIOR VERTICAL ELEMENTS

Linear Feet Partitions/Cross Floor Area	1:33.32
---	---------

E-9



**Hanscomb
Roy
Associates**

**Project: FOOD & DRUG BUILDING - TORONTO
PERFORMANCE AND STATISTICAL DATA**

**Sheet
No: 8**

4. EXTERIOR CLADDING


% Total Sq. Ft. Glazed (above grade)	29 Per Cent
% Gross Area Openable	None
Sun Control Measures	Tinted Glass
Wall Thickness	10 inches
Unglazed "U" Factor	Concrete Block
Inside Face Material	"Face Brick, insulated aluminum panel cladding and aluminum louvers to penthouse.
Exterior Face Material and Finish	Aluminum with baked acrylic enamel.
Window Type	Double
Gazing Type	

5. INTERIOR VERTICAL ELEMENTS

Linear Feet Partitions/Gross Floor Area	1:14.49 Ratio
Partition Types	Type % Area Height
- Replaceable	Concrete Block 69 11' 2" & 10' 0"
.....	Brick 4 11' 2"
.....	Drywall and Steel Stud 11 11' 2"

E-9

**Hanscomb
Roy
Associates**



**Project: CHIEFAL PURPOSE BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA**

Sheet
No: 8

- 126 -

5. INTERIOR VERTICAL ELEMENTS (cont'd.)

Partition Types	Type	% Area	Height
- Structural (load-bearing)	Concrete	4%	10'
- Replaceable	Concrete Block	55%	10' 0", 10' 0"
	Aluminum glazed	15%	7' 6"

- Doors Type Solid core wood slats, hollow metal slab, all in pressed metal frames, some with glazed panels, virtually all with aluminum ventilation grilles.
- Doors Ratio 1.43 per 106 Lin. Ft. partition


6. MULTI-STORY ELEMENTS

Staircase Types	Reinforced concrete, steel ships ladders.
Elevator Types	4 No. 2500# passenger, 800 rpm, high rise - 11 floors, 11 openings.
Hoist Type	4 No. 3500# passenger, 500 rpm, low rise. 12 floors, 12 openings. 1 No. 1500# freight, 250 rpm, 2 floors, 2 openings.

7. INTERIOR FINISHES

Floors	Generally 1/8" vinyl asbestos tile, epoxy seamless ceramic tile, hardened concrete, slate in lobby.
Ceilings	Generally acoustic tile, painted plaster, rubbed and painted concrete.

**Hanscomb
Roy
Associates**



E-9

**Project: FOOD & DRUG BUILDING - TORONTO
PERFORMANCE & STATISTICAL DATA**

Sheet
No: 9

- 140 -

5. INTERIOR VERTICAL ELEMENTS (cont'd.)

	Type	% Area	Height
Partition Types	16	
- Sliding and folding		
Door Types		Plastic Laminate with Fixed sidelights and H.W. Frames

Doors Ratio 4.2 per 100 Lin. Ft. Partition


6. MULTI-STORY ELEMENTS

Staircase Types	Poured Concrete
Elevator Types	Electric traction - 4000# passenger, 200 FPM, 4 floors, 4 Openings.

7. INTERIOR FINISHES

Floors	Mainly vinyl asbestos tile, linoleum carpet and quarry tile.
Ceilings	Mainly painted concrete, suspended acoustic tile, suspended painted drywall.
Walls	Mainly vinyl acrylic and paint to block, epoxy paint, brick facing ceramic tile.

E-9



**Hanscomb
Roy
Associates**

Project: GENERAL PURPOSE BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA

Sheet
No: 3

- 127 -

7.	<u>INTERIOR FINISHES</u> (cont'd.)		
	Walls		Painted plaster, painted block and concrete, vinyl fabric and ceramic tile.
8.	<u>FITTINGS, FIXTURES & EQUIPMENT</u>		
	(a) Non-Instructional		Masterroot accessories, vanities, directory boards, lockers and miscellaneous metal items.
	(b) Instructional		Nil
9.	<u>CASH ALLOWANCES</u>		
	(a) Finishing hardware		
	- Type		Standard
	- Finish		Brushed aluminum
10.	<u>PLUMBING AND DRAINS</u>		
	Hot and Cold Water Piping Type		Type L Copper
	Sanitary Soil Piping Type		Cast iron
	Sanitary Waste, Ventilating Piping Type		Type DWV Copper
	Special Piping Type		None
	Plumbing Fixtures Density per 1000		
	Sq. Ft.		1.10
	Special Services		None

221

Hanscomb
Roy
Associates



E-9

**Project: FOOD & DRUG BUILDING - TORONTO
PERFORMANCE & STATISTICAL DATA**

Sheet
No: 10

- 141 -

8. FITTINGS, FIXTURES AND EQUIPMENT

Non-Instructional	Washroom accessories, millwork, chimney, miscellaneous specialties.
Instructional	Lab. furniture.

9. CASH ALLOWANCES

(a) Finishing Hardware

- Type	Standard
- Finish	Brushed Aluminum

10. PLUMBING AND DRAINS

Hot and Cold Water Piping Type	Type L and K Copper
Sanitary Soil Piping Type	Cast Iron
Sanitary Waste, Ventilating Piping Type	Type DWV Copper
Special Piping Type	High silicone cast iron, glass, PVC, polypropylene.
Plumbing Fixtures Density per 1000 S.F.78
Special Services	Gas, air, vacuum, steam, acid waste, de-mineralized water, distilled water, nitrogen.

E-9

**Hanscomb
Roy
Associates**



Project: GENERAL PURPOSE BUILDING - OTTAWA
Performance & Statistical Data

Sheet
No: 10

Notes:


11. HEATING, VENTILATION, AIR CONDITIONING (HVAC)

% Building Served by AC	90%
Heating Source	Remote
Fuel	N.A.
Cooling Source	Remote
Air Handling Source	Building
Capacities Heating	27,000,000 BTU/hr.
Cooling Capacity	1,200 tons
Air Handling CFM	267,000 CFM
Heating Ratio	62.3 BTU/hr per Sq. Ft.
Cooling Ratio	2.7 tons per 2000 RSF
Ventilation Ratio	0.02 CFM per Sq. Ft.
% Return Air	55% in office areas
% Main Exfiltration	45% in office areas
Thermostats per 1000 RSF	1.4
Control Zones	12
Special Systems	None



Hanscomb
Roy
Associates

Project:	FOOD & DRUG BUILDING - TORONTO PERFORMANCE & STATISTICAL DATA	Notes:	Sheet No: 1.1
11. HEATING, VENTILATING, AIR CONDITIONING (HVAC)			
% Building Served by AC	75%		
Heating Source	Building		
Fuel	Oil and gas		
Cooling Source	Building		
Air Handling Source	Building		
Capacities Heating	11,172,000 BTU/HR		
Cooling Capacity	370 tons		
Air Handling CFM	101,685 CFM		
Heating Ratio	110 BTU/HR per Sq. Ft.		
Cooling Ratio	3.50 tons per 1000 GSF		
Ventilation Ratio	.96 CFM per Sq. Ft.		
% Return Air	75%		
% Main Exhaust	25%		
Thermostats per 1000 GSF	1.20		
Control Zones	None		
Special Systems	Fume hood exhaust and fans, special controls.		



12. ELECTRICAL

1. Substation

- Characteristics of Primary Voltage 15 kv
- Characteristics of Secondary Voltage
- kVA Rating/Mains Area Sq. Ft.
- Primary Protection Load Break Switch
- Secondary Protection Breakers
- Main Distribution Board Folded Case

2. Distribution


- Related to Type of Structure Vertical
- Voltage of Main Distribution 120/208 and 347/600
- Transformation to 120/208

3. Lighting

- Average Intensity of General Lighting in F.C. 100
- Average Cost of General Lighting Fixtures \$18.00
- Branch Circuit Characteristics ..
- Switches

4. Motors

- Motor Control Centres Included
- Base Building Facilities Air Conditioning



Hanscomb
Roy
Associates


Project: FOOD & DRUG BUILDING - TORONTO
PERFORMANCE & STATISTICAL DATA

Sheet
No: 12

12. ELECTRICAL

1. Substation
 - Characteristics of Primary Voltage 27,600 kv
 - Characteristics of Secondary Voltage 600
 - KVA Rating/Gross Area S.F. 15 Watts/Sq. Ft.
 - Primary Protection Load Break Switch
 - Secondary Protection Breaker
 - Main Distribution Board! Folded Case
2. Distribution
 - Related to Type of Structure Horizontal
 - Transformation to 120/208v : ... Scattered
3. Lighting
 - Average Intensity of General Lighting, in F.C. 70
 - Average cost of General Lighting Fixtures \$25.00
 - Branch Circuit Characteristics Galvanized
 - Switching Local Switching
4. Motors
 - Motor Control Centres Included

- 143 -



**Hanscomb
Roy
Associates**

Project: GENERAL PURPOSE BUILDING - OTTAWA
PERFORMANCE & STATISTICAL DATA


**Sheet
No: 12**

- 130 -

12. ELECTRICAL (cont'd.)


- | | | |
|----|--|-------------------|
| 5. | <u>Fire Alarm</u> | Minimum |
| - | Requirements | |
| - | Smoke Detection | |
| 6. | <u>Clocks</u> | Minimum |
| - | Average Number of Clocks | |
| 7. | <u>Telephone</u> | Minimum |
| - | Average Number of Telephones | |
| 8. | <u>T.V.</u> | |
| - | Characteristics | |
| 9. | <u>Special Requirements of Typical
Occupancy</u> | |
| - | Machinery Generator | Approx. \$20,000 |
| - | Industrial Electric Motor | Approx. \$154,000 |
| - | Office Equipment | Approx. \$10,000 |

**Hanscomb
Roy
Associates**



E-9

Project:	FOOD & DRUG BUILDING - TORONTO PERFORMANCE & STATISTICAL DATA	Notes:	Sheet No: 13
12. ELECTRICAL (cont'd.)			
4.	<u>Motors</u> (cont'd.)		
	- Base Building Facilities	Air Conditioning	
5.	<u>Fire Alarm</u>		
	- Requirements	Heavy	
	- Smoke Detection	Minimum	
6.	<u>Clocks</u>		
	- Average Number Clocks	1/2000 Sq. Ft.	
7.	<u>Telephone</u>		
	- Average Number Telephones ...	1/200 Sq. Ft.	
8.	<u>T.V.</u>		
	- Characteristics		Close Circuit System - not applicable
		Empty Conduit Network - not applicable
9.	<u>Special Requirements of Typical Occupancy</u>		
	- Vault Type Substation		
	- Snow Melting	\$4,500 minimum	
	- Sound Minimal	\$1,200 minimum	
	- Emergency	\$13,000 minimum	
	- Lightning Protection	\$12,000	



Hanscomb
Roy
Associates

- 131 -

FOOD AND DRUG BUILDING, TORONTO

- 145 -

GEORGIAN CAAT IIIA, BARRIE

Project: ONTARIO UNIVERSITY COST STUDY
Food & Drug Building - TORONTO.

ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / UCSC			%
		Quantity	Unit Rate	Unit of Measure		Sub-Element	Element	Sub-Element	
1	INDIRECT & GENERAL EXPENSES	-	-	-	193,420				5.7
2	SUBSTRUCTURE	21,574	3.87	SF Grade Area	82,800				2.4
a)	Normal Foundations	264	105.37	CY Concrete	27,921				0.26
b)	Basement Excavations	570,402	0.10	CY Basement Vol.	55,850				0.53
"	c) Special Foundations	-	-	-	-				-
3	HORIZONTAL STRUCTURAL ELEMENTS	111,257	3.27	SF Struct. Area	369,760				3.50
a)	Slabs on Grade	24,574	1.21	SF Slab Area	31,000				0.29
b)	Floor & Roof Construction	90,383	3.46	SF Slab Area	312,860				2.26
c)	Roof Finish	23,274	1.07	SF Roof Finish	25,300				0.25
4	EXTERIOR CLADDING	57,450	5.26	SF Wall Area	304,570				2.08
a)	Walls below Grade	15,220	3.12	SF Wall Area	53,000				0.50
b)	Walls above Grade	32,592	4.71	SF Wall Area	156,320				1.48
c)	Windows	9,530	9.53	SF Window Area	95,250				0.30
d)	Exterior Doors, Entrances, Screen	-	-	SF Opening Area	-				-
e)	Projections, Balconies, Etc.	-	-	-	-				-
5	INTERIOR VERTICAL ELEMENTS	86,757	1.87	SF Part. Area	167,000				1.59
a)	Partitions	69,303	1.57	SF Part. Area	107,000				1.02
b)	Folding & Sliding Partitions	10,889	2.33	SF Part. Area	25,000				0.24
c)	Doors	313	108.67	Per Door Leaf	31,000				0.33

132 -

E-9

Hanscomb
Roy
Associates



Project: GEORGIAN CAAT - IIIA
COST ANALYSIS

ALL COSTS ON A SEPTEMBER 1971 TORONTO BASEL

No.	ELEMENT	ELEMENTAL COST'			AMOUNT	UNIT RATE / OGSR	\$
		Quantity	Unit Rate	Unit of Measure			
1	INDIRECT & GENERAL EXPENSES	-	-	-	76,000	1.76	7.4
2	SUBSTRUCTURE	23.306	0.36	SF Grade Area	23,140	0.54	2.2
	a) Normal Foundations	139	10647	CY Concrete	23,140	-	
	b) Basement Excavations	-	-	CF Basement Vol.	-	-	
	c) Special Foundations	-	-	-	-	-	
3	HORIZONTAL STRUCTURAL ELEMENTS	66.569	2.57	SF Struct. Area	171,000	3.96	15.6
	a) Slabs on Grade	24,033	0.95	SF Slab Area	22,800	0.53	
	b) Floor & Roof Construction	42,536	2.70	SF Slab Area	115,050	2.66	
	c) Roof Finish	23,427	1.42	SF Roof Finish	33,150	0.77	
4	EXTERIOR CLADDINGS	23,816	5.62	SF Wall Area	134,080	3.11	13.0
	a) Walls below Grade	-	-	SF Wall Area	-	-	
	b) Walls above Grade	21,310	4.83	SF Wall Area	103,030	2.39	
	c) Windows, Entrances, Screens	2,132	13.44	SF Window Area	28,650	0.66	
	d) Exterior Doors,	147	11.90	SF Opening Area	1,750	0.04	
	e) Projections, Balconies, Etc.	257	2.50	SF Soffit Area	640	0.02	
5	INTERIOR VERTICAL ELEMENTS	48,063	1.77	SF Part. Area	85,140	1.97	6.2
	a) Partitions	115,033	1.50	SF Part. Area	68,040	1.58	
	b) Folding	60	3.34	SF Part. Area	500	0.01	
	c) Doors	110	15.91	Per Door Leaf	16,500	0.38	

E-9

Hanscom
Roy
Associates



Project: ONTARIO CHIMNEY STONE COST STUDY
Food & Sanit Building - Toronto. - All costs on a summer 1971 TORONTO BASE

Sheet 2

No: 2

No.	ELEMENT	ELEMENTAL COST			AMOUNT	UNIT RATE / OSSE	%
		Quantity	Unit Rate	Unit of Measure			
6	MULTI-STORY ELEMENTS	-	-	-			
a)	Stairs, Steps & Ladders	22	500.75	Per Flight	12,513	0.28	
b)	Catwalks, Gratings	1,331	4.35	SF on Plan	5,255	0.05	
c)	Elevators & Hoists	4	6275.00	Per Stop	25,100	0.31	
d)	Escalators	-	-	Per Floor	-	-	
					131,670	1.2n	3.8
7	INTERIOR FINISHES	-	-	-			
a)	Floor Finishes	20,567	3.75	SF Finished Area	57,500	0.54	
b)	Ceiling Finishes	82,556	0.55	SF Finished Area	50,570	0.48	
c)	Wall Finishes	125,343	0.15	SF Fin. Wall Area	23,300	0.22	
d)	Special Finishes	-	-	-	-	-	
					369,349	3.82	11.5
8	FITTINGS, FIXTURES & EQUIPMENT	-	-	-			
a)	Non Instructional	-	-	-	73,525	0.75	
b)	Instructional	-	-	-	215,000	2.38	
					415,000	3.25	1.2
9	CASH ALLOWANCES	-	-	-			
a)	Hardware	31,115.00	Per Unit	25,000	0.34		
b)	Printed Instructions	-	-	5,000	0.05		

- 133 -

227

E-9



Roy
Associates

Project: GEORGIA CAAT - III A
COST ANALYSIS - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

No.	ELEMENT	ELEMENT COST	Quantity	Unit Rate	Unit of Measure	Sub-Element	AMOUNT	UNIT RATE / OCSR	Sub-Element	Element	No.
6.	MULTI-STORY ELEMENTS		-	-	-		9,900				4
a)	Stairs, Steps & Ladders	11	211.75	Per Flight	9,900			0.23			
b)	Catwalks, Gratings	-	-	SF on Plan	-			-			
c)	Elevators & Hoists	-	-	Per Stop	-			-			
d)	Escalators	-	-	Per Floor	-			-			
7.	INTERIOR FINISHES		-	-	-		90,000				6.7
a)	Floor Finishes	40,777	0.83	SF Finished Area	33,840			0.78			
b)	Ceiling Finishes	40,777	0.53	SF Finished Area	21,710			0.50			
c)	Wall Finishes	95,410	0.36	SF Fin. Wall Area	34,450			0.80			
d)	Special Finishes	-	-	-	-			-			
8.	FITTINGS, FIXTURES & EQUIPMENT		-	-	-		113,500				4.2
a)	Non Instructional	-	-	-			13,050	0.30			
b)	Instructional	-	-	-			30,450	0.71			
9.	CASH ALLOWANCES		-	-	-		20,500				2.0
a)	Hardware	110	16304	Per Unit	19,000			0.42			
b)	Inspection and Testing	-	-	-	2,500			0.06			

E-9



Hanscomb
Roy
Associates

241

Project: ONTARIO UNIVERSITIES COST STUDY
FOOD & DRUG BUILDING - TORONTO. - ALL COSTS ON A SEPTEMBER 1971 TORONTO BASE

Sheet No. 3

No.	ELEMENT	ELEMENTAL COST			Sub-Element	UNIT RATE / OS&F	Element
		Quantity	Unit Rate	Unit of Measure			
10	PLUMBING & DRAINS	-	-	-	355.340	2.36	10.5.
	a) Roughing-In (Standard)	65	1010	Per Fixture	65,700	0.62	
	b) Roughing-In (Special)	265	226	Per Fixture	60,000	0.56	
	c) Plumbing Fixtures (Standard)	65	220	Per Fixture	14,300	0.14	
	d) Plumbing Fixtures (Special)	18	200	Per Fixture	3,600	0.04	
	e) Fire Protection	20	1438	Per Cabinet ex	28,750	0.27	
	f) Special Services	225	50	Per Head	11,250	0.11	
			-	Per Outlet	171,740	1.62	
11	HEATING, VENTILATING & AIR COND'G.	-	-	-	820,110	7.76	24.2
	a) HVAC	-	-	-	700,000	6.62	
	b) Special Systems				120,110	1.14	
12	ELECTRICAL	-	-	-	473,670	4.48	14.0
	a) Transformers & Distribution	-	-	-	163,500	1.60	
	b) Lighting Fixtures & Branch Wiring	-	-	-	145,000	1.37	
	c) Underfloor Duct Systems	-	-	-	30,000	0.29	
	d) Special Systems	-	-	-	120,170	1.22	
					\$ 3,385,900	32.04	100.00

\$62,86 / MASF

Hansenom
Roy
Associates



E-9

Project: GEORGIAN CAAT - III A
COST ANALYSIS - ALL COSTS IN A SEPTEMBER 1971 TORONTO BASE

No.	ELEMENT	ELEMENTAL COST			Sub-Element	Amount	UNIT RATE / OSF	%
		Quantity	Unit Rate	Unit of Measure				
10	PLUMBING & DRAINS	-	-	-		72,500	1.68	7.0
a)	Roughing-In (Standard)	45	739	Per Fixture	34,050		0.73	
b)	Roughing-In (Special)	34	550	Per Fixture	19,000		0.44	
c)	Plumbing Fixtures (Standard)	46	217	Per Fixture	10,300		0.23	
d)	Plumbing Fixtures (Special)	16	168	Per Fixture	3,000		0.07	
e)	Fire Protection	-	-	Per Cabinet or Head	3,500		0.08	
f)	Special Services	-	-	Per Outlet	3,000		0.07	
11	HEATING, VENTILATING & AIR COND'G.	-	-	-	133,000		3.08	12.5
a)	HVAC	-	-	-	105,000		2.43	
b)	Special Systems	-	-	-	26,000		0.65	
12	ELECTRICAL	-	-	-	173,000		4.03	15.9
a)	Transformers & Distribution	-	-	-	53,500		1.24	
b)	Lighting Fixtures & Branch Wiring	-	-	-	98,300		2.28	
c)	Underfloor Duct Systems	-	-	-	-		-	
d)	Special Systems	-	-	-	21,300		0.51	
	Federal Sales Tax Rebate				1032,200 (30,200)		23.93 (0.73)	100
					1201,300		23.20	

\$34.17 /OSF

Hanscomb
Roy
Associates

E-9

242

Project: FOOD & DRUG BUILDING - TORONTO		Notes:
COST RECONCILIATION		
A)	BUILDING CONTRACT COST (Low bid)	\$ 3,575,000
	DEDUCTIONS	189,160
1.	Site Development	
B)	ADJUSTED BUILDING COST AT NOVEMBER, 1971.	\$ 3,385,840
H.3.	All costs in Analysis have been reconciled to low bidder's costs provided by client.	

E-9



Hanscomb
Roy
Associates

Project: GEORGIAN CAAT - III A
COST RECONCILIATION:


Sheet
No.: 1

A) BUILDING CONTRACT COST (LOW BID)

DEDUCTIONS:

		\$ 1,021,580
A)	BUILDING CONTRACT COST (LOW BID)	
	<u>DEDUCTIONS:</u>	
1.	Exterior Work (Low Bid)	\$ 23,000
2.	Asphalt Paving (Low bid)	5,560
3.	Kitchen Equipment (Low Bid)	19,000
4.	Contingency (Specified Allowance)	<u>45,000</u>
		\$ 929,080
5.	Federal Sales Tax	<u>27,890</u>
B)	ADJUSTED BUILDING CONTRACT COST AT MAY, 1970	\$ 901,200
C)	BUILDING CONTRACT COST AT SEPTEMBER 1971 PER COST ANALYSIS	<u>1,001,300</u>
D)	COST INCREASE MAY 1970 TO SEPTEMBER 1971	\$ <u>100,100</u>

The above reflects an increase, or escalation factor
of 11% of adjusted original low bid amount.




**Hanscomb
Roy
Associates**

GENERAL DATA:

Gross Floor Area	105,675 Sq. Ft.
Net Assignable Floor Area	53,825 Sq. Ft.
Cubic Volume	1,327,832 Cu. Ft.
'Net Assignable Floor Area/Gross Floor Area	0.51:1 Ratio
Exterior Wall Area/Gross Floor Area	0.54:1 Ratio
Roof Area/Gross Floor Area	0.23:1 Ratio
Volume/Gross Floor Area	12.57:1 Ratio
Floors At and Above Grade	3 No.
Floors Below Grade	1 No. (Partial)

Hanscomb
Roy
Associates



Project: GEORGIAN CAAT - III A
PERFORMANCE & STATISTICAL DATA

**Sheet
No: 5**

GENERAL DATA:

Gross Floor Area	43,140 Sq. Ft.
Net Assignable Floor Area	30,210 Sq. Ft.
Cubic Volume	621,440 Cu. Ft.
Net Assignable Floor Area/Gross Floor Area	0.70:1 Patio
Exterior Wall Area/Cross Floor Area	0.55:1 Ratio
Roof Area/Gross Floor Area	0.55:1 Ratio
Volume/Cross Floor Area	14.41:1 Ratio
Floors At and Above Grade	2 No.
Floors Below Grade	None

344


- 150 -

E-9



**Hanscomb
Roy
Associates**

Project: FOOD & DRUG BUILDING - TORONTO PERFORMANCE & STATISTICAL DATA		Sheet No: 6
1. INDIRECT & GENERAL EXPENSES		
Construction Period	20 months
Winter Construction Period	9 months
Performance bond	50 Per Cent.
Fire Insurance by Owner	No.
Market Conditions	Depressed market, keen bidding - 13 bids - Range 23% (11.7% discounting the high bid of \$4.4 million)
2. SUBSTRUCTURE		
Type of Soil	Generally silty sand to approx. 10 ft. below grade, then small gravel.
Watertable	Ft. Below Grade
Bearing Capacity of Soil	12,000 lbs./Sq.Ft.
Slope of Site	5 Per Cent



Hanscomb
Roy
Associates

Project: GEORGIA CAIT - IIIA
PERFORMANCE & STATISTICAL DATA

**Sheet
No: 5**

1. IMPACT AND CAPITAL EXPENSES	
Construction Period	16 Months
Winter Construction Period	5 Months
Performance Bond	50%
Fire Insurance by Owner	Yes
Market Conditions	Average (5 bids, range 4%)
2. SUBSTRUCTURE	
Type of Soil	Silty sand
Water table	13'0" below grade
Bearing Capacity of Soil	6000 lbs./Sq. Ft.
Slope of Site	2%
3. (b) HORIZONTAL STRUCTURAL ELEMENTS	
Structure Type and Material	Structural steel frame with CUSJ: 2nd floor - 2-1/2" concrete slab on vertical rib flat roof - 1-1/2" metal deck.
Shear Structure	None
Structural Bay Sizes	Average 19'6" x 35'0"
Floor to Floor Heights	14'0"
Structural Depth	2-1/2" (slab) 16" (CUSJ)
Floor Live Loading	196 lbs./Sq. Ft.
Roof Live Loading	60 lbs./Sq. Ft.
3. (c) ROOF FINISH	
Roof Finish Type	4 ply built-up felt and asphalt, gravel surfacing, vapour barrier, 1-1/2" insulation, prefabricated air-tight flashings with baked enamel finish.
Rooflights	None
Perimeter/Roof Area	1:31 Ratio
"U" Factor	0.12

245

**Hanscomb
Roy
Associates**



**Project: GEORGIA CAN - IIIA
PERFORMANCE & STATISTICAL DATA**

**Sheet
No: 7**

- 152 -


4. INTERIOR CLADDING

% Total Sq. Ft. Glazed (Above Grade).	6.4%
% Glazed Area Openable	None
Sun Control Features	Tinted glass to sloped planing.
Wall Thickness	10", 12", 14"
Unlabeled "U" Factor	Average 0.11
Inside Face Material	Concrete Block
Exterior Face Material and Finish	Face brick and precast concrete with striated finish.
Window Type	Single windows, curtainwall and sloped aluminum with Paracor: finish. (Sloped area 44% of total)
Glazing Type	Double.

5. INTERIOR VERTICAL ELEMENTS

Linear Feet Partitions/Gross Floor Area		1:12.64 Ratio	Height
Partition Types	Type	Block	$\frac{\% \text{ Area}}{25.625}$
- Replaceable	Block	Drywall	10'0" and 13'9"
.....	Glazed	(7'2")
.....	Wiremesh	(10'4")
- Folding	Stanchmaster 240	0.13%
.....	109.0%
Doors Types	HW, wood and aluminum: <u>20%</u> glazed
Doors Ratio	3.23 per 100 Lin. Ft. Partition.

**Hanscomb
Roy
Associates**




Project: GEORGIAN CAAT - IIIA
PERFORMANCE & STATISTICAL DATA

**Sheet
No: 8**

- 153 -

6.	MULTI-STORY ELEMENTS	
	Staircase Types	Steel pan with concrete fill, quarry tile finish.
	Elevator Types	None
	Hoist Types	None
7.	INTERIOR FINISHES	
	Floors	Generally carpet, hardened concrete, 1/8" vinyl asbestos tile, quarry and ceramic tile.
	Ceilings	Generally suspended 2' x 4' lay-in acoustic tile, painted exposed structure, suspended drywall, suspended lath and plaster.
	Walls	Generally paint to drywall and block; plastic paint ceramic tile.
8.	FITTINGS, FIXTURES AND EQUIPMENT	
	(a) Non-Instructional	Washroom accessories, manufactured specialties, counters, cupboards, vanities, miscellaneous metal items.
	(b) Instructional	Laboratory furniture
9.	CASH ALLOWANCES	
	(a) Finishing Hardware	
	- Type	Standard
	- Finish	Generally brushed chrome.
	(b) Inspection and Testing	soil compaction, structural steel, concrete, roofing.

**Hanscomb
Roy
Associates**



Project: GIGLIOTTI CAAT - IIIA
PERFORMANCE & STATISTICAL DATA

**Sheet
No:**

10. PLUMBING AND DRAINS


Hot and Cold Water Piping Type	Type L Copper
Sanitary Soil Piping Type	Cast iron and transite
Sanitary Waste, Ventilating, Piping Type	Type DW Copper and galvanized iron
Special Piping Type	Proxylene
Plumbing Fixtures Density per 1000 S.F.	1.49
Special Services	Acid drains

11. HEATING, VENTILATING, AIR CONDITIONING (HVAC)

% Building Served by AC	100%
Heating Source	Building
Fuel	Gas
Cooling Source	Building
Air Handling Source	Building
Capacities Heating	1,675,000 BTU/Hr (including 300,000 electric)
Cooling Capacity	92 tons
Air Handling CFM	39,860 CFM
Heating Ratio	4.9 BTU/Hr per sq. ft.
Cooling Ratio	2.4 tons per 1000 CSR
Ventilation Ratio	0.96 CFM per sq. ft.
% Return Air	0%
% Main Exhaust	36%

248

**Hanscomb
Roy
Associates**



**Project: CHOCOLATE CAST - ITIA
PERFORMANCE & STATISTICAL DATA**

**Sheet
No: 17**

11. HEATING, VENTILATING, AIR CONDITIONING (HVAC) (cont'd.)

Thermostats per 1000 SF	1.1
Control Zones	43
Special Services	Laboratory and shop exhaust systems

12. ELECTRICAL

1. Substation

- Characteristics of Primary Voltage 13.8/5kv (5kva temporary tap)
- Characteristics of Secondary Voltage 120/2031
- KVA Rating/gross Area S.F. 1050/1333 (4 watts/sq. ft. lighting)
- Primary Protection Load break switch
- Secondary Protection breaker
- Main Distribution Board Fusible units

2. Distribution

- Related to Type of Structure . Mixed
- Voltage of "main" distribution . 120/208
- Transformation to 120/208v ... Scattered

3. Lighting

- Average intensity of General Lighting in F.C. \$1.36
- Average Cost of General Lighting Fixtures \$24.00



**Hanscomb
Roy
Associates**

Project: CONCRETE CART - IIIA
INSTRUMENT & STATISTICAL DATA


**Sheet
No: 11**

12. ELECTRICAL (cont'd.)

- | | |
|---|-----------------------|
| 3. <u>Lighting</u> (cont'd.) | |
| - Branch Circuit Characteristics | EXT |
| Walls | |
| - Branch Circuit Characteristics | N/A |
| Ceilings | |
| - Switching | Local switching |
| 4. <u>Motors</u> | |
| - Motor Control Centres | Excluded |
| - Base Building Facilities | Air Conditioning |
| 5. <u>Fire Alarm</u> | |
| - Requirements | Minimum |
| - Smoke Detection | Minimum |
| 6. <u>Clocks</u> | |
| - Average Number Clocks | 1 Room sq. ft. |
| 7. <u>Telephone</u> | |
| - Average Number Telephones | 1 Office sq. ft. |
| 8. <u>T.V.</u> | |
| - Characteristics | Empty Conduit Network |
| 9. Special Requirements of Typical
Occupancy | |
| - Laboratory S.F./Cross Area .. | 27.115 |
| - Classrooms | 8.00% |

250

E-9



**Hanscomb
Roy
Associates**

- 157 -

ELEMENTAL UNIT RATES

Hanscomb
Roy
Associates

11771


SEARCHED OR CLEARED INDEXED - FILED - COUNTRY

- 158 -

M-Report		Performance Index Report									
No.	Title or Requirement	Cost by Category	Cost by Supplier Category	Net Total Refundable Fees							
1. INSPECT AND REPAIR, EQUIPMENT	ST. NSP	2.53	2.53	2.30	2.30	1.77	1.77	1.00	1.00	1.00	1.00
2. CONSTRUCTION	ST. Grade Area	5.62	5.62	1.65	5.11	2.68	3.28	0.50	0.50	0.50	0.50
a) Normal Publications	EV. Periodicals	11.74	11.74	137.37	57.92	25.35	231.22	112.00	60.76	60.76	60.76
b) Emergency Publications	ST. News.	2.13	2.13	3.77	1.11	5.11	5.11	—	—	—	—
c) Special Publications	ST. Grade Area	8.87	8.87	—	—	—	—	—	—	—	—
3. INSPECT AND REPAIR, EQUIPMENT	ST. Inspect. Areas	2.31	2.31	3.44	3.44	3.44	3.44	3.44	3.44	3.44	3.44
a) Glass or Glass Floor and Roof Constra. c) Roof Finials	ST. Glass Area	1.35	1.35	1.35	1.35	1.35	1.35	1.35	1.35	1.35	1.35
b) INSPECT AND REPAIR, EQUIPMENT	ST. Glass Area	2.47	2.47	2.47	2.47	2.47	2.47	2.47	2.47	2.47	2.47
c) Wall Areas	ST. Wall Area	2.27	2.27	2.63	1.43	1.35	1.35	1.35	1.35	1.35	1.35
d) INSPECT AND REPAIR, EQUIPMENT	ST. Wall Area	2.73	2.73	3.44	3.44	3.44	3.44	3.44	3.44	3.44	3.44
e) Walls below Grade	ST. Wall Area	4.20	4.20	6.40	6.40	6.40	6.40	6.40	6.40	6.40	6.40
f) Walls above Grade	ST. Wall Area	5.54	5.54	6.40	6.40	6.40	6.40	6.40	6.40	6.40	6.40
g) Windows	ST. Window Area	22.29	22.29	21.79	21.79	21.79	21.79	21.79	21.79	21.79	21.79
h) Exterior Paint, Entrances, Jewelers	ST. Exterior Area	16.02	16.02	24.42	24.42	24.42	24.42	24.42	24.42	24.42	24.42
i) Projections, Balconies etc.	ST. Project Area	2.91	2.91	4.35	2.51	2.51	2.51	2.51	2.51	2.51	2.51
j) INSPECT AND REPAIR, EQUIPMENT	ST. Project. Areas	2.45	2.45	2.39	2.39	2.39	2.39	2.39	2.39	2.39	2.39
k) Partitions	ST. Part. Areas	2.67	2.67	2.67	2.67	2.67	2.67	2.67	2.67	2.67	2.67
l) Folding, Clinton, Panels, Screens	ST. Part. Areas	16.28	16.28	16.28	16.28	16.28	16.28	16.28	16.28	16.28	16.28
m) Other	ST. Other	—	—	—	—	—	—	—	—	—	—

**Hanscomb
Roy
Associates**

OBJECTS OF ANARCHY INSTRUMENTS - CRAFTS



TYPE AND DATE PAPER

ITEM	TYPE OF ARTICLE OR ITEM	DATE OF MANUFACTURE	CRAFTS		INSTRUMENTS		TYPE AND DATE PAPER	
			PERIOD MANUFACTURE	PERIOD MANUFACTURE	PERIOD MANUFACTURE	PERIOD MANUFACTURE	PERIOD MANUFACTURE	PERIOD MANUFACTURE
1. CLOTHING, 24 JULY 1945	New Fibre/Fab.	24 JULY 1945	1945 1945	1945 1945	1945 1945	1945 1945	1945 1945	1945 1945
(1) Clothing, 24 JULY 1945	Old Fibre/Fab.	24 JULY 1945	-	-	-	-	-	-
(2) Clothing, 24 JULY 1945	Per Star/Fir.	24 JULY 1945	-	-	-	-	-	-
(3) Clothing, 24 JULY 1945	Per Fiber	24 JULY 1945	-	-	-	-	-	-
2. CLOTHING, 24 JULY 1945								
(1) Fibers	COT. Finishe	1.50	1.50	1.40	1.50	1.50	1.50	1.50
(2) Clothing	COT. Finishe	1.50	1.50	1.40	1.50	1.50	1.50	1.50
(3) Clothing	COT. Finishe	1.50	1.50	1.40	1.50	1.50	1.50	1.50
(4) Clothing	COT. Finishe	1.50	1.50	1.40	1.50	1.50	1.50	1.50
3. CLOTHING, 24 JULY 1945								
(1) Non-Instrumental	Per ST. 1945	6.37	6.37	6.40	6.36	6.36	6.37	6.37
(2) Non-Instrumental	Per ST. 1945	6.37	6.37	6.40	6.36	6.36	6.37	6.37
4. CLOTHING								
(1) Garments	Per Suit Per Apron	1945-50	1945-50	1945-50	1945-50	1945-50	1945-50	1945-50
(2) Garments	Per Suit Per Apron	1945-50	1945-50	1945-50	1945-50	1945-50	1945-50	1945-50

**Hanscomb
Roy Associates**